

PROJECT: B-5808

**STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION**

**SIGNING PLAN
CABARRUS COUNTY**

LOCATION: BRIDGES #057 & #059 OVER IRISH BUFFALO CREEK ON US 29 /US 601

TIP NO. B-5808	SHEET NO. SIGN-1
APPROVED: _____	
DATE: 2/20/2023	
SEAL	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	SIGNING PLAN COVER SHEET
SIGN-2 THRU SIGN-4	SIGNAGE DETAILS

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4072000000	SUPPORTS, 3-LB STEEL U-CHANNEL	215	LF
4102000000	SIGN ERECTION, TYPE E	1	EA
4116100000	SIGN ERECTION, RELOCATE TYPE D (GROUND MOUNTED)	1	EA
4116100000	SIGN ERECTION, RELOCATE TYPE E (GROUND MOUNTED)	6	EA
4116100000	SIGN ERECTION, RELOCATE TYPE F (GROUND MOUNTED)	3	EA
4192000000	DISPOSAL OF SUPPORT, U-CHANNEL	10	EA

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
903.10	GROUND MOUNTED SIGN SUPPORTS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE "D", "E", AND "F" SIGNS ON "U" CHANNEL POSTS
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

SIGNING GENERAL NOTES

- A) IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE / CITY MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONSTRUCTION SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- B) SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING OR PAVEMENT MARKINGS. SEE TRANSPORTATION MANAGEMENT AND PAVEMENT MARKING PLANS.
- C) WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER.
- D) WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- E) THE BACKGROUND FOR TYPE "E" SIGNS SHALL BE TYPE "C" REFLECTIVE SHEETING.

TYPE "E" SIGNS

401 QUANTITY REQ'D = 1
ONE "U" POST PER SIGN

**RIGHT LANE
MUST
TURN RIGHT**

**R3-7R
30" X 30"**

**PLAN PREPARED BY:
STV Engineers, Inc.**

NIKKI T. HONEYCUTT, PE	TRAFFIC ENGINEER
CLARK GROVES	TRANSPORTATION DESIGNER

