


### EDI MODEL 2018ECL-NC CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Connect serial cable from conflict monitor to comm. port 1 of 2070 controller. Ensure conflict monitor communicates with 2070.

■ = DENOTES POSITION OF SWITCH

### NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Program phases 4 and 8 for Dual Entry.
3. Program controller to start up in phase 2 Green and 6 Green.
4. If this signal will be managed by an ATMS software, enable controller and detector logging for all detectors used at this location.
5. The cabinet and controller are part of the City of Concord Central System.

### EQUIPMENT INFORMATION

CONTROLLER.....2070  
 CABINET.....332  
 SOFTWARE.....ECONOLITE ASC/3-2070  
 CABINET MOUNT.....BASE  
 OUTPUT FILE POSITIONS...12  
 LOAD SWITCHES USED.....S2,S5,S8,S11  
 PHASES USED.....2,4,6,8  
 OVERLAPS.....NONE


### SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED
SIGNAL HEAD NO.	NU	21,22	NU	NU	41,42	NU	NU	61,62	NU	NU	81,82	NU
RED		128			101			134			107	
YELLOW		129			102			135			108	
GREEN		130			103			136			109	
RED ARROW												
YELLOW ARROW												
GREEN ARROW												

NU = Not Used

### INPUT FILE POSITION LAYOUT


(front view)



### INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND TIME	DELAY TIME	ADDED INITIAL	DETECTOR TYPE
2A	TB2-5,6	I2U	39	2	2	YES			X	N
2B	TB2-7,8	I2L	43	12	2	YES			X	N
4A	TB4-9,10	I6U	41	4	4	YES				N
4B	TB4-11,12	I6L	45	14	4	YES		10		N
4C	TB6-1,2	I7U	65	34	4	YES		15		N
8A	TB5-9,10	J6U	42	8	8	YES				N
8B	TB5-11,12	J6L	46	18	8	YES		15		N


INPUT FILE POSITION LEGEND: J2L



### SPECIAL DETECTOR NOTE

For detectors 6A, 6B, 6C and 6D install a video detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer-approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

### TYPICAL OPTICOM FIELD WIRE DETAIL



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 10-0446T1  
 DESIGNED: January 2022  
 SEALED: 1/14/2022  
 REVISED:

Electrical Detail - Temp 1 - Sheet 1 of 2

Prepared In the Offices of:  
 G.L. Transportation, Mobility and Safety Division  
 NORTH CAROLINA DEPARTMENT OF TRANSPORTATION  
 Signal Management Section  
 750 N. Greenfield Pkwy, Garner, NC 27529

US 29-601 (Concord Parkway North) at SR 1394 (Poplar Tent Rd) / McGill Avenue

Division 10 Cabarrus County Concord

PLAN DATE: January 2022 REVIEWED BY: T. Joyce

PREPARED BY: C. Strickland REVIEWED BY:

REVISIONS INIT. DATE

DocuSigned by: D. Todd Joyce 01/18/2022

SIG. INVENTORY NO. 10-0446T1

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL  
 NORTH CAROLINA DEPARTMENT OF TRANSPORTATION  
 PROFESSIONAL ENGINEER  
 SEAL 031001  
 D. TODD JOYCE

14-1116-2022 10:52  
 S:\IT\ASST\TIS\Sig\Signal\work\hous\51g\_MonPrj\Projects From Signal Design\Active Projects\10-0446\_Sm\elc\_xxx.dgn  
 C:\Users\cstrickland