


TIP PROJECT: BR-0073

CONTRACT: C204795




See Sheet 1A For Index of Sheets



STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

COLUMBUS COUNTY


LOCATION: *BRIDGE NO. 230005 ON US 76 OVER GAPWAY SWAMP*
 TYPE OF WORK: *GRADING, DRAINAGE, PAVING, & STRUCTURE*



4

THERE IS NO CONTROL OF ACCESS ON THIS PROJECT.

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED



DESIGN DATA

ADT 2023 =	1,057
ADT 2045 =	1,400
K =	N/A
D =	N/A
T =	9% *
V =	60 MPH
* TTST =	5% DUALS = 4%
FUNC CLASS =	PRINCIPAL ARTERIAL
STATEWIDE TIER	

PROJECT LENGTH

LENGTH ROADWAY TIP PROJECT BR-0073	=	0.171 MILES
LENGTH STRUCTURES TIP PROJECT BR-0073	=	0.031 MILES
TOTAL LENGTH TIP PROJECT BR-0073	=	0.202 MILES

PLANS PREPARED BY:
wsp
434 FAYETTEVILLE ST. #1500
RALEIGH, N.C. 27601
NC ENG. F. 1253
2018 STANDARD SPECIFICATIONS

RIGHT OF WAY DATE:
MAY 31, 2022

LETTING DATE:
APRIL 18, 2023

PLANS PREPARED FOR:
DIVISION OF HIGHWAYS
STRUCTURES MGMT UNIT
1000 BIRCH RIDGE DRIVE
RALEIGH, NC 27610

CHRISTOPHER H. LEE, PE
PROJECT ENGINEER


DAVID STUTTS, PE
PROJECT ENGINEER - PEP/PROGRAM MGMT

HYDRAULICS ENGINEER

(Signature)
P.E.

ROADWAY DESIGN ENGINEER

(Signature)
P.E.



INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1A	INDEX OF SHEETS, GENERAL NOTES, AND STANDARD DRAWINGS
1B	CONVENTIONAL SYMBOLS
2A-1	PAVEMENT SCHEDULE, TYPICAL SECTIONS, AND DETAILS FOR WEDGING, MILLING, & SHOULDER BERM GUTTER
2C-1	SPECIAL DETAIL FOR GUARDRAIL INSTALLATION
2C-2	GREU TYPE TL-3 DETAILS
3B-1	ROADWAY SUMMARIES
3D-1	DRAINAGE SUMMARY
3G-1	GEOTECHNICAL SUMMARIES
4	PLAN AND PROFILE SHEET
RW01-1 THRU RW-04	SURVEY CONTROL, EXISTING CENTERLINES, RIGHT OF WAY, EASEMENTS, AND PROPERTY TIES
TMP-1 THRU TMP-4	TRAFFIC MANAGEMENT PLANS
PMP-1 AND PMP-2	PAVEMENT MARKING PLANS
EC-1 THRU EC-5	EROSION CONTROL PLANS
X1-A	CROSS-SECTION SUMMARY
X-1 THRU X-12	CROSS-SECTION PLANS
1 THRU 6	PAVEMENT RESURFACING PLANS
S-1 THRU S-39	STRUCTURES PLANS

GENERAL NOTES: 2018 SPECIFICATIONS

EFFECTIVE: 01-16-2018
REVISED:

EFF. 01-16-2018
REV.

GRADE LINE:
GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01

SIDE ROADS:

THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

SUBSURFACE DRAINS:

SUBSURFACE DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 815.02 AT LOCATIONS DIRECTED BY THE ENGINEER.

DRIVEWAYS:

DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. 848.03 AT LOCATIONS SHOWN ON PLANS OR AS DIRECTED BY THE ENGINEER.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

END BENTS:

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE Riverstreet Networks
ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

RIGHT-OF-WAY MARKERS:

ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY OTHERS.

2018 ROADWAY ENGLISH STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" HIGHWAY DESIGN BRANCH - N. C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N. C., DATED JANUARY, 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:


STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	METHOD OF CLEARING - METHOD II
225.02	GUIDE FOR GRADING SUBGRADE - SECONDARY AND LOCAL
225.04	METHOD OF OBTAINING SUPERELEVATION - TWO LANE PAVEMENT
DIVISION 3 - PIPE CULVERTS	
300.01	METHOD OF PIPE INSTALLATION
DIVISION 4 - MAJOR STRUCTURES	
422.01	BRIDGE APPROACH FILLS - TYPE I STANDARD APPROACH FILL
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS	
560.01	METHOD OF SHOULDER CONSTRUCTION - HIGH SIDE OF SUPERELEVATED CURVE - METHOD I
DIVISION 6 - ASPHALT BASES AND PAVEMENTS	
654.01	PAVEMENT REPAIRS
DIVISION 8 - INCIDENTALS	
815.02	SUBSURFACE DRAIN
840.00	CONCRETE BASE PAD FOR DRAINAGE STRUCTURES
840.25	ANCHORAGE FOR FRAMES
840.29	FRAMES AND NARROW SLOT FLAT GRATES
840.35	TRAFFIC BEARING GRATED DROP INLET - FOR CAST IRON DOUBLE FRAME AND GRATES
840.46	TRAFFIC BEARING PRECAST DRAINAGE STRUCTURE
840.66	DRAINAGE STRUCTURE STEPS
862.01	GUARDRAIL PLACEMENT
862.02	GUARDRAIL INSTALLATION
862.03	STRUCTURE ANCHOR UNITS
876.02	GUIDE FOR RIP RAP AT PIPE OUTLETS
876.04	DRAINAGE DITCHES WITH CLASS 'B' RIP RAP

BR-0073

4RDI IA

ROADWAY DESIGN ENGINEER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



ROADWAY DESIGN UNIT

PREPARED BY

434 FAYETTEVILLE ST. #1500
RALEIGH, NC 27601
NC ENG P-1253

STATE OF NORTH CAROLINA, DIVISION OF HIGHWAYS CONVENTIONAL PLAN SHEET SYMBOLS

Note: Not to Scale

BOUNDARIES AND PROPERTY:

State Line	-----
County Line	-----
Township Line	-----
City Line	-----
Reservation Line	-----
Property Line	-----
Existing Iron Pin (EIP)	----- ○ EIP
Computed Property Corner	----- X
Existing Concrete Monument (ECM)	----- □ ECM
Parcel / Sequence Number	----- (23)
Existing Fence Line	----- -x-x-x-
Proposed Woven Wire Fence	----- ○
Proposed Chain Link Fence	----- □
Proposed Barbed Wire Fence	----- ◇
Existing Wetland Boundary	----- -MLB-
Proposed Wetland Boundary	----- MLB
Existing Endangered Animal Boundary	----- -EAB-
Existing Endangered Plant Boundary	----- -EPB-
Existing Historic Property Boundary	----- -HPB-
Known Contamination Area: Soil	----- -s-s-
Potential Contamination Area: Soil	----- -s-s-
Known Contamination Area: Water	----- -w-w-
Potential Contamination Area: Water	----- -w-w-
Contaminated Site: Known or Potential	----- ☠ ☡

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	----- ○
Sign	----- ○
Well	----- ♀
Small Mine	----- X
Foundation	----- □
Area Outline	----- □
Cemetery	----- □
Building	----- □
School	----- □
Church	----- □
Dam	----- ▬

HYDROLOGY:

Stream or Body of Water	-----
Hydro, Pool or Reservoir	----- □
Jurisdictional Stream	----- JS
Buffer Zone 1	----- BZ 1
Buffer Zone 2	----- BZ 2
Flow Arrow	----- ←
Disappearing Stream	----- >
Spring	----- ○
Wetland	----- ↓
Proposed Lateral, Tail, Head Ditch	----- ▬
False Sump	----- ▽

RAILROADS:

Standard Gauge	-----
RR Signal Milepost	----- ○ MILEPOST 35
Switch	----- □ SWITCH
RR Abandoned	----- - - - -
RR Dismantled	----- - - - -

RIGHT OF WAY & PROJECT CONTROL:

Primary Horiz Control Point	----- ○
Primary Horiz and Vert Control Point	----- ●
Secondary Horiz and Vert Control Point	----- ◆
Vertical Benchmark	----- ⊠
Existing Right of Way Monument	----- △
Proposed Right of Way Monument (Rebar and Cap)	----- ▲
Proposed Right of Way Monument (Concrete)	----- ●
Existing Permanent Easement Monument	----- ◇
Proposed Permanent Easement Monument (Rebar and Cap)	----- ◆
Existing C/A Monument	----- ▲
Proposed C/A Monument (Rebar and Cap)	----- ▲
Proposed C/A Monument (Concrete)	----- ●
Existing Right of Way Line	----- ▬
Proposed Right of Way Line	----- ▬
Existing Control of Access Line	----- (C/A)
Proposed Control of Access Line	----- (C/A)
Proposed ROW and CA Line	----- ▬
Existing Easement Line	----- E
Proposed Temporary Construction Easement	----- E
Proposed Temporary Drainage Easement	----- TDE
Proposed Permanent Drainage Easement	----- PDE
Proposed Permanent Drainage/Utility Easement	----- DUE
Proposed Permanent Utility Easement	----- PUE
Proposed Temporary Utility Easement	----- TUE
Proposed Aerial Utility Easement	----- AUE

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	-----
Existing Curb	-----
Proposed Slope Stakes Cut	----- C
Proposed Slope Stakes Fill	----- F
Proposed Curb Ramp	----- (CR)
Existing Metal Guardrail	----- ▬
Proposed Guardrail	----- ▬
Existing Cable Guiderail	----- ▬
Proposed Cable Guiderail	----- ▬
Equality Symbol	----- ⊕
Pavement Removal	----- ▬

VEGETATION:

Single Tree	----- ☼
Single Shrub	----- ☼
Hedge	----- ▬

Woods Line	-----
Orchard	----- ☼ ☼ ☼ ☼
Vineyard	----- ▬ Vineyard

EXISTING STRUCTURES:

MAJOR:	
Bridge, Tunnel or Box Culvert	----- CONC
Bridge Wing Wall, Head Wall and End Wall	-----) CONC WW (
MINOR:	
Head and End Wall	----- CONC HW
Pipe Culvert	-----
Footbridge	-----
Drainage Box: Catch Basin, DI or JB	----- □ CB
Paved Ditch Gutter	-----
Storm Sewer Manhole	----- ⊙
Storm Sewer	----- S

UTILITIES:

* SUE - Subsurface Utility Engineering
LOS - Level of Service - A,B,C or D (Accuracy)

POWER:	
Existing Power Pole	----- ●
Proposed Power Pole	----- ○
Existing Joint Use Pole	----- ●
Proposed Joint Use Pole	----- ○
Power Manhole	----- ⊙
Power Line Tower	----- ⊠
Power Transformer	----- ⊠
U/G Power Cable Hand Hole	----- □
H-Frame Pole	----- ●
U/G Power Line Test Hole (SUE - LOS A)*	----- ●
U/G Power Line (SUE - LOS B)*	----- P
U/G Power Line (SUE - LOS C)*	----- P
U/G Power Line (SUE - LOS D)*	----- P

TELEPHONE:

Existing Telephone Pole	----- ●
Proposed Telephone Pole	----- ○
Telephone Manhole	----- ⊙
Telephone Pedestal	----- ⊠
Telephone Cell Tower	----- ⊠
U/G Telephone Cable Hand Hole	----- □
U/G Telephone Test Hole (SUE - LOS A)*	----- ●
U/G Telephone Cable (SUE - LOS B)*	----- T
U/G Telephone Cable (SUE - LOS C)*	----- T
U/G Telephone Cable (SUE - LOS D)*	----- T
U/G Telephone Conduit (SUE - LOS B)*	----- TC
U/G Telephone Conduit (SUE - LOS C)*	----- TC
U/G Telephone Conduit (SUE - LOS D)*	----- TC
U/G Fiber Optics Cable (SUE - LOS B)*	----- T FO
U/G Fiber Optics Cable (SUE - LOS C)*	----- T FO
U/G Fiber Optics Cable (SUE - LOS D)*	----- T FO

WATER:

Water Manhole	----- ⊙
Water Meter	----- ○
Water Valve	----- ⊗
Water Hydrant	----- ⊕
U/G Water Line Test Hole (SUE - LOS A)*	----- ●
U/G Water Line (SUE - LOS B)*	----- W
U/G Water Line (SUE - LOS C)*	----- W
U/G Water Line (SUE - LOS D)*	----- W
Above Ground Water Line	----- A/G Water

TV:

TV Pedestal	----- ⊠
TV Tower	----- ⊗
U/G TV Cable Hand Hole	----- □
U/G TV Test Hole (SUE - LOS A)*	----- ●
U/G TV Cable (SUE - LOS B)*	----- TV
U/G TV Cable (SUE - LOS C)*	----- TV
U/G TV Cable (SUE - LOS D)*	----- TV
U/G Fiber Optic Cable (SUE - LOS B)*	----- TV FO
U/G Fiber Optic Cable (SUE - LOS C)*	----- TV FO
U/G Fiber Optic Cable (SUE - LOS D)*	----- TV FO

GAS:


Gas Valve	----- ◇
Gas Meter	----- ⊕
U/G Gas Line Test Hole (SUE - LOS A)*	----- ●
U/G Gas Line (SUE - LOS B)*	----- G
U/G Gas Line (SUE - LOS C)*	----- G
U/G Gas Line (SUE - LOS D)*	----- G
Above Ground Gas Line	----- A/G Gas

SANITARY SEWER:

Sanitary Sewer Manhole	----- ⊙
Sanitary Sewer Cleanout	----- ⊕
U/G Sanitary Sewer Line	----- SS
Above Ground Sanitary Sewer	----- A/G Sanitary Sewer
SS Force Main Line Test Hole (SUE - LOS A)*	----- ●
SS Force Main Line (SUE - LOS B)*	----- FSS
SS Force Main Line (SUE - LOS C)*	----- FSS
SS Force Main Line (SUE - LOS D)*	----- FSS

MISCELLANEOUS:

Utility Pole	----- ●
Utility Pole with Base	----- □
Utility Located Object	----- ○
Utility Traffic Signal Box	----- ⊠
Utility Unknown U/G Line (SUE - LOS B)*	----- TUL
U/G Tank; Water, Gas, Oil	----- □
Underground Storage Tank, Approx. Loc.	----- (UST)
A/G Tank; Water, Gas, Oil	----- □
Geoenvironmental Boring	----- ●
Abandoned According to Utility Records	----- AATUR
End of Information	----- E.O.I.




TYPICAL SECTION NO. 1

- * 11' WITH GUARDRAIL
- * VARIABLE SLOPE

USE TYPICAL SECTION NO. 1 AS FOLLOWS:

- L- STA. 12+30.00 TO 15+00.00
- L- STA. 21+00.00 TO 23+17.66

NOTE: SHOULDER WORK ONLY FOR
-L- STA. 22+96.00 TO 23+17.66




TYPICAL SECTION NO. 2


- * 11' WITH GUARDRAIL
- * VARIABLE SLOPE

USE TYPICAL SECTION NO. 2 AS FOLLOWS:


- L- STA. 15+00.00 TO 17+42.00 (BEGIN BRIDGE)
- L- STA. 19+07.00 (END BRIDGE) TO 21+00.00



DETAIL SHOWING METHOD OF WEDGING NO. 1




WEDGING DETAIL FOR RESURFACING



BRIDGE SKETCH NO. 1

USE BRIDGE TYPICAL SECTION AS FOLLOWS:


- L- STA. 17+42.00 (BEGIN BRIDGE) TO
- L- STA. 19+07.00 (END BRIDGE)



TYPICAL SECTION NO. 3


USE TYPICAL SECTION NO. 3 AS FOLLOWS:

- DR1- STA. 10+14.00 TO 12+55.17



TYPICAL SECTION FOR SHOULDER BERM GUTTER

- L- STA 16+36.66 TO -L- STA 17+11.47 LT
- L- STA 19+23.87 TO -L- STA 19+33.86 LT



INCIDENTAL MILLING OF EXISTING PAVEMENT AS DIRECTED BY ENGINEER

- L- STA 12+30.00 TO -L- STA 13+05.00
- L- STA 22+21.00 TO -L- STA 22+96.00


NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.

BR-0073
4RD1 2A-1
ROADWAY DESIGN ENGINEER
3/13/2023
SEAL 04789
PROFESSOR
CHRISTOPHER H. LEE
CHATELAIN, INC.
PAVEMENT DESIGN ENGINEER
3/13/2023
SEAL 022896
PROFESSOR
CLARK S. MORRISON
MORRISON, S. MORRISON & ASSOCIATES, INC.
CLARK S. MORRISON
STATE OF NORTH CAROLINA
ROADWAY DESIGN UNIT
PREPARED BY
WSP
434 FAYETTEVILLE ST., #1500
RALEIGH, N.C. 27601
NC ENG P-1253

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 6 OF 8
862D02





PROJECT REFERENCE NO.	SHEET NO.
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR
GUARDRAIL INSTALLATION

SHEET 6 OF 8
862D02



**CONTRACTS STANDARDS
AND DEVELOPMENT UNIT**
Office 919-707-6950 FAX 919-250-4119


SEE TITLE BLOCK

ORIGINAL BY: J. HOWERTON	DATE: 3-7-2018
MODIFIED BY:	DATE:
CHECKED BY:	DATE:
FILE SPEC.:	

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR STRUCTURE ANCHOR UNITS GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE

SHEET 1 OF 7 862D03



ELEVATION

NOTE:
**POST NOT REQUIRED FOR SKEW ANGLES GREATER THAN 150° OR LESS THAN 30° UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
*THE DISTANCE FROM END OF BRIDGE RAIL TO CENTER LINE OF THE FIRST POST SHOULD BE 11 1/2" IF CONCRETE BACKWALL IS NOT PRESENT.
-SHOULDER BERM GUTTER MUST BE INSTALLED TO THE LIMITS 8' x 4" LIP CURB IS SHOWN IF ANCHOR UNIT IS NOT ADJACENT TO AN APPROACH SLAB.
-MEASURE GUARDRAIL HEIGHT FROM THE TOP OF ADJACENT SURFACE (SHOULDER, BERM, OR GUTTER).
-LAP JOINTS IN THE DIRECTION OF TRAFFIC FLOW.
-SEE SHEET 3 FOR POST SECTIONS 1 THRU 9.



PLAN VIEW

GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE

SHEET 1 OF 7 862D03


STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR STRUCTURE ANCHOR UNITS GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.


ROADWAY DETAIL DRAWING FOR STRUCTURE ANCHOR UNITS GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE - SUB REGIONAL TIER

SHEET 2 OF 7 862D03



ELEVATION

NOTE:
**POST NOT REQUIRED FOR SKEW ANGLES GREATER THAN 150° OR LESS THAN 30° UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
*THE DISTANCE FROM END OF BRIDGE RAIL TO CENTER LINE OF THE FIRST POST SHOULD BE 11 1/2" IF CONCRETE BACKWALL IS NOT PRESENT.
-SHOULDER BERM GUTTER MUST BE INSTALLED TO THE LIMITS 8' x 4" LIP CURB IS SHOWN IF ANCHOR UNIT IS NOT ADJACENT TO AN APPROACH SLAB.
-MEASURE GUARDRAIL HEIGHT FROM THE TOP OF ADJACENT SURFACE (SHOULDER, BERM, OR GUTTER).
-LAP JOINTS IN THE DIRECTION OF TRAFFIC FLOW.
-SEE SHEET 3 FOR POST SECTIONS 1 THRU 9.



PLAN VIEW


GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE - SUB REGIONAL TIER

SHEET 2 OF 7 862D03

STATE OF NORTH CAROLINA DEPT. OF TRANSPORTATION DIVISION OF HIGHWAYS RALEIGH, N.C.

ROADWAY DETAIL DRAWING FOR STRUCTURE ANCHOR UNITS GUARDRAIL ANCHOR UNIT, TYPE III FOR ATTACHMENT TO RAIL ON BRIDGE - SUB REGIONAL TIER

PROJECT REFERENCE NO. SHEET NO.



CONTRACT STANDARDS AND DEVELOPMENT UNIT Office 919-707-6950 FAX 919-250-4119
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
ORIGINAL BY: J. HOWERTON DATE: 06-22-12
MODIFIED BY: DATE:
CHECKED BY: DATE:
FILE SPEC.:
SEE TITLE BLOCK

BR-0073
4RD1 2C-2
ROADWAY DESIGN ENGINEER
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
STATE OF NORTH CAROLINA
ROADWAY DESIGN UNIT
PREPARED BY WSP
434 FAYETTEVILLE ST. #1500 RALEIGH, NC 27601 NC ENG P-1253

SUMMARY OF BREAKING EXISTING ASPHALT PAVEMENT

SURVEY LINE	STATION	STATION	LOCATION L/R/T/CL	YD ²
-L-	16+00.00	17+10.00	CLRT	276.97
-L-	19+40.00	20+50.00	LTCL	275.16
TOTAL:				552.13
SAY:				580

ASPHALT PAVEMENT REMOVAL SUMMARY

SURVEY LINE	STATION	STATION	LOCATION L/R/T/CL	YD ²
-L-	15+00.00	16+00.00	CL	248.25
-L-	17+10.00	17+59.00	CL	109.68
-L-	18+92.00	19+40.00	CL	106.05
-L-	20+50.00	21+00.00	CL	123.77
TOTAL:				587.75
SAY:				620

SHOULDER BERM GUTTER SUMMARY

SURVEY LINE	STATION	STATION	LENGTH
-L-	16+36.66(LT)	17+11.47(LT)	74.81
-L-	19+23.87(LT)	19+33.86(LT)	9.99
TOTAL:			84.80
SAY:			90

SUMMARY OF EARTHWORK
(VOLUMES IN CY)

LINE	STATION	STATION	UNCL. EXCAV.	EMBANK. +%	BORROW	WASTE
(BEG. BRIDGE)						
-L-	12+30.00	17+42.00	138	2,665	2,527	
-DR1-	10+14.00	12+55.71	13	844	831	
SUBTOTALS:			151	3,509	3,358	
(END BRIDGE)						
-L-	19+07.00	23+17.00	168	3,766	3,598	
SUBTOTALS:			168	3,766	3,598	
TOTALS:			319	7,275	6,956	
MATERIAL FOR SHOULDER CONSTRUCTION				356	356	
PROJECT TOTALS:			319	7,631	7,312	
EST. 5% TO REPLACE TOPSOIL ON BORROW PIT						366
GRAND TOTALS:			319	7,631	7,678	
SAY:			350		8,450	

PAVEMENT STRUCTURE VOLUME = 1,195 CY
PER GEOTECH RECOMMENDATIONS DATED FEB. 2, 2022, ESTIMATED 300 CUBIC YARDS OF UNDERCUT TO BE USED AT THE DISCRETION OF THE RESIDENT ENGINEER.

Note: Earthwork quantities are calculated by WSP USA E&I, Inc. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.

Note: Approximate quantities only. Clearing and Grubbing, Unclassified Excavation, Fine Grading, Removal of Existing Asphalt Pavement, and Breaking of Existing Asphalt Pavement will be paid for at the contract lump sum price for "Grading."

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL.
TOTAL SHOULDER WIDTH = DISTANCE FROM EDGE OF TRAVEL LANE TO SHOULDER BREAK POINT.
FLARE LENGTH = DISTANCE FROM LAST SECTION OF PARALLEL GUARDRAIL TO END OF GUARDRAIL.
W = TOTAL WIDTH OF FLARE FROM BEGINNING OF TAPER TO END OF GUARDRAIL.
G = GATING IMPACT ATTENUATOR TYPE 350
NG = NON-GATING IMPACT ATTENUATOR TYPE 350

GUARDRAIL SUMMARY

SURVEY LINE	BEG. STA.	END STA.	LOCATION	LENGTH			WARRANT POINT		"N" DIST. FROM E.O.L.	TOTAL SHOUL. WIDTH	FLARE LENGTH		W		ANCHORS						IMPACT ATTENUATOR TYPE 350			SINGLE FACED GUARDRAIL	REMOVE EXISTING GUARDRAIL	REMOVE AND STOCKPILE EXISTING GUARDRAIL	REMARKS								
				STRAIGHT	SHOP CURVED	DOUBLE FACED	APPROACH END	TRAILING END			APPROACH END	TRAILING END	GREU TL-3	III	B-77	CAT-1	AT-1											EA	G	NG					
-L-	14+39.135	17+49.51	RT	310.375			17+49.51		8	11	50		1							1											270.7				
-L-	15+86.565	17+34.44	LT	147.875				17+34.44	8	11		125		2.5						1											101.8				
-L-	18+98.85	22+09.225	LT	310.375			18+98.85		8	11	50		1							1											303.0				
-L-	19+15.10	22+87.975	RT	372.875				19+15.10	8	11		50		1						1											127.0				
SUBTOTALS				1,141.500					8	11										4											802.5				
ANCHOR DEDUCTIONS:																																			
				4 B-77 @ 22.875	-91.50																														
				4 GREU @ 50.00	-200.00																														
TOTALS:				850.00																	4												825.0		
SAY:				875.00																4															
ADDITIONAL GUARDRAIL POSTS = 5 EA																																			

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA



ROADWAY DESIGN UNIT

PREPARED BY



434 FAYETTEVILLE ST. #1500
RALEIGH, N.C. 27601
NC ENG P-1253

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

**STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS**

SUMMARY OF SUBSURFACE DRAINAGE

LINE	Station	Station	Location LT/RT/CL	Drain Type* UD/BD/SD	LF
CONTINGENCY				SD	200
				TOTAL LF:	200

*UD = Underdrain
 *BD = Blind Drain
 *SD = Subsurface Drain

SUMMARY OF GEOTEXTILE
 FOR PAVEMENT STABILIZATION

LINE	Station	Station	Geotextile for Pavement Stabilization SY	Class IV Subgrade Stabilization TONS
CONTINGENCY				
			TOTAL SY/TONS:	0 0*

*Total tons of "Class IV Subgrade Stabilization" is only the estimated quantity for pavement stabilization and may only represent a portion of the subgrade stabilization quantity shown in the Item Sheets of the Proposal.

SUMMARY OF AGGREGATE SUBGRADE/STABILIZATION

LINE	Station	Station	Aggregate Type* ASU(1/2)/AST	Aggregate Thickness INCHES [8" for ASU(2)]	Shallow Undercut CY	Class IV Subgrade Stabilization TONS	Geotextile for Soil Stabilization SY	Stabilizer Aggregate TONS	Class IV Aggregate Stabilization TONS
CONTINGENCY									
			TOTAL CY/TONS/SY:		0	0**	0**	0	0

*ASU(1/2) = Aggregate Subgrade (Type 1 or 2)
 *AST = Aggregate Stabilization
 **Total tons of "Class IV Subgrade Stabilization" and total square yards of "Geotextile for Soil Stabilization" are only the estimated quantities for ASU(1/2)/AST and may only represent a portion of the subgrade stabilization and geotextile quantities shown in the Item Sheets of the Proposal.

SUMMARY OF ROCK PLATING

LINE	Beginning Slope (H:V)	Approx. Station	Ending Slope (H:V)	Approx. Station	Location LT/RT	Rock Plating Detail No. 1/2/3/4	Riprap Class* 1/2/B	Rock Plating SY
							TOTAL SY:	0

*Use Class 1, 2 or B riprap if riprap class is not shown for rock plating location.

SUMMARY OF REINFORCED SOIL SLOPES AND SLOPE EROSION CONTROL

LINE	Beginning Slope/ RSS (H:V)	Approx. Station	Ending Slope/ RSS (H:V)	Approx. Station	Location LT/RT	Reinforced Soil Slope (RSS) SY	Geocells SY	Coir Fiber Mat SY	Matting for Erosion Control SY
						TOTAL SY:	0	0	0* 0**

*Total square yards of "Coir Fiber Mat" is only the estimated quantity for slopes steeper than 2:1 (H:V) and may only represent a portion of the coir fiber mat quantity shown in the Item Sheets of the Proposal.
 **Total square yards of "Matting for Erosion Control" is only the estimated quantity for RSS and may only represent a portion of the matting quantity shown in the Item Sheets of the Proposal.

SUMMARY OF PRE-SPLITTING OF ROCK

LINE	Beginning Rock Cut Slope (H:V)	Approx. Station	Ending Rock Cut Slope (H:V)	Approx. Station	Location LT/RT	Pre-splitting of Rock SY
					TOTAL SY:	0

SUMMARY OF SURCHARGES
 AND SURCHARGE WAITING PERIODS

LINE	Station	Station	Surcharge Height FT	MONTHS

SUMMARY OF
 SETTLEMENT GAUGES


Gauge No.	LINE and Station	Offset	
		Distance FT	Direction LT/RT
TOTAL GAUGES (EACH):			

SUMMARY OF EMBANKMENT
 WAITING PERIODS

LINE	Station	Station	MONTHS

SUMMARY OF BRIDGE WAITING PERIODS

Bridge Description	End Bent/ Bent No.	MONTHS



BR-0073
4RDI 004
ROADWAY DESIGN ENGINEER

STATE OF NORTH CAROLINA
REGISTERED PROFESSIONAL ENGINEER
SEAL
047089
CHRISTOPHER H. LEE
11/7/2023

HYDRAULICS ENGINEER

STATE OF NORTH CAROLINA
REGISTERED PROFESSIONAL ENGINEER
SEAL
29185
RICHARD L. HINES
11/7/2023

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
STATE OF NORTH CAROLINA

ROADWAY DESIGN UNIT

PREPARED BY
wsp
434 FAYETTEVILLE ST. #1500
RALEIGH, N.C. 27601
NC ENG P-1253

PRELIMINARY PLANS
DO NOT USE FOR CONSTRUCTION

REVISIONS

