

PROJECT NO.	SHEET NO.	TOTAL NO.
2023CPT.09.01.10291	10	
2023CPT.09.02.20291		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1220000000-E	1245000000-E	1260000000-E	1297000000-E	1308000000-E	1330000000-E	1519000000-E	1523000000-E	1575000000-E	1704000000-E	1840000000-E	2830000000-N	2845000000-N	5255000000-N		
												INCIDENTAL STONE BASE	SHOULDER RECONSTRUCTION	AGGREGATE SHOULDER BORROW	MILLING ASPHALT PAVEMENT, 1 1/2" DEPTH	MILLING ASPHALT PAVEMENT, 0" TO 1 1/2" DEPTH	INCIDENTAL MILLING	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	ADJ. OF MANHOLES	ADJ. OF METER OR VALVE BOX	PORTABLE LIGHTING		
											MI	FT	TONS	SMI	TONS	SY	SY	SY	TONS	TONS	TONS	TONS	LF	EA	EA	LS	
2023CPT.09.01.10291	Davidson	1	US-64	FROM BRIDGE #063 TO CHILDRESSES VINEYARD RD	1	2,3	MD	NO	NO	6	29-44	275	12.00	2,316	110,051	1,300	5,821		10,669	641	10	91,650	1	1			
TOTAL FOR MAP NO. 1											6		275	12.00	2,316	110,051	1,300	5,821		10,669	641	10	91,650	1	1		
2023CPT.09.01.10291	Davidson	2	US-64	FROM CHILDRESS VINEYARD RD TO BRIDGE #039 INCLUDING TO PVT JOINT ON RAMP #51037 AND RAMP #5438	5	4,6	MD	NO	NO	1.1	14-53		2.20	425	47,450		4,605		4,786	288	10		1	1			
TOTAL FOR MAP NO. 2											1.1			2.20	425	47,450		4,605		4,786	288	10		1	1		
TOTAL FOR PROJ NO. 2023CPT.09.01.10291											7.1		275	14.20	2,741	157,501	1,300	10,426		15,455	929	20	91,650	2	2		
2023CPT.09.02.20291	Davidson	3	SR-1895 / US 29-70 SERVICE RD	FROM N MAIN ST SR3346 TO FAIR ST (NS)	3	2	2WU	NO	NO	0.24	22-27		0.48	93	8,019			360		25	10		1	1			
TOTAL FOR MAP NO. 3											0.24			0.48	93	8,019			360		25	10		1	1		
2023CPT.09.02.20291	Davidson	4	PIEDMONT DR SR1889/1890	FROM PVT JOINT APPROXIMATELY 1000' EAST OF 8TH ST INTERSECTION TO INTERSECTION OF FAIRGROUNDS RD (NS)	3	2	2WU	NO	NO	0.748	20-24	25	1.50	289	9,654		833	961		65	10		1	2	*		
TOTAL FOR MAP NO. 4											0.748		25	1.50	289	9,654		833	961		65	10		1	2		
2023CPT.09.02.20291	Davidson	5	PIEDMONT DR SR 1888	FROM FAIRGROUNDS RD TO CLEARVIEW ST SR1853	2	2	2WU	NO	NO	0.733	21	10	1.47	283			350	1,007		68	10		1	2			
TOTAL FOR MAP NO. 5											0.733		10	1.47	283			350	1,007		68	10		1	2		
2023CPT.09.02.20291	Davidson	6	LINWOOD-SOUTHMOUNT RD SR1396	FROM PVT JOINT AT INTERSECTION OF NC47 TO BRIDGE#0257	2	2	2WU	NO	NO	4.55	24-38	300	9.10	1,756	68,317		2,681		6,632	398	10		1	15			
TOTAL FOR MAP NO. 6											4.55		300	9.10	1,756	68,317		2,681		6,632	398	10		1	15		
2023CPT.09.02.20291	Davidson	7	OLD GREENSBORO RD SR1798	FROM NC109 TO NEW CONSTRUCTION JOINT SOUTH OF ROUNDABOUT	2	2,3	2WU	NO	NO	6.979	25-40	375	13.96	2,694	106,254		3,635		10,314	619	10		1	30			
TOTAL FOR MAP NO. 7											6.979		375	13.96	2,694	106,254		3,635		10,314	619	10		1	30		
2023CPT.09.02.20291	Davidson	8	EAST AND WEST HOLLY HILL RD SR2060	FROM NC62 TO PVMT JOINT AT KENDALL MILL RD SR2087	2	2,3	2WU	NO	NO	2.462	20-36	150	4.92	950	33,800		1,475		3,414	205	10		20	12			
TOTAL FOR MAP NO. 8											2.462		150	4.92	950	33,800		1,475		3,414	205	10		20	12		
TOTAL FOR PROJ NO. 2023CPT.09.02.20291											15.712		860	31.43	6,065	226,044		8,974		20,360	1,380	60		25	62	1	
GRAND TOTAL											22.812		1,135	45.63	8,806	383,545	1,300	19,400		2,328	35,815	2,309	80	91,650	27	64	1

Note: All quantities listed include turn lanes and are estimates; Payments will be based on actual field measurements and quantities recieved