PROJECT NO.	SHEET NO.	TOTAL NO.
I-5955	7	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1297000000-E MILLING ASPHALT PAVEMENT, ***"DEPTH (2")	1297000000-E MILLING ASPHALT PAVEMENT, ***"DEPTH (1 1/2")	1297000000-E MILLING ASPHALT PAVEMENT, ***"DEPTH (4")	1330000000-E INCIDENTAL MILLING	1503000000-E ASPHALT CONC INTERMEDIATE, TYPE I19.0C	1524200000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5D	1575000000-E ASPHALT BINDER FOR PLANT MIX	1577000000-E POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	1662000000-E OPEN-GRADED ASPHALT FRICTION	1840000000-E MILLED RUMBLE STRIPS	2364200000-N FRAME WITH TWO GRATES, STD 840.20	2473000000-N REMOVE AND REPLACE CONCRETE APRON	4600000000-N CONNECTED LANE CLOSURE DEVICE	5255000000-N PORTABLE LIGHTING	7444000000-E INDUCTIVE LOOP SAW CUT
										MI	FT	SY	SY	SY	SY	TONS	TON	TON	TONS	TON	LF	EA	EA	EA	LS	LF
45908.3.1	Guilford	1	I-40 EB	I-40 EB FROM BRIDGE OVER BUFFALO CREEK TO JOINT EAST OF E GATE CITY BLVD/E LEE ST	1	3		NO	NO	5.315	45	175,101			6,522		19,697		1,508	5,897	53,040					
			TOTAL FOR MAP NO. 1							**5.315**		**175,101**			**6,522**		**19,697**		**1,508**	**5,897**	**53,040**					
45908.3.1	Guilford	2	RAMP TO BUS 85 SB	I-40 EB RAMP TO BUS 85 SB	2	1		NO	NO	0.058	22		832				72		4							
			TOTAL FOR MAP NO. 2							**0.058**			**832**				**72**		**4**							
45908.3.1	Guilford	3	BUS 85 NB	BUS 85 NB TO I-40 EB	3	2		NO	NO	0.177	31	5,516			537		621		47	179	930					
			TOTAL FOR MAP NO. 3							**0.177**		**5,516**			**537**		**621**		**47**	**179**	**930**					
45908.3.1	Guilford	4	BUS 85 NB RAMP TO RANDLEMAN RD	BUS 85 NB RAMP TO RANDLEMAN RD	2,8,13	1		NO	NO	0.08	29		1,360				115		7							450
			TOTAL FOR MAP NO. 4							**0.08**			**1,360**				**115**		**7**							**450**
45908.3.1	Guilford	5	I-40 EB RAMP TO RANDLEMAN RD	I-40 EB RAMP TO RANDLEMAN RD	2,4	1		NO	NO	0.139	27		2,426				205		12							400
			TOTAL FOR MAP NO. 5							**0.139**			**2,426**				**205**		**12**							**400**
45908.3.1	Guilford	6	W PREDDY BLVD/RANDLEMAN RD RAMP TO I-40 EB	W PREDDY BLVD/RANDLEMAN RD RAMP TO I-40 EB	2,4,6	1		NO	NO	0.194	19		3,890				330		19							450
			TOTAL FOR MAP NO. 6							**0.194**			**3,890**				**330**		**19**							**450**
		6A	I-40 EB RAMP TO S ELM-EUGENE ST	I-40 EB RAMP TO S ELM-EUGENE ST	7,8	1		NO	NO	0.077	26		1,655				140		8							650
			TOTAL FOR MAP NO. 6A							**0.077**			**1,655**				**140**		**8**							**650**
45908.3.1	Guilford	7	S ELM-EUGENE ST RAMP TO I-40 EB	S ELM-EUGENE ST RAMP TO I-40 EB	8	1		NO	NO	0.092	21		1,296				110		6							
			TOTAL FOR MAP NO. 7							**0.092**			**1,296**				**110**		**6**							
45908.3.1	Guilford	8	I-40 EB OFF RAMP TO MLK JR DR	I-40 EB OFF RAMP TO MLK JR DR	8,9	1		NO	NO	0.152	28		3,684				312		18							650
			TOTAL FOR MAP NO. 8							**0.152**			**3,684**				**312**		**18**							**650**
45908.3.1	Guilford	9	MAP DELETED	MAP DELETED				NO	NO	0	1															
			TOTAL FOR MAP NO. 9							**0**																
45908.3.1	Guilford	10	MLK JR DR RAMP TO I-40 EB	MLK JR DR RAMP TO I-40 EB	10	2		NO	NO	0.365	27	6,974					789		46							
			TOTAL FOR MAP NO. 10							**0.365**		**6,974**					**789**		**46**							
45908.3.1	Guilford	11	MAP DELETED	MAP DELETED				NO	NO	0	1															
			TOTAL FOR MAP NO. 11							**0**																
45908.3.1	Guilford	12	I-40 EB RAMP TO E GATE CITY BLVD/E LEE ST	I-40 EB RAMP TO E GATE CITY BLVD/E LEE ST	2	1		NO	NO	0.258	24		3,806				322		19							425
			TOTAL FOR MAP NO. 12							**0.258**			**3,806**				**322**		**19**							**425**
45908.3.1	Guilford	13	E GATE CITY BLVD/E LEE ST RAMP TO I-40 EB	E GATE CITY BLVD/E LEE ST RAMP TO I-40 EB	5	1		NO	NO	0.316	33			3,054		436	258	21	15							
			TOTAL FOR MAP NO. 13							**0.316**				**3,054**		**436**	**258**	**21**	**15**			20	20	4	1	
45908.3.1	Guilford	14	I-40 WB	I-40 WB FROM JOINT EAST OF GATE CITY BLVD TO BRIDGE OVER BUFFALO CREEK	1	3		NO	NO	4.9	35	176,605			4,625		19,864		1,491	5,466	53,790					
			TOTAL FOR MAP NO. 14							**4.9**		**176,605**			**4,625**		**19,864**		**1,491**	**5,466**	**53,790**					
45908.3.1	Guilford	15	I-40 WB RAMP TO E GATE CITY BLVD	I-40 WB RAMP TO E GATE CITY BLVD	2,11	1		NO	NO	0.128	29		2,768				234		14							
			TOTAL FOR MAP NO. 15							**0.128**			**2,768**				**234**		**14**							
45908.3.1	Guilford	16	E GATE CITY BLVD RAMP TO I-40 WB	E GATE CITY BLVD RAMP TO I-40 WB	2	1		NO	NO	0.068	25		1,131				96		6							
			TOTAL FOR MAP NO. 16							**0.068**			**1,131**				**96**		**6**							
45908.3.1	Guilford	17	I-40 WB RAMP TO MLK JR DR	I-40 WB RAMP TO MLK JR DR	2,8,12	1		NO	NO	0.259	35		4,976				422		24		640					
			TOTAL FOR MAP NO. 17							**0.259**			**4,976**				**422**		**24**		**640**					
45908.3.1	Guilford	18	US 29 SB TO I-40 WB	US 29 SB TO I-40 WB	3	2		NO	NO	0.12	34	3,068			675		347		24	63	760					
			TOTAL FOR MAP NO. 18							**0.12**		**3,068**			**675**		**347**		**24**	**63**	**760**					
45908.3.1	Guilford	19	US 29 SB RAMP TO MLK JR DR	US 29 SB RAMP TO MLK JR DR	2,4	1		NO	NO	0.403	25		7,658				648		38							425
			TOTAL FOR MAP NO. 19							**0.403**			**7,658**				**648**		**38**							**425**
45908.3.1	Guilford	20	MLK JR DR RAMP TO I-40 WB	MLK JR DR RAMP TO I-40 WB	2,13	1		NO	NO	0.098	20		1,266				108		6							
			TOTAL FOR MAP NO. 20							**0.098**			**1,266**				**108**		**6**							
45908.3.1	Guilford	21	I-40 WB RAMP TO S ELM-EUGENE ST	I-40 WB RAMP TO S ELM-EUGENE ST	2,13	1		NO	NO	0.121	21		1,479				159		9							300
			TOTAL FOR MAP NO. 21							**0.121**			**1,479**				**159**		**9**							**300**
45908.3.1	Guilford	22	S ELM-EUGENE ST RAMP TO I-40 WB	S ELM-EUGENE ST RAMP TO I-40 WB	2,13	1		NO	NO	0.108	26		1,995				169		10							
			TOTAL FOR MAP NO. 22							**0.108**			**1,995**				**169**		**10**							
45908.3.1	Guilford	22A	S ELM-EUGENE ST RAMP TO I-40 WB	I-40 WB RAMP TO RANDLEMAN RD	7	1		NO	NO	0.103	20		1,273				108		6							1,000
			TOTAL FOR MAP NO. 22A							**0.103**			**1,273**				**108**		**6**							**1,000**
45908.3.1	Guilford	23	RANDLEMAN RD RAMP TO I-40 WB	RANDLEMAN RD RAMP TO I-40 WB	2,14	1		NO	NO	0.286	22		4,206				357		21							
			TOTAL FOR MAP NO. 23							**0.286**			**4,206**				**357**		**21**							
45908.3.1	Guilford	24	RANDLEMAN RD RAMP TO BUS 85 SB	RANDLEMAN RD RAMP TO BUS 85 SB	2,15	1		NO	NO	0.239	18		3,130				266		15							
			TOTAL FOR MAP NO. 24							**0.239**			**3,130**				**266**		**15**							
45908.3.1	Guilford	25	BUS 85 SB	I-40 WB TO BUS 85 SB	3	2		NO	NO	0.066	38	1,892			493		213		16	54	525					
			TOTAL FOR MAP NO. 25							**0.066**		**1,892**			**493**		**213**		**16**	**54**	**525**					
TOTAL FOR PROJ NO. 45908.3.1										**14.122**		**369,156**	**48,831**	**3,054**	**12,852**	**436**	**45,962**	**21**	**3,389**	**11,659**	**109,685**	**20**	**20**	**4**	**1**	**4,750**
GRAND TOTAL										**14.122**		**369,156**	**48,831**	**3,054**	**12,852**	**436**	**45,962**	**21**	**3,389**	**11,659**	**109,685**	**20**	**20**	**4**	**1**	**4,750**