


**SECTION THRU SLAB**  
(TYPE III - REINFORCED APPROACH FILL)



**NOTES**

FOR BRIDGE APPROACH FILL INCLUDING GEOTEXTILE, MSE WALL REINFORCEMENT, AND BACK FILL MATERIAL, SEE ROADWAY PLANS.

GEOTEXTILE SHALL BE TYPE 1 IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS SECTION 1056.

BACKFILL MATERIAL IS GOING TO BE THE AGGREGATE USED IN THE REINFORCED ZONE FOR THE MSE RETAINING WALL.

APPROACH SLAB SHALL NOT BE CONSTRUCTED PRIOR TO COMPLETION OF THE BRIDGE DECK.

THE JOINT SHALL BE SAWED PRIOR TO THE CASTING OF THE BARRIER RAIL OR PARAPET AND END POST.

AREA LEFT AND RIGHT OF APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.


**WITH FOAM JOINT SEAL**  
FOR FOAM JOINT SEALS, SEE SPECIAL PROVISIONS.

THE NOMINAL UNCOMPRESSED SEAL WIDTH OF THE FOAM JOINT SEAL SHALL BE 2\"/>


FOR ELASTOMERIC CONCRETE, SEE SPECIAL PROVISIONS.

BILL OF MATERIAL					
STAGE I & III					
FOR ONE APPROACH SLAB (2 REQ'D)					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
* A1	25	#4	STR	39'-4"	657
A2	26	#4	STR	39'-0"	677
* B1	69	#5	STR	23'-7"	1697
B2	69	#6	STR	24'-7"	2548
* B3	5	#4	STR	24'-7"	82
* G1	25	#4	STR	5'-3"	88
REINFORCING STEEL					3,225 LBS.
* EPOXY COATED REINFORCING STEEL					2,524 LBS.
CLASS AA CONCRETE					
POUR #1 (SLAB) (STAGE I)					37.4 C.Y.
POUR #2 (SIDEWALK) (STAGE III)					3.1 C.Y.
CLASS AA CONCRETE					40.5 C.Y.
STAGE II					
FOR ONE APPROACH SLAB (2 REQ'D)					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
* A3	50	#4	STR	26'-7"	888
A4	52	#4	STR	26'-3"	912
* B1	92	#5	STR	23'-7"	2263
B2	92	#6	STR	24'-7"	3397
* B3	5	#4	STR	24'-7"	82
* G1	25	#4	STR	5'-3"	88
* U1	10	#4	1	3'-0"	20
REINFORCING STEEL					4,309 LBS.
* EPOXY COATED REINFORCING STEEL					3,341 LBS.
CLASS AA CONCRETE					
POUR #1 (SLAB)					49.9 C.Y.
POUR #2 (SIDEWALK)					3.1 C.Y.
CLASS AA CONCRETE					53.0 C.Y.


SPLICE LENGTHS		
BAR SIZE	EPOXY COATED	UNCOATED
#4	1' - 11"	1' - 7"
#5	2' - 5"	2' - 0"
#6	3' - 7"	2' - 5"



**PLAN VIEW**



**SECTION S-S**



**TEMPORARY DRAINAGE DETAIL**

NOTE: IMMEDIATELY AFTER THE CONSTRUCTION OF THE APPROACH SLAB, THE CONTRACTOR SHALL PROVIDE TEMPORARY BERM AND SLOPE DRAIN. CONTRACTOR SHALL GRADE TO PIPE INLET AND PROVIDE EROSION RESISTANT MATERIAL AS SHOWN. THE EROSION RESISTANT MATERIAL SHALL BE EITHER 1) ASPHALT PLANT MIX, TYPE 1 OR TYPE 2, MIN. 2" DEPTH, 2) EROSION CONTROL MAT, OR 3) CONCRETE, AS DIRECTED BY THE ENGINEER. THE SLOPE DRAIN SHALL CONSIST OF A NON-PERFORATED TEMPORARY DRAINAGE PIPE, 12 INCHES IN DIAMETER.


NOTE: IF THE APPROACH SLAB IS NOT CONSTRUCTED IMMEDIATELY AFTER THE BACKFILLING OF THE END BENT EXCAVATION, GRADE TO DRAIN TO THE BOTTOM OF THE SLOPE AND PROVIDE EROSION RESISTANT MATERIAL, SUCH AS FIBERGLASS ROVING OR AS DIRECTED BY THE ENGINEER TO PREVENT SOIL EROSION AND TO PROTECT THE AREA ADJACENT TO THE STRUCTURE. THE CONTRACTOR WILL BE REQUIRED TO REMOVE THESE MATERIALS PRIOR TO CONSTRUCTION OF THE APPROACH SLAB.

**TEMPORARY BERM AND SLOPE DRAIN DETAILS**

(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)

ASSEMBLED BY : M.L. CATER	DATE : 10/2022
CHECKED BY : G. COLS	DATE : 10/2022
DRAWN BY : EEM 3/95	REV. 6/13 MAA/GM
CHECKED BY : VAP 3/95	REV. 12/17 MAA/THC
	REV. 6/19 BNB/THC

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



PROJECT NO. BR-0041  
ROCKINGHAM COUNTY  
STATION: POT 34+73.00 -L-  
SHEET 2 OF 2

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-47
1			3			TOTAL SHEETS 48
2			4			