PROJ. REFERENCE NO.	SHEET NO.
BR-0043	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Clearing and grubbing, unclassified excavation, borrow excavation, fine grading, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
20+50.00	0	0
21+00.00	136	2
21+50.00	181	2
22+00.00	83	0
22+50.00	74	4
23+00.00	11	312
23+50.00	2	965
24+00.00	0	1466
24+50.00	0	1881
24+99.00	0	2100

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
26+62.00	0	0
27+00.00	0	1009
27+50.00	0	1251
28+00.00	0	1065
28+50.00	0	816
29+00.00	0	477
29+50.00	0	199
30+00.00	5	359
30+50.00	47	587
31+00.00	83	514
31+50.00	94	423
32+00.00	87	386
32+50.00	67	355
33+00.00	69	294
33+50.00	66	212
34+00.00	48	119
34+50.00	43	58
35+00.00	32	41
35+50.00	20	48
36+00.00	17	109
36+50.00	10	255
37+00.00	11	344
37+50.00	13	330
38+00.00	16	337
38+50.00	21	257
39+00.00	28	85
39+06.56	4	1

Station RPA	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
16+65.00	0	0
17+00.00	13	8
17+50.00	39	30
18+04.61	44	40

Station RPB	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
20+90.00	0	0
21+00.00	27	1
21+50.00	239	6
22+00.00	165	10
22+50.00	66	11
22+73.75	5	4

Station RPC	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+00.00	0	0
17+50.00	6	68
18+00.00	6	116
18+50.00	5	145
19+00.00	2	194
19+50.00	0	369
20+00.00	0	306
20+16.33	0	33

Station RPD	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
18+75.00	0	0
19+00.00	0	0
19+50.00	11	59
20+00.00	6	249
20+50.00	2	462
21+00.00	0	577
21+50.00	0	582
22+00.00	0	580
22+23.64	0	484

Station Y	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
23+00.00	0	0
23+50.00	90	4
24+00.00	109	7
24+50.00	120	6
25+00.00	127	7
25+50.00	119	14
26+00.00	112	28
26+50.00	131	38
27+00.00	165	40
27+50.00	206	44
28+00.00	248	53
28+50.00	344	60
29+00.00	411	60
29+50.00	251	30
30+00.00	107	0
30+50.00	94	0
31+00.00	65	31
31+50.00	42	69
32+00.00	32	111
32+50.00	30	141
33+00.00	36	117
33+50.00	47	70
34+00.00	54	65
34+50.00	58	64
35+00.00	65	34
35+50.00	73	23
36+00.00	80	20
36+50.00	87	19
37+00.00	81	8