CLASS "B" STONE ———
FOR EROSION CONTROL

EARTH DITCH BLOCK-

END OF APPROACH SLAB

DRAWN BY :

CHECKED BY : .

DESIGN ENGINEER OF RECORD: _

APPROACH

B.T. LEROY

J.C. MORRISON

J.C. MORRISON

SLAB

TEMP. SLOPE DRAIN -

2'-0" MIN.

S

NOTE: IMMEDIATELY AFTER THE CONSTRUCTION OF THE APPROACH SLAB,

DRAIN. CONTRACTOR SHALL GRADE TO PIPE INLET

THE CONTRACTOR SHALL PROVIDE TEMPORARY BERM AND SLOPE

PLANT MIX, TYPE 1 OR TYPE 2, MIN. 2" DEPTH, 2) EROSION CONTROL

AND PROVIDE EROSION RESISTANT MATERIAL AS SHOWN. THE

11/2022

12/2022

EROSION RESISTANT MATERIAL SHALL BE EITHER 1) ASPHALT

MAT, OR 3) CONCRETE, AS DIRECTED BY THE ENGINEER

TEMPORARY DRAINAGE PIPE, 12 INCHES IN DIAMETER.

PLAN VIEW


_ DATE :

DATE:

THE SLOPE DRAIN SHALL CONSIST OF A NON-PERFORATED

MIN

EROSION RESISTANT MATERIAL



SECTION THRU SLAB

(TYPE III - REINFORCED APPROACH FILL)

TOE OF FILI

4'-0"

12" MINIMUM -

- ELBOW

CLASS "B" STONE

SECTION R-R

4'-0" MIN.

SECTION S-S

FOR EROSION CONTROL

— 3" EARTH RESISTANT

MATERIAL OVER PIPE

NOTES

FOR BRIDGE APPROACH FILL INCLUDING GEOTEXTILE, MSE WALL REINFORCEMENT, AND BACK FILL MATERIAL, SEE ROADWAY PLANS.

GEOTEXTILE SHALL BE TYPE 1 IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS SECTION 1056.

BACKFILL MATERIAL IS GOING TO BE THE AGGREGATE USED IN THE REINFORCED ZONE FOR THE MSE RETAINING WALL.

APPROACH SLAB SHALL NOT BE CONSTRUCTED PRIOR TO COMPLETION OF THE BRIDGE DECK.

AREA LEFT AND RIGHT OF APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

FOR STRIP SEAL EXPANSION JOINTS, SEE SPECIAL PROVISIONS.

SPLICE LENGTHS							
BAR EPOXY UNCOAT	Έľ						
#4 1'-11" 1'-7	11						
#5 2'-5" 2'-0	11						
#6 3'-7" 2'-5	Ш						

BILL OF MATERIAL

STAGE I

FOR ONE APPROACH SLAB (2 REQ'D)

BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT		
* A1	48	#4	STR	19'-10"	636		
A2	52	#4	STR	19'-6"	677		
* B1	69	#5	STR	24'-8"	1775		
B2	69	#6	STR	24'-8"	2556		
* B3	4	#5	STR	6'-6"	27		
B4	4	#6	STR	6'-6"	39		
REINFORCING STEEL 3,272 LBS.							
* EPOXY COATED							

STAGE II

REINFORCING STEEL

CLASS AA CONCRETE

CLASS AA CONCRETE

PROJECT NO.__

ROCKINGHAM

STATION: POT 25+80.88 -L-

2,438 LBS.

38.4 C.Y.

53.0 C.Y.

FOR ONE APPROACH SLAB (2 REQ'D)

BA	١R	NO.	SIZE	TYPE	LENGTH	WEIGHT
* A	.3	48	#4	STR	25'-10"	828
Α	4	52	#4	STR	25'-8"	892
* B	1	97	#5	STR	24'-8"	2496
В	2	97	#6	STR	24'-8"	3594
* B	3	4	#5	STR	6'-6"	27
В	4	4	#6	STR	6'-6"	39
REINFORCING STEEL				3,351 LBS.		
<u>—</u> —	POX	Y COATE	D			
REINFORCING STEEL					4,	525 LBS.

BRIDGE DECK

GRADE TO BOTTOM OF SHORE

CAP FLOW LINE ONLY WITH EROSION RESISTANT MATERIAL BACKFILL EXCAVATION HOLE

NOTE: IF THE APPROACH SLAB IS NOT CONSTRUCTED IMMEDIATELY AFTER THE BACKFILLING OF THE END BENT EXCAVATION, GRADE TO DRAIN TO THE BOTTOM OF THE SLOPE AND PROVIDE EROSION RESISTANT MATERIAL, SUCH AS FIBERGLASS ROVING OR AS DIRECTED BY THE ENGINEER TO PREVENT SOIL EROSION AND TO PROTECT THE AREA ADJACENT TO THE STRUCTURE. THE CONTRACTOR WILL BE REQUIRED TO REMOVE THESE MATERIALS PRIOR TO CONSTRUCTION OF THE APPROACH SLAB.

AND GRADE TO DRAIN

TEMPORARY DRAINAGE DETAIL

AECOM TECHNICAL SERVICES OF NC, INC.
5438 WADE PARK BOULEVARD, SUITE 200
RALEIGH, NC 27607
(919) 854-6200 www.aecom.com
AECOM License No. F-0342

A

SEAL
030474

APPROACH SLAB DETAILS

STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

BR-0043

COUNTY

REVISIONS SHEET NO.

1/31/2023 NO. BY: DATE: NO. BY: DATE: S-44

1 3 TOTAL SHEETS

TEMPORARY BERM AND SLOPE DRAIN DETAILS

TEMPORARY SLOPE DRAIN

- EARTH DITCH BLOCK

- FILL SLOPE

- ELBOW

(TO BE USED WHEN SHOULDER BERM GUTTER IS REQUIRED)

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

1/31/2023
c:\pwworking\aecom_ds21_na_2020\d0125534\401_087_BR-0043_SMU_BAS2_S1-44_780151.dgn
caterm

- FUTURE SHOULDER