PROJ. REFERENCE NO.	SHEET NO.
U-2729	X-B

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+00.00	0	0
12+50.00	18	69
13+00.00	21	59
13+50.00	22	54
14+00.00	18	75
14+50.00	15	106
15+00.00	19	119
15+50.00	19	145
16+00.00	15	201
16+50.00	11	237
17+00.00	7	282
17+50.00	5	343
18+00.00	4	391
18+50.00	4	437
19+00.00	4	519
19+45.18	3	522

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
21+54.28	0	0
22+00.00	809	44
22+50.00	439	69
23+00.00	309	82
23+50.00	219	87
24+00.00	162	103
24+50.00	114	96
25+00.00	63	145
25+50.00	48	271
26+00.00	67	181
26+50.00	61	63
27+00.00	42	93
27+50.00	32	134
28+00.00	28	240
28+50.00	26	394
29+00.00	23	654
29+50.00	21	789
30+00.00	19	494
30+50.00	9	458
31+00.00	17	854
31+50.00	17	1420
32+00.00	0	1971
32+50.00	11	2271
33+00.00	11	3862
33+14.78	0	1567

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
35+23.53	0	0
35+50.00	8	1339
36+00.00	11	2305
36+50.00	4	1734

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
37+00.00	0	1124
37+50.00	0	456
38+00.00	0	406
38+50.00	0	654
39+00.00	0	616
39+50.00	124	570
40+00.00	125	693
40+50.00	4	850
41+00.00	30	562
41+50.00	41	377
42+00.00	52	341
42+50.00	78	228
43+00.00	88	137
43+50.00	94	89
44+00.00	46	76
44+50.00	63	36
45+00.00	140	0
45+50.00	127	17
46+00.00	91	48
46+50.00	69	66
47+00.00	76	62
47+50.00	76	67
48+00.00	45	88
48+50.00	31	105
49+00.00	24	131
49+50.00	25	198
50+00.00	29	292
50+50.00	35	238
51+00.00	44	84
51+50.00	40	35
52+00.00	31	37
52+50.00	30	30

Station RDBT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+25.00	0	176
10+50.00	0	214
10+75.00	2	153
11+00.00	2	143
11+25.00	16	164
11+50.00	112	171
11+75.00	95	182
12+00.00	10	160
12+25.00	10	167
12+50.00	0	255
12+75.00	0	406
13+00.00	0	453
13+25.00	0	451
13+50.00	0	327
13+70.71	0	105

Station RPA	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+50.00	0	0
18+00.00	224	107
18+50.00	156	170
19+00.00	77	283
19+50.00	22	401
20+00.00	6	506
20+50.00	0	598
21+00.00	0	751
21+50.00	0	894
22+00.00	0	1071
22+39.90	0	696

RPB	(cu. yd.)	(cu. yd.)
23+50.00	0	0
24+00.00	87	72
24+50.00	42	131
25+00.00	19	184
25+50.00	10	315
26+00.00	0	558
26+50.00	0	812
27+00.00	0	894
27+26.18	0	449

Station Y1A	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
9+00.00	0	0
9+50.00	76	5
10+00.00	76	50
10+50.00	0	215
11+00.00	0	506
11+50.00	0	752
12+00.00	0	947
12+36.84	0	783

Station Y1B	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+32.76	0	0
10+50.00	116	0
11+00.00	222	5
11+50.00	97	5

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+29.46	0	0
11+50.00	18	30
12+00.00	58	131
12+16.76	9	38

Station Y3A	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+37.50	0	0
10+50.00	0	131
11+00.00	67	293
11+50.00	150	31
11+54.95	8	0

Station Y5	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+34.92	0	0
10+50.00	0	53
11+00.00	24	88
11+50.00	67	7
11+76.22	24	88

Station Y6A	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00	0	0
11+50.00	75	16
12+00.00	131	19
12+50.00	120	24
13+00.00	104	34
13+50.00	131	26
14+00.00	133	8
14+50.00	71	20
15+00.00	56	40
15+50.00	67	36
16+00.00	69	25
16+50.00	77	13
17+00.00	82	6
17+50.00	144	8
17+61.50	48	3

Station Y6B	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+52.77	0	0
11+00.00	110	26
11+50.00	125	19
12+00.00	166	16
12+50.00	152	10
13+00.00	140	3
13+30.00	43	2