Note: Quantities are approximate only. The Resident Engineer will use methods including but not limited to recross-sectioning, truck measurements, and aerial surveys to compute the final quantities for which the contractor will be paid.

PROJ. REFERENCE NO.	SHEET NO.
R-2707D	X-1D

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station Srvrd_4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
9+78.55	0	0
10+00.00	231	1
10+50.00	927	0
11+00.00	1219	0
11+50.00	1643	0
12+00.00	1875	0
12+50.00	1912	0
13+00.00	2363	0
13+50.00	5020	0
14+00.00	6944	0
14+50.00	5624	275
15+00.00	4305	523
15+50.00	3338	248
16+00.00	1945	0
16+50.00	674	46
17+00.00	19	579
17+50.00	0	898
18+00.00	26	398
18+50.00	52	47
19+00.00	69	24
19+50.00	90	17
20+00.00	89	14
20+20.00	17	3

Station Srvrd_5	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+10.00	0	0
10+50.00	5779	0
11+00.00	5397	0
11+50.00	5225	0
12+00.00	5115	0
12+50.00	5117	0
13+00.00	5646	0
13+50.00	6698	0
14+00.00	6417	0
14+50.00	4800	0
15+00.00	3505	0
15+50.00	2841	0
16+00.00	2399	0
16+50.00	1698	0
17+00.00	1081	0
17+50.00	946	0
18+00.00	1043	0
18+50.00	529	174
19+00.00	0	379
19+50.00	0	956
20+00.00	0	1290
20+50.00	0	660
21+00.00	62	156
21+50.00	137	38
22+00.00	141	3
22+50.00	124	0
22+96.49	114	0

Station Srvrd_5A	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+50.00	0	75
11+00.00	355	75
11+50.00	1122	0
12+00.00	2077	0
12+50.00	2965	0
13+00.00	3543	0
13+38.14	3946	0

Station Pvtent1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
5+65.72	0	0
6+00.00	33	0
6+50.00	59	0
7+00.00	104	0
7+50.00	162	0
8+00.00	236	0
8+50.00	253	0
9+00.00	158	0
9+50.00	84	0
9+70.00	19	1
9+88.00	7	4

Station Pvtent2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.00	0	0
10+50.00	153	0
11+00.00	81	12
11+50.00	26	24
12+00.00	34	12
12+50.00	41	1
13+00.00	31	1
13+50.00	24	0
14+00.00	17	0
14+20.00	6	0

Station Pvtent4	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+25.00	0	0
10+50.00	343	0
10+75.00	494	0
11+00.00	563	0
11+25.00	502	0
11+50.00	377	0
11+75.00	300	0
12+00.00	248	0
12+25.00	227	0
12+50.00	196	0
12+75.00	146	2
12+80.00	24	1

Station Pvtent5	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.18	0	0
10+25.00	31	0
10+50.00	28	0
10+75.00	7	0
10+85.00	3	0

Station Pvtent6	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.00	0	0
10+50.00	1265	0
11+00.00	1012	0
11+50.00	564	0
12+00.00	222	0
12+50.00	44	0

Station Det_2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00000	0	0
10+50.00000	0	144
11+00.00000	0	383
11+50.00000	0	708
12+00.00000	0	1239
12+50.00000	0	1745
12+94.37000	0	1182

Station Det_2 (Removal)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00000	0	0
10+50.00000	144	0
11+00.00000	363	0
11+50.00000	425	0
12+00.00000	292	0
12+50.00000	0	0
12+94.37000	0	0