

jHagenbush

4/14/2023

c:\pvt_working\00302743\sbw2_4.dgn

BEGIN WALL STATION (NW10A)	END WALL STATION (NW10A)	PILE EXCAVATION DEPTHS, "D" (FT)		
		PILE SPACING = 10 FT	PILE SPACING = 15 FT	PILE SPACING = 20 FT
10+00	14+95	6	7	8
14+95	17+80	6	6	7
17+80	20+80	6	7	8
20+80	23+20	6	7	8
23+20	23+95	6	7	7

PILE EXCAVATION DEPTHS - SOUND BARRIER WALL 10A

1. BEGIN AND END WALL STATIONS ARE REFERENCED TO THE NW10A ALIGNMENT. SEE ROADWAY PLANS FOR ADDITIONAL INFORMATION.
2. STATIONS ARE TO THE ROADWAY FACE OF THE SOUND BARRIER WALL CONCRETE PILES.

PROJECT NO. R-2707E
CLEVELAND COUNTY
 STATION: 935+69.92 -L-

SHEET 4 OF 4



STATE OF NORTH CAROLINA
 DEPARTMENT OF TRANSPORTATION
 RALEIGH
 STANDARD
 SOUND BARRIER WALL
 PILE EXCAVATION
 DEPTHS



Stantec Consulting Services Inc.
 801 Jones Franklin Road
 Suite 300
 Raleigh, NC 27606
 Tel. (919) 851-6866
 Fax. (919) 851-7024
 www.stantec.com
 License No. F-0672

DRAWN BY : A.L. BOYKIN DATE : 02/23/23
 CHECKED BY : S.S. POOLE DATE : 03/03/23
 DESIGN ENGINEER OF RECORD: S.S. POOLE DATE : 04/14/23

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	NW10A-4
1			3			TOTAL SHEETS
2			4			4