

PROJECT NO.	SHEET NO.
I-6039	26

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO.	COUNTY	MAP NO.	ROUTE	DESCRIPTION	TYP NO.	LANES	LANE TYPE	LENGTH	WIDTH	4825000000-E	4850000000-E	4855000000-E	4890000000-E	4900000000-N	4905100000-N	
										12" WHITE PAINT	REMOVAL OF PAVEMENT MARKING LINES (4")	REMOVAL OF PAVEMENT MARKING LINES (6")	REMOVAL OF PAVEMENT MARKING (THERMO. ON CONCRETE ISLAND)	YELLOW & YELLOW MARKERS	NON CAST IRON SNOWPLOW-ABLE MARKERS (C/R)	
									MI	FT	LF	LF	LF	EA	EA	
TOTAL FOR MAP NO. 17									0.48			660				
47988.3.1	NewHanover	18	EXIT 416B - I-40 WB EXIT RAMP AT I-140	FROM I-40 WB TO I-140 EB [MP 0.14 - MP 0.60]	2	2		0.46	25							
TOTAL FOR MAP NO. 18									0.46							
47988.3.1	NewHanover	19	EXIT 416A - I-40 WB EXIT LOOP AT I-140	FROM I-40 TO I-140 WB [MP 0.04 - MP 0.22]	6	1		0.18	22							
TOTAL FOR MAP NO. 19									0.18							
47988.3.1	NewHanover	20	EXIT 20B - I-140 WB EXIT RAMP AT I-40 WB	FROM I-140 TO I-40 WB [MP 0.31 - MP 0.75]	2	1		0.44	24							
TOTAL FOR MAP NO. 20									0.44							
47988.3.1	NewHanover	21	EXIT 414 - I-40 WB EXIT RAMP AT SR 1002 (HOLLY SHELTER ROAD)	FROM I-40 WB TO SR 1002 (HOLLY SHELTER RD.) [MP 0.08 - MP 0.39]	8	1		0.31	18				80	9	14	
TOTAL FOR MAP NO. 21									0.31				80	9	14	
47988.3.1	NewHanover	22	EXIT 414 - I-40 WB ENTRANCE RAMP AT I-40 WB	FROM SR 1002 (HOLLY SHELTER RD.) TO I-40 WB [MP 0.01 - MP 0.17]	9	1		0.16	18					9		
TOTAL FOR MAP NO. 22									0.16					9		
47988.3.1	Pender	23	EXIT 408 - I-40 WB EXIT RAMP AT NC 210 HWY.	FROM I-40 WB TO NC 210 HWY. [MP 0.03 - MP 0.24]	8	1		0.21	18				80	9	22	
TOTAL FOR MAP NO. 23									0.21				80	9	22	
47988.3.1	Pender	24	EXIT 408 - I-40 WB ENTRANCE RAMP AT I-40 WB	FROM NC 210 HWY. TO I-40 WB [MP 0.01 - MP 0.22]	7	1		0.21	18							
TOTAL FOR MAP NO. 24									0.21							
TOTAL FOR PROJ NO. 47988.3.1									33.03		2,340	760	550	400	66	2,368
GRAND TOTAL									33.03		2,340	760	550	400	66	2,368