

Project No.	Sheet No.
I-6039	28

I-40 RAMPS GUARDRAIL													
MAP NO.	MILE MARKER/RANGE	SIDE OF RDWY. RT/LT	TL-3 END UNIT (EA)	REMOVE & RESET TL-3 END UNIT (EA)	CAT-1 UNIT (EA)	REMOVE & REPLACE CAT-1 UNIT (EA)	REMOVE & RESET CAT-1 UNIT (EA)	REMOVE & REPLACE TL-3 END UNIT (EA)	STEEL BEAM GR SHOP CURVED (LF)	REMOVE & REPLACE GR (LF)	STEEL BEAM GUARDRAIL (LF)	GUARDRAIL PRE-FAB ANCHOR POSTS (GENERIC)	REMOVE & RESET EXISTING GR (LF)
3	0.19 - 0.27	RT	1							100			275
4	0.00 - 0.09	RT											150
8	0.50 - 0.57	LT				1							
8	0.67 - 0.70	LT				1							
13	0.05 - 0.19	RT								125			
13	0.08 - 0.12	LT	1			1				75			217
14	6.48 - 6.72	RT								200			590
14	6.56 - 6.70	LT	1			1				100			125
15	0.23 - 0.29	LT				1				25			294
16	0.10 - 0.46	LT	1										1305
16	0.14 - 0.48	RT		1		1							1787
17	9.18 - 9.48	RT								970			785
17	9.20 - 9.46	LT						1		680			
17	9.54 - 9.58	RT				1				50			157
18	0.24 - 0.60	RT		1						75			
20	0.29 - 0.48	RT				1							1000
23	0.16 - 0.24	RT		1									555
24	0.01 - 0.10	RT				1				570			
RAMPS TOTAL			4	3	0	9	0	1	0	2970	0	0	7240

GRAND TOTAL			5	11	0	18	5	26	0	3250	1560	0	11990
--------------------	--	--	----------	-----------	----------	-----------	----------	-----------	----------	-------------	-------------	----------	--------------