\_\_\_\_

RELIMINARY USE FOR CO

Z

 $\bigcirc$ 

+





TABLE 1						
01-26-2023						
BENT/ JOINTS	DIM 'A' @ 51°F					
END BENT 1	2 <sup>1</sup> ⁄ <sub>4</sub> "					
END BENT 2	2"					

DRAWN BY :	FIDEL L. FLORES	DATE: 01/2023
CHECKED BY :	ALLEN J. MCSWAIN	DATE : 01/2023
DESIGN ENGINEER	OF RECORD: JACOB H. DUKE	DATE : 01/2023

4/17/2023 640059\_I6039\_SMU\_JT02.dgn jduke



SECTION D-D (PROPOSED FOAM JOINT SEAL)

## NOTES:

THE CONTRACTOR SHALL FIELD VERIFY THE EXISTING JOINT OPENING PRIOR TO ORDERING JOINT SEAL MATERIAL. IF THE ACTUAL OPENING VARIES FROM THE OPENING INDICATED IN THE DETAIL BY MORE THAN 1/4", NOTIFY THE ENGINEER. REVISION OF THE JOINT SEAL SIZE MAY BE NECESSARY.

THE MANUFACTURER IS TO PROVIDE THE NOMINAL UNCOMPRESSED SEAL WIDTH OF THE FOAM JOINT SEAL FOR THE SIZE OF THE OPENING ON THE PLANS AND ACCOMODATE THE MINIMUM EXPANSION SHOWN ON THE PLANS.

INSTALL FOAM JOINTS AS PER THE MANUFACTURER'S RECOMMENDATIONS.

THE CONTRACTOR SHALL TAKE CARE DURING JOINT REPAIR OPERATIONS NOT TO DROP ANY MATERIAL THAT FALLS BELOW THE BRIDGE, WITHOUT PROTECTIVE DEVICES BELOW TO CATCH THE MATERIAL. ANY MATERIAL THAT FALLS BELOW THE BRDIGE SHALL BE CONTAINED, REMOVED AND DISPOSED OF BY THE CONTRACTOR AT NO EXTRA COST TO THE DEPARTMENT. IF THE ENGINEER DETERMINES THAT THE PROTECTIVE DEVICES ARE NOT ADEQUATE OR NOT BEING EMPLOYED, THE WORK SHALL BE SUSPENDED UNTIL ADEQUATE PROTECTIÓN IS PROVIDED.

THE CONTRACTOR WILL NOT BE PERMITTED TO FORM THE JOINTS IN LIEU OF SAWING THE JOINT.

FOR BRIDGE JOINT DEMOLITION, SEE SPECIAL PROVISIONS.

FOR FOAM JOINT SEALS FOR PRESERVATION, SEE SPECIAL PROVISIONS.

DEMOLISH BRIDGE JOINT AREA SUCH THAT THE BOTTOM OF THE EXCAVATION SHALL BE REASONABLY FLAT AND LEVEL AND TO THE NECESSARY DEPTH, SUCH THAT THE REPAIR SHALL BE FOUNDED ON CONCRETE OR REPAIR CONCRETE SUBSTRATE.

TAKE CARE NOT TO DAMAGE ANY EXISTING DECK REINFORCING EXPOSED DURING BRIDGE JOINT DEMOLITION. NOTIFY THE ENGINEER OF ANY DECK REINFORCING EXPOSED DURING BRIDGE JOINT DEMOLITION OPERATIONS.

EXISTING DECK REINFORCING IS NOT SHOWN IN THE SECTIONS PROVIDED ON THIS SHEET.

	PROJEC <u>NE\</u> Bridge	N HAN		/EF	-6039 CC 10059	UNTY		
SHEET 2 OF 3								
CLARO/ Saucase (Stable) S / 0/ 1/4 SEAL 043777 / 17/ 0/0/3 H	STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH JOINT DETAILS							
 ASSOCIATES		SHEET NO.						
	NO. BY:	DATE:		BY:	DATE:	S4-5		
FAYETTEVILLE ST., SUITE 1500 EIGH, NC 27601 (919) 882-7839 IRM LICENSE: C-1506	12		3 4			total sheets <b>13</b>		