

- AFTER ALL WORK IS PERFORMED. CUTOVER TO NEW IT TRUNK SHALL NOT EXCEED 24 HOURS IN DURATION. WORK IS NOT COMPLETE UNTIL THE IT NETWORK IS BACK UP AND OPERATIONAL.
- 4. UPON REMOVAL OF EXISTING FIBER, REMOVE EXISTING JUNCTION BOXES AND BACKFILL WITH APPROVED MATERIAL. ABANDON UNUSED CONDUITS IN PLACE.
- 5. BACKPULL EXISTING FIBER OPTIC CABLE AND REROUTE TO NEW SPLICE ENCLOSURE AS SHOWN.
- 6. INSTALL NEW FIBER OPTIC CABLE IN SAME TRENCH. USE SEPARATE CONDUIT AND SEPERATE JUNCTION BOXES FOR IT AND SIGNAL SYSTEM FIBER.



