DocuSign Envelope ID: 68305EC9-A1FB-4E86-87A0-E22285C22061

6/2/99

REVISIONS

PROPOSED ALIGNMENT CONTROL SHEET

PROJECT REFERENCE NO.	SHEET NO.
R-5799	RW02D-1

Location and Surveys

MATTERN AND CRAIG
ENGINEERS & SURVEYORS
12 BROAD STREET
ASHEVILLE NORTH CAROLINA 28801
(828) 254-2201
FAX (828) 254-4562
NC LIC. NO. C-1154

PROJECT SURVEYOR

NORTH CAROLINA PROFESSIONAL SEAL L-5235 LAND SURVEYOR RON L. ZIETLOW

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

I, R. L. Zietlow, PLS, certify that the data compiled came from available surveys/mapping performed by others and provided to me by NCDOT and do not certify to the accuracy or quality of the individual data sources.

This 11th day of May, 2023.

DocuSigned by:
Ron Zietlow
84E55C984005472...

Professional Land Surveyor L-5235

-L- US 64/US 276/NC 280

TYPE	STATION	NORTH	EAST
POT	4+50.00	573929.1941	893406.2998
PC	4+90.09	573953.9140	893437.8641
PT	8+12.31	574166.4203	893679.8517
PC	27+81.65	575547.0060	895084.2256
PT	30+82.05	575742.2354	895312.2293
POT	37+85.71	576162.1005	895876.8915

-Y1- ECUSTA RD.

TYPE	STATION	NORTH	EAST
POT	10+00.00	574571.2478	894091.6546
PC	10+09.70	574565.3328	894099.3444
PT	10+73.16	574513.7594	894134.4647
PC	10+73.16	574513.7594	894134.4647
PT	12+54.08	574335.4051	894161.6650
POT	18+88.97	573700.6717	894175.7029

-Y2- US 64

TYPE	STATION	NORTH	EAST
PC	10+00.00	575221.2203	894752.8265
PT	10+97.98	575183.9545	894843.4352
PC	20+58.67	574796.8875	895722.6939
PT	32+22.05	574329.6176	896788.1130

-Y3- US 276

TYPE	STATION	NORTH	EAST
PC	10+00.00	575221.2203	894752.8265
PT	11+46.20	575268.4676	894614.5044
POT	26+88.51	575713.3336	893137.7478

-Y4- DEAVOR RD.

TYPE	STATION	NORTH	EAST
POT	10+00.00	575597.5786	895137.4284
PC	11+53.51	575485.7561	895242.5958
PT	12+38.31	575422.9385	895299.5609
POT	13+10.00	575368.9707	895346.7436

-Y5- FOREST GATE DR.

TYPE	STATION	NORTH	EAST
POT	10+00.00	575605.6515	895146.2604
PC	11+25.83	575698.7509	895061.6086
PT	12+73.38	575818.5696	894976.0923
POT	12+90.28	575833.3847	894967.9635

Y6

TYPE	STATION	NORTH	EAST
POT	10+00.00	575735.9029	895303.7558
POT	12+05.73	575894.2716	895172.4431

NOTES:

1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.

2. THE PROPOSED ALIGNMENT CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

09-MAY-2023 14:10
I:\3921 NCDOT Survey\3921AR_r5799 RW Revision\03 Design\03-Survey\01-Deliverables\R5799_ls_rw02d-1.dgn
rlzietlow AT MC-ASH-WKS-L52H