


18 CHANNEL IP CONFLICT MONITOR PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



REMOVE DIODE JUMPERS 1-5, 1-6, 1-15, 2-5, 2-6, 2-13, 2-15, 4-14, 5-13, 6-13, 6-15, AND 13-15.



REMOVE JUMPERS AS SHOWN

NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that the Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.



NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the signal plan.
2. Return controller to Factory Defaults before programming per this electrical detail.
3. Program controller to start up in phase 2 Green Walk and 6 Green Walk.
4. If this signal will be managed by an ATMS software, enable controller and detector logging for all detectors used at this location.
5. The cabinet and controller are part of a Temporary Time Based Coordination System.

EQUIPMENT INFORMATION

Controller.....2070LX
 Cabinet.....332 w/ Aux
 Software.....Q-Free MAXTIME
 Cabinet Mount.....18 With Aux. Output File
 Load Switches Used.....S1, S2, S3, S4, S5, S6, S7, S8, S9
 Phases Used.....1, 2, 2PED, 3, 4, 4PED, 5, 6, 6PED
 Overlaps.....NONE


SIGNAL HEAD HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12	AUX S1	AUX S2	AUX S3	AUX S4	AUX S5	AUX S6
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16	9	10	17	11	12	18
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED	OL1	OL2	SPARE	OL3	OL4	SPARE
SIGNAL HEAD NO.	11,12	21, 22,23	P21, P22	31	32	62	41	42,43	P41, P42	51,52	32	61,62	P61, P62	NU	NU	NU	NU	NU
RED		128		116	116		101	101				134						
YELLOW		129		117	117		102	102				135						
GREEN		130		118	118		103	103				136						
RED ARROW	125											131						
YELLOW ARROW	126				117							132	132					
FLASHING YELLOW ARROW																		
GREEN ARROW	127			118	118	103						133	133					
Hand icon			113						104					119				
Walking person icon			115						106					121				

NU = Not Used

INPUT FILE POSITION LAYOUT

(front view)




EX. : 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE
 ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT POINT	DETECTOR NO.	CALL PHASE	DELAY TIME	EXTEND TIME	EXTEND	ADDED INITIAL	CALL	DELAY DURING GREEN
PED PUSH BUTTONS												
P21,P22	TB8-4,6	I12U	67	33	2	PED 2						
P41,P42	TB8-5,6	I12L	69	35	4	PED 4						
P61,P62	TB8-7,9	I13U	68	34	6	PED 6						

NOTE:
 INSTALL DC ISOLATORS IN INPUT FILE SLOTS I12 AND I13.



SPECIAL DETECTOR NOTE

Install a multizone microwave detection system for vehicle detection. Perform installation according to manufacturer's directions and NCDOT engineer -approved mounting locations to accomplish the detection schemes shown on the Signal Design Plans.

COUNTDOWN PEDESTRIAN SIGNAL OPERATION

Countdown Ped Signals are required to display timing only during Ped Clearance Interval. Consult Ped Signal Module user's manual for instructions on selecting this feature.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 14-0798T5
 DESIGNED: May 2023
 SEALED: May 4, 2023
 REVISED: _____

Temporary Signal 5 - TCP Phase VI Step 1
 Electrical Detail - Sheet 1 of 2

Electrical and Programming Details For: **US 64-276 (Asheville Highway)**

Prepared for the Offices of:

750 N. Greenfield Pkwy, Garner, NC 27529

at
SR 1512 (Ecusta Road) / Bank Driveway

Division 14 Transylvania County Brevard

PLAN DATE: May 2023 REVIEWED BY: V. Kaiser

PREPARED BY: S.G. Haynie REVIEWED BY:

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL

DocuSigned by: **Steven G. Haynie** 5/4/2023

DATE: _____

SIG. INVENTORY NO. 14-0798T5



5/4/2023 8:11:30:26 AM R:\IT\OFFICE\Signal\Drawings\Sheet\5799_s1g_psh_6-1_140798T5.dwg