

PED 3 PROGRAMMING DETAIL

Front Panel
Main Menu >Controller >Detector >Ped Det Plans

Web Interface
Home >Controller >Detector Configuration >Pedestrian Detector

Plan 1

Detector	Description	Call Phase	Call Overlap
2		2	0
4		4	0
6		6	0
8		3	0

NOTICE PHASE 3 PED
ASSIGNED TO
DETECTOR 8 PED →

Front Panel
Main Menu >Controller >More>Channels>Channels Config

Web Interface
Home >Controller >Advanced IO>Channels>Channels Configuration

Channel Configuration

Channel	Control Type	Control Source	Flash Yellow	Flash Red	Flash Alt	MMU Channel
1	Phase Vehicle	1		X	X	1
2	Phase Vehicle	2	X			2
3	Phase Vehicle	3		X	X	3
4	Phase Vehicle	4		X		4
5	Phase Vehicle	5		X		5
6	Phase Vehicle	6	X		X	6
7	Phase Vehicle	7		X		7
8	Phase Vehicle	8		X	X	8
9	Overlap	1	X		X	9
10	Overlap	2		X	X	10
11	Overlap	3	X			11
12	Overlap	4		X		12
13	Phase Ped	2				13
14	Phase Ped	4				14
15	Phase Ped	6				15
16	Phase Ped	3				16
17	Overlap	5		X	X	17
18	Overlap	6		X		18



NOTICE PHASE 3 PED
ASSIGNED TO CHANNEL 16 →

ACCESSIBLE PEDESTRIAN SIGNAL (APS) INSTALLATION NOTES

1. Install push buttons and APS equipment per manufacturer's instructions.
2. Provide a dedicated cable to each push button per manufacturer's instructions.
3. If APS equipment is mounted in cabinet, use filtered power (i.e., Controller Receptacle) to power APS equipment. Do not use Equipment Receptacle, which is a GFCI outlet.
4. Never attempt to operate a standard contact closure push button with the APS system unless cabinet is re-wired for standard button operation or unless explicitly allowed by the manufacturer.
5. Place manufacturer's instructions in cabinet with cabinet prints, signal plans, and electrical details.

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 14-0798T6
DESIGNED: May 2023
SEALED: May 4, 2023
REVISED: _____

Temporary Signal 6 - TCP Phase VI, Step 2
Electrical Detail - Sheet 2 of 2

Electrical and Programming Details For:	US 64-276 (Asheville Highway)		DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED
	at SR 1512 (Ecusta Road) / Bank Driveway		
Prepared for the Offices of: 	Division 14 PLAN DATE: May 2023 PREPARED BY: S.G. Haynie	Transylvania County REVIEWED BY: V. Kaiser REVIEWED BY:	SEAL  DATE: 5/4/2023
750 N. Greenfield Pkwy, Garner, NC 27529	REVISIONS INIT. DATE	DATE	SIG. INVENTORY NO. 14-0798T6



5/4/2023 8:41:07 AM C:\Users\sgn\OneDrive\Documents\Signal\14-0798T6.dwg 11:29:35 AM