PATCHING EXISTING PAVEMENT

PATCHING TO BE PERFORMED PRIOR TO MILL AND FILL OPERATION

DETAIL OF PROJECT LIMITS AT

SIGNALIZED Y LINES

NOTES

DETAIL OF PROJECT LIMITS AT UNSIGNALIZED Y LINES

ALL UNPAVED S.R. ROADS TO BE RESURFACED 50' FROM EDGE OF PAVEMENT OF MAIN PROJECT ALL PAVED S.R. ROADS TO BE RESURFACED TO THE ENDS OF THE RADII, OR AS DIRECTED BY THE ENGINEER. EDGES, PAVEMENT WIDENING, INTERSECTIONS AND BRIDGE FLARES ARE INCLUDED IN THE TABLE OF QUANTITIES. BRIDGES TO BE RESURFACED AT LOCATIONS AND TO DEPTH AS DIRECTED BY THE ENGINEER.



