PROJECT NO.	SHEET NO.
I-6036	5

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1260000000-E AGGREGATE SHOULDER BORROW	1245000000-E SHOULDER RECONSTRUCTION	1297000000-E 3" MILLING	1524200000-E SURFACE COURSE, S9.5D	1577000000-E POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX	1662000000-E OG ASP FRICT FC-1	1840000000-E MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	3420000000-E REMOVE & RESET EXISTING GUARDRAIL	3435000000-N REMOVE & RESET GUARDRAIL END UNIT, TYPE CAT-1	3435000000-N REMOVE & REPLACE GUARDRAIL END UNIT, TYPE CAT-1	3435000000-N REMOVE & RESET GUARDRAIL END UNIT, TYPE TL-3	3435000000-N REMOVE & REPLACE GUARDRAIL END UNIT, TYPE TL-3	4109000000-N SIGN ERECTION, TYPE A (OVERHEAD)	4234000000-N DISPOSAL OF SIGN, A OR B (OVERHEAD)	4600000000-N SINGLE LANE CLOSURE	4600000000-N RAMP / LOOP CLOSURES	5255000000-N PORTABLE LIGHTING
										MI	FT	TON	SMI	SY	TONS	TON	TON	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	LS
47985.3.1	Brunswick	1	I-140 EB (JOHN JAY BURNEY JR. HWY.)	FROM US 17 (OCEAN HWY E.) TO US 74 / 76 (ANDREW JACKSON HWY.) [MP O.82 TO MM 5.76]	1	2	2WD	NO	NO	4.94	41	2,470	9.88	118,824	22,092	1,579	4,801	52,166	1,580	2	1	3		1	1	137		
TOTAL FOR MAP NO. 1										**4.94**		**2,470**	**9.88**	**118,824**	**22,092**	**1,579**	**4,801**	**52,166**	**1,580**	**2**	**1**	**3**		**1**	**1**	**137**		
47985.3.1	Brunswick	2	I-140 WB (JOHN JAY BURNEY JR. HWY.)	FROM US 74 / 76 (ANDREW JACKSON HWY.) TO US 17 (OCEAN HWY E.) [MP 0.82 TO MP 5.76]	1	2	2WD	NO	NO	4.94	41	2,470	9.88	118,824	22,092	1,579	4,801	52,166	1,700	1	2	1	2			137		
TOTAL FOR MAP NO. 2										**4.94**		**2,470**	**9.88**	**118,824**	**22,092**	**1,579**	**4,801**	**52,166**	**1,700**	**1**	**2**	**1**	**2**			**137**		
47985.3.1	Brunswick	3	I-140 RAMP # 6560	FROM GORE AT US 17 (OCEAN HWY. E.) TO OVERPASS AT I-140 [MP 0.04 TO MP 0.60]	2	2		NO	NO	0.56	33	187	1.03	10,842	1,927	143	503	50									10	*
TOTAL FOR MAP NO. 3										**0.56**		**187**	**1.03**	**10,842**	**1,927**	**143**	**503**	**50**									**10**	*
47985.3.1	Brunswick	4	I-140 RAMP # 6563	FROM GORE AT US 17 (OCEAN HWY. E.) TO GORE AT I-140 [MP 0.11 TO MP 0.33]	2	1		NO	NO	0.22	28	74	0.44	3,614	632	52	240	50									5	*
TOTAL FOR MAP NO. 4										**0.22**		**74**	**0.44**	**3,614**	**632**	**52**	**240**	**50**									**5**	*
47985.3.1	Brunswick	5	I-140 RAMP # 6562	FROM GORE AT I-140 TO GORE AT US 17 (OCEAN HWY. E.) [MP 0.09 TO MP 0.30]	2	2		NO	NO	0.21	33	70	0.42	4,066	723	58	267	50									10	*
TOTAL FOR MAP NO. 5										**0.21**		**70**	**0.42**	**4,066**	**723**	**58**	**267**	**50**									**10**	*
47985.3.1	Brunswick	6	I-140 RAMP # 6561	FROM OVERPASS AT I-140 TO GORE AT US 17 (OCEAN HWY. E.) [MP 0.00 TO MP 0.24]	2	1		NO	NO	0.24	27	80	0.48	3,802	677	55	250										5	*
TOTAL FOR MAP NO. 6										**0.24**		**80**	**0.48**	**3,802**	**677**	**55**	**250**										**5**	*
TOTAL FOR PROJ NO. 47985.3.1										**11.11**		**5,351**	**22.13**	**259,972**	**48,143**	**3,466**	**10,862**	**104,482**	**3,280**	**3**	**3**	**4**	**2**	**1**	**1**	**274**	**30**	**1**
GRAND TOTAL										**11.11**		**5,351**	**22.13**	**259,972**	**48,143**	**3,466**	**10,862**	**104,482**	**3,280**	**3**	**3**	**4**	**2**	**1**	**1**	**274**	**30**	**1**