



NOTES:

1. FIVE (5) DAYS PRIOR TO BEGINNING WORK ON THE SIGNAL SYSTEM/CCTV INSTALLATION, CONTACT THE DIVISION TRAFFIC ENGINEER AT (252)640-6502 TO ARRANGE FOR THE DIVISION TO PROGRAM THE NEW FIELD ETHERNET SWITCHES WITH THE NECESSARY NETWORK CONFIGURATION DATA, INCLUDING BUT NOT LIMITED TO: THE PROJECT IP ADDRESS, DEFAULT GATEWAY, SUBNET MASK AND VLAN ID INFORMATION. NOTIFY THE DIVISION TRAFFIC ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY. WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
2. CONTRACTOR TO RECORD EXISTING SPLICE ARRANGEMENT FOR COMPARISON TO THE SUPPLIED SPLICE DETAILS. IF DISCREPANCIES EXIST, CONTACT THE DIVISION ENGINEER TO DETERMINE HOW TO PROCEED WITH RESPLICING. PROVIDE AS-BUILT PLANS TO THE ENGINEER IF FINAL SPLICE ARRANGEMENT DIFFERS FROM THE SUPPLIED SPLICE DETAILS.
3. ALL NEW NCDOT FIBER ATTACHMENTS ARE 40" BELOW NEUTRAL, FRONT SIDE OF POLE, UNLESS OTHERWISE NOTED.
4. ABANDON IN PLACE THE EXISTING 12-FIBER CABLE BETWEEN EXISTING SPLICE ENCLOSURE AT 04-1360 AND POLE 'PQ04BA'. CUT AND DISPOSE OF 12-FIBER CABLE NOT ATTACHED TO MESSENGER CABLE (HANGING FROM POLE PQ04BA AND COILED ON GROUND).

RK&K
 P: (919) 878-8560
 8801 Six Forks Road Suite 700 | Raleigh, North Carolina 27615-2965
 NC License No. F-0112
 www.rk.com
 Responsive People | Creative Solutions

Prepared for the Offices of:

 750 N. Greenfield Pkwy., Garner, NC 27529

I-5972
 Signal Communications Plans
 TMP Phase IV Steps 1 & 2
 Division 4 Johnston County Smithfield
 PLAN DATE: September 2023 REVIEWED BY: DT Sears
 PREPARED BY: WP Erickson-Jones REVIEWED BY:
 REVISIONS INIT. DATE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SEAL
 NORTH CAROLINA PROFESSIONAL ENGINEER
 SEAL 044558
 DAVID T. SEARS
 DocuSigned by:
 David T. Sears 9/19/2023
 SIGNATURE DATE
 CADD Filename: