STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

TEMPORARY GUARDRAIL SUMMARY

SURVEY LINE	BEG. STA.	END STA.	LOCATION	LENGTH			WARRANT POINT		"N" DIST. FROM E.O.L.	TOTAL SHOUL WIDTH	FLARE LENGTH		W		ANCHORS									CRASH CUSHION	PORTABLE CONCRETE BARRIER	REMOVE & RESET EXISTING GUARDRAIL	REMOVE & STOCKPILE EXISTING GUARDRAIL	REMARKS
				STRAIGHT	SHOP CURVED	DOUBLE FACED	APPROACH END	TRAILING END			APPROACH END	TRAILING END	APPROACH END	TRAILING END	XI MOD	XI	GREU TL-3	MEDIA N TL-3	XIII	CAT-1	B-77	AT-1	TES	TYPE III					
L_DET1	10+00.66	19+41.12	LT	937.50'			--	10+41	4'	6'	50	50	1	1			2												
L_DET1	19+71.15	24+64.90	LT	500.00'			24+93	--	4'	6'	50	50	1	1			2												
L_DET1	16+78.71	34+97.64	RT				19+74	28+42																	2	1773			SEE TMP PLANS FOR MORE INFORMATION
L_DET1	29+73.26	36+01.57	LT	625.00'			35+22	30+85	4'	6'	50	50	1	1			2												
L_DET1	36+21.07	39+98.00	LT	375.00'			38+21	39+72	4'	6'		50		1			1												
L_DET2	14+58.18	16+17.91	LT	160.38'			21+70	16+18	4'	6'		50		1			1				1								
L_DET2	21+70.64	23+31.01	LT	160.38'			21+70	16+18	4'	6'	50		1				1				1								
L_DET2	16+17.91	21+69.85	LT																							554			SEE TMP PLANS FOR MORE INFORMATION
												50																	
L_DET3	10+00.00	18+02.66	LT																						2	775			SEE TMP PLANS FOR MORE INFORMATION
L_DET3	11+18.04	18+00.24	RT	687.50'			12+72	17+34	4'	6'	50	50	1	1			2												
L_DET 4	12+62.98	18+93.37	LT	637.50'			17+93	13+34	4'	6'	50	50	1	1			2												
L_DET 4	29+00.00	39+50.00	RT	1050.00'			30+50	39+00	4'	6'	50	50	1	1			2												
L_DET 4	39+07.46	42+98.89	LT	387.50'			41+80	40+28	4'	6'		50		1			1												
TEMPORARY GUARDRAIL (TRAFFIC CONTROL) : PHASE 1																													
-L-	18+89.19	21+14.73	LT	225.00'			19+39	20+64	2'	4'	50	50	1	1			2												
-L-	21+93.69	26+94.01	LT	500.00'			22+44	26+44	2'	4'	50	50	1	1			2												
-L-	28+03.20	31+28.32	LT	325.00'			30+78	28+53	2'	4'	50	50	1	1			2												
-L-	68+26.27	73+91.00	RT	537.50'	43.75'		68+77	73+91	2'	4'	50		1	1			1			1									
-L-	71+55.00	71+75.00	LT		37.50'		71+75		2'	4'												1							
-L-	169+73.63	173+62.18	LT	387.50'			39+58	42+99	2'	4'	50		1				1												
-L-	153+09.00	160+84.00	RT																								775		
TEMPORARY GUARDRAIL (TRAFFIC CONTROL) : PHASE 2																													
-L-	78+00.00	78+99.00	LT																								99		
			SHEET TOTALS	7495.75	81.25										0	0	24	0	0	1	2	1	0	0	4	3102	875		SEE TMP PLANS FOR MORE INFORMATION
		LESS ANCHOR DEDUCTIONS																											
		QUANTITY	LF PER EA	TOTAL LF																									
	GREU TL-3	24	50	1200																									
	CAT-1	1	6.25		6.25																								
	TYPE III	0	18.75	0																									
	TYPE B-77	2	22.875	45.75																									
	AT-1	1	6.25		6.25																								
R-5861 TOTAL (LF)				6,250.00	68.75																								
R-5861 SAY (LF)				6,262.50	75.00										0	0	24	0	0	1	2		0	0	4	3102	875		

RK&K
P: (919) 878-9560
8601 Six Forks Road, Forum 1,Suite 700
Raleigh, North Carolina 27615-3960
NC License No. F-0112
Engineers | Construction Managers | Planners | Scientists
www.rkk.com
Responsive People | Creative Solutions

8/17/99
12/12/2023
R:\Roadway\Proj\R5861_Rdy_sht03B-5.dgn
default