STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
B-5981	X-1A

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
12+00.00	0	0	0
12+50.00	15	0	51
13+00.00	15	0	105
13+50.00	18	0	120
14+00.00	16	0	155
14+50.00	13	0	194
15+00.00	13	0	228
15+50.00	12	0	258
16+00.00	9	0	309
16+50.00	8	0	406
17+00.00	7	0	572
17+50.00	6	27	797
18+00.00	6	129	1039
18+50.00	6	38	1293
19+00.00	6	0	1560
19+50.00	5	46	1837
20+00.00	4	194	2101
20+50.00	3	213	2346
21+00.00	2	222	2528
21+50.00	1	56	2590
22+00.00	0	0	3114
22+26.39	0	0	1919
22+26.39	ENDBENT #1		810

Station L	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
25+50.89	ENDBENT #2		248
25+50.89	0	0	0
26+00.00	0	0	1533
26+50.00	0	0	1520
27+00.00	0	0	1477
27+50.00	0	0	1298
28+00.00	0	0	1028
28+50.00	0	0	788
29+00.00	0	0	377
29+50.00	0	0	72
30+00.00	0	0	59
30+50.00	0	0	57
31+00.00	0	0	62
31+50.00	0	0	56
32+00.00	0	0	35
32+50.00	8	0	12
33+00.00	15	0	1
33+50.00	15	0	0
33+55.00	1	0	0

Station Y1	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0	0
10+50.00	0	0	342
11+00.00	0	0	180
11+50.00	0	0	69
12+00.00	1	0	19
12+50.00	6	0	2
13+00.00	14	0	5
13+50.00	19	0	5
14+00.00	24	0	0
14+25.00	14	0	0

Station SR1 (L STA.)	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
12+50.00	0	0	0
13+00.00	82	0	60
13+50.00	76	0	39
14+00.00	79	0	26
14+50.00	82	0	20
15+00.00	79	0	20
15+50.00	76	0	28
16+00.00	72	0	40
16+50.00	63	0	56
17+00.00	52	350	80
17+50.00	42	166	99
18+00.00	36	253	104
18+50.00	33	172	88
19+00.00	29	84	92
19+50.00	23	165	111
20+00.00	19	253	110
20+50.00	19	247	86
21+00.00	23	249	88
21+50.00	17	128	114
22+00.00	6	0	116

Station SR1	Uncl. Exc. (cu. yd.)	Undercut (cu. yd.)	Embt (cu. yd.)
20+66.54	0	0	0
21+00.00	2	0	76
21+50.00	1	0	123
22+00.00	1	0	123
22+50.00	4	0	96
23+00.00	7	0	63
23+50.00	11	0	30
24+00.00	12	0	13
24+50.00	8	0	6
24+60.00	1	0	6