



NOTES

1. INSTALL A MINIMUM OF THREE (3) GROUNDING ELECTRODES SPACED A MINIMUM OF 10 FEET APART. ENSURE THAT EXISTING UNDERGROUND FACILITIES ARE NOT DAMAGED DURING INSTALLATION.
2. TEST GROUNDING SYSTEM USING AN APPROVED METHOD. SYSTEM SHOULD MEASURE TWENTY (20) OHMS OR LESS. ADDITIONAL GROUNDING ELECTRODES SHALL BE INSTALLED AS DIRECTED BY THE ENGINEER TO MEET THIS REQUIREMENT.
3. MECHANICALLY CRIMP ALL CONNECTIONS TO GROUND RODS USING AN IRREVERSIBLE COMPRESSION TOOL.
4. INSTALL MARKER TAPE DIRECTLY ABOVE ALL GROUNDING ELECTRODES AND CONDUCTORS AT A DEPTH OF 12 INCHES.
5. REMOVE BONDING JUMPER IN EQUIPMENT CABINET IF INSTALLED BETWEEN AC NEUTRAL AND EQUIPMENT GROUND.
6. BOND ALL RIGID GALVANIZED STEEL CONDUITS ENTERING THE CABINET TO "EQUIPMENT GROUND".
7. INSTALL CONDUIT BETWEEN DISCONNECT AND CABINET.
8. ENSURE EQUIPMENT GROUND IS ELECTRICALLY BONDED TO CABINET.

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

	Prepared for the Offices of: DYNAMIC MESSAGE SIGN WITH UNDERGROUND ELECTRICAL SERVICE TYPICAL DETAIL		
	Division 14 Haywood County Waynesville	PLAN DATE: August 2023 REVIEWED BY: R. Garrett	
750 N. Greenfield Pkwy., Garner, NC 27529	REVISIONS	INIT. DATE	DocuSigned by: Rochelle Garrett 8/4/2023 SIGNATURE DATE CADD Filename:

8/4/2023
 pw://becomac-pw-bentley.com:AECDMLUSA_NorthCaroIina/Documents/60610967-1-NCDDT_B5898_B3186/900-CAD_615/910-CAD/70-NCDDT_TIP/Intelligent Transportation Systems/B-5898_ITS_PSH29.dgn
 Tindal M