

COMPUTING EARTHWORKS FOR BASELINE = L
 COMPUTING EARTHWORKS FOR JOB = RDY
 FORMING LIST OF XSCELLS
 BEGINNING EARTHWORKS COMPUTATION

↑

Station	Material Name	End Areas (sq. ft.)	Unadjusted Volumes (cu. yd.)	Adjusted Volumes (cu. yd.)	Mult Factor	Mass Ordinate
19+00.00	SUITABLE					
	Excavation	0.00	0	0	1.00	
	Fill	224.99	0	0	1.00	0
19+50.00	SUITABLE					
	Excavation	0.00	0	0	1.00	
	Fill	163.37	360	360	1.00	-360
20+00.00	SUITABLE					
	Excavation	0.00	0	0	1.00	
	Fill	123.80	266	266	1.00	-626
20+50.00	SUITABLE					
	Excavation	0.00	0	0	1.00	
	Fill	121.60	227	227	1.00	-853
21+00.00	SUITABLE					
	Excavation	0.00	0	0	1.00	
	Fill	126.25	229	229	1.00	-1082
21+50.00	SUITABLE					
	Excavation	0.00	0	0	1.00	
	Fill	106.63	216	216	1.00	-1298
22+00.00	SUITABLE					
	Excavation	0.00	0	0	1.00	
	Fill	82.59	175	175	1.00	-1473
22+50.00	SUITABLE					
	Excavation	0.00	0	0	1.00	
	Fill	54.78	127	127	1.00	-1600
23+00.00	SUITABLE					
	Excavation	1.45	1	1	1.00	
	Fill	10.04	60	60	1.00	-1659
23+50.00	SUITABLE					
	Excavation	20.68	20	20	1.00	
	Fill	1.19	10	10	1.00	-1649
24+00.00	SUITABLE					
	Excavation	19.27	37	37	1.00	

	Fill	0.00	1	1	1.00	-1613
24+50.00	SUITABLE					
	Excavation	49.70	64	64	1.00	
	Fill	0.00	0	0	1.00	-1549
25+00.00	SUITABLE					
	Excavation	58.82	100	100	1.00	
	Fill	0.00	0	0	1.00	-1449
25+50.00	SUITABLE					
	Excavation	15.78	69	69	1.00	
	Fill	0.86	1	1	1.00	-1381
26+00.00	SUITABLE					
	Excavation	3.35	18	18	1.00	
	Fill	1.95	3	3	1.00	-1366

↑

G R A N D S U M M A R Y T O T A L S

Material Name	Unadjusted Volumes (cu. yd.)	Adjusted Volumes (cu. yd.)	Multi Factor
---------------	------------------------------------	----------------------------------	-----------------

SUITABLE

Excavation	309	309	1.00
Fill	1675	1675	1.00