PROJECT NO.: U-5873 SHEET OF
COMPUTED BY: A. Weeks
CHECKED BY: F. Masterson SECTION: 607

INCIDENTAL MILLING

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS	
-L-	12+19		RT	66	28	7	*
-L-	13+27		RT	187	35	21	*
-L-	13+96		LT	79	25	9	*
-L-	14+18		RT	130	25	14	*
-L-	14+32		LT	91	17	10	*
-L-	14+47		RT	86	35	10	*
-Y1-	10+54		LT/RT	1363		151	*
-Y1-	10+69		RT	86	17	10	*
-Y1-	10+96		RT	103	20	11	*
-Y1-	11+10		LT	79	17	9	*
-Y1-	11+44		RT	102	20	11	*
-Y1-	12+11		RT	42	17	5	*
-Y1-	13+01		RT	86	17	10	*
-Y1-	13+38		RT	493		55	*
-Y2-	15+66		LT	91	17	10	*
-Y2-	17+96		RT	86	17	10	*
-Y2-	18+82		LT	79	17	9	*
-Y3-	10+70		LT	177	23	20	*
					TOTAL	381	
					SAY	**390**	

PROJECT NO.: U-5873 **SHEET OF**
COMPUTED BY: A. Weeks
CHECKED BY: F. Masterson **SECTION: 607**

MILLING ASPHALT PAVEMENT, 1.5" DEPTH

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
-L-	12+58	15+44	LT/RT	8308		923
-Y2-	11+57	20+00	LT/RT	1298		144
-Y3-	10+10	11+30	LT/RT	2643		294
-Y5-	11+15	12+10	LT/RT	1824		203
-Y5-	14+96	15+86	LT/RT	2003		223
-Y6-	10+11	11+94	LT/RT	4065		452
					TOTAL	2,238
					SAY	**2,240**

PROJECT NO.: U-5873
COMPUTED BY: A. Weeks
CHECKED BY: F. Masterson **SECTION: 607**

MILLING ASPHALT PAVEMENT, 3" DEPTH

LINE	STATION	STATION	LOCATION	LENGTH OR AREA	WIDTH	SQUARE YARDS
					TOTAL	
					SAY	