PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.12.02.10181, 2024CPT.12.02.20181	11	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1½" MILLING	1308000000-E 0" TO 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1519000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1520000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	1523000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1524000000-E ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2612300000-N RETROFIT EXST. CONCRETE CURB RAMPS	2830000000-N ADJUSTMENT OF MANHOLES	2845000000-N ADJUSTMENT OF METER BOXES OR VALVE BOXES	2846000000-N ADJUSTMENT OF OVERSIZED MANHOLE	5255000000-N PORTABLE LIGHTING	7324000000-N JUNCTION BOX (STANDARD SIZE)	7444000000-E INDUCTIVE LOOP	7456100000-E LEAD-IN CABLE, 14-2
										MI	FT			TONS	SMI	TON	SY	SY	SY	TON	TON	TON	TON	TONS	TONS	EA	EA	EA	EA	LS	EA	LF	LF
2024CPT.12.02.10181	Catawba	1	US-70 W	FROM US 321 TO BURKE CO	1, 2, 3	2		NO	NO	2.56	36	0	2.56		4.20	252	21,625		1,500			8,207		489	100		2	1		*	1	1,400	100
TOTAL FOR PROJ NO. 2024CPT.12.02.10181										**2.56**					**4.20**	**252**	**21,625**		**1,500**			**8,207**		**489**	**100**		**2**	**1**		*****	**1**	**1,400**	**100**
2024CPT.12.02.20181	Catawba	2	SR-2043/2044 BANOAK RD	FROM NC 10 TO LINCOLN CO	2	2	2WU	NO	NO	1.52	18	0	1.52	60	3.04	185			260			1,426		87	60								
2024CPT.12.02.20181	Catawba	3	SR-1692 OO / 1ST AV SW	FROM SR 1007 (LR BLVD) TO 17TH ST SW	4, 8, 9	2		NO	NO	2.33	23	3.501	5.831				41,050					3,287		206	250	2	82	46	24	*			
2024CPT.12.02.20181	Catawba	4	SR-2231 OI / 2ND AV SE	FROM NC 127 TO EXST PVMT JOINT 250' W OF SR 1007 (LR BLVD)	4	2		NO	NO	0.46	24	1.97	2.43				9,720					856		51	20		10	12		*			
2024CPT.12.02.20181	Catawba	5	SR-1358 / 4TH ST SW	FROM US 70 TO SR 2231 (2ND AVE SW)	4	2	2WU	NO	NO	0.7	22	0	0.7				14,025					1,260		75	20		24	24		*		426	50
2024CPT.12.02.20181	Catawba	6	SR-1485 / 10TH ST NW	FROM SR 1007 (1ST ST W) TO SR 1484 (COUNTY HOME RD)	4	2	2WU	NO	NO	0.557	36	0	0.557				10,800					956		56			8					200	50
2024CPT.12.02.20181	Catawba	7	SR-1544 / ADAM ST	FROM SR 1441 (SPENCER RD) TO SR 1491 (SECTION HOUSE RD)	2	2	2WU	NO	NO	0.98	20	0	0.98	20	1.92	120	2,160		880			1,021		65	100			2					
2024CPT.12.02.20181	Catawba	8	SR-1701 / HAFER RD	FROM SR 1700 (RIVERBEND RD) TO CUL-DE-SAC	2, 7	2	2WU	NO	NO	0.44	21	0	0.44		0.88	55		180	250			504		33	60								
2024CPT.12.02.20181	Catawba	9	SR-1154 / RADIO STATION RD	FROM SR 1149 (CONOVER STARTOWN RD) TO US 321 BUS	2, 4	2	2WU	NO	NO	1.14	22	0	1.14		2.28	140	3,100					1,305		77				2				275	50
2024CPT.12.02.20181	Catawba	10	SR-1153 / LONG DR	FROM NC 10 TO SR 1154 (RADIO STATION RD)	2	2	2WU	NO	NO	0.74	20	0	0.74	15	1.48	90			150			771	513	78	40								
2024CPT.12.02.20181	Catawba	11	SR-2015 / JARRETT FARM RD	FROM NC 10 TO NC 10	2	2	2WU	NO	NO	1.47	18	0	1.47		2.94	180			250			1,379		93	250								
2024CPT.12.02.20181	Catawba	12	SR-1884 / SMYRE FARM RD	FROM US 321 BUS TO SR 1880 (ST JAMES CH RD)	2	2	2WU	NO	NO	1.34	22	0	1.34		2.68	160			365			1,534		103	260								
2024CPT.12.02.20181	Catawba	13	SR-1155 / W 7TH ST	FROM SR 1149 (OLD CONOVER STARTOWN RD) TO US 321 BUS	2, 4	2	2WU	NO	NO	0.96	22	0	0.96		1.83	110	1,550		340			1,130		71	100				2			461	50
2024CPT.12.02.20181	Catawba	14	SR-1156 / W 15TH ST	FROM SR 1149 (OLD CONOVER STARTOWN RD) TO US 321 BUS	2, 4	2	2WU	NO	NO	0.69	21	0	0.69	20	1.93	120	3,700		140			776		58	250		4	1				404	50
2024CPT.12.02.20181	Catawba	15	SR-1713 / 1ST ST E	FROM US 70 TO NC 16 BUS	4	2	2WU	NO	NO	0.45	48	0	0.45				13,350					1,176		69			12	10		*		800	50
2024CPT.12.02.20181	Catawba	16	SR-1442 / 23RD ST NE	FROM SR 1441 (12TH AVE DR NE) TO CUL-DE-SAC	2, 4	2	2WU	NO	NO	0.21	18	0	0.21		0.42	30	130		100			203		16	20		1	1					
2024CPT.12.02.20181	Catawba	17	SR-1657 / 32ND AV NE	FROM SR 1502 (39TH ST NE) TO END MAINT	5	2	2WU	NO	NO	0.42	20	0	0.42							286	50			19				3					
2024CPT.12.02.20181	Catawba	18	SR-1684 / 33RD AV NE	FROM SR 1502 (28TH ST NE) TO SR 2394 (24TH ST NE)	5	2		NO	NO	0.4	20	0	0.4							272				18									
2024CPT.12.02.20181	Catawba	19	SR-2394 / 24TH ST NE	FROM SR 1657 (32ND AVE NE) TO SR 1684 (33RD AVE NE)	5	2	2WU	NO	NO	0.11	20	0	0.11							75				5									
2024CPT.12.02.20181	Catawba	20	SR-1685 / 25TH ST NE	FROM SR 1684 (33RD ST NE) TO SR 1657 (32ND ST NE)	5	2	2WU	NO	NO	0.11	20	0	0.11							75				5									
2024CPT.12.02.20181	Catawba	21	SR-1686 / 25TH ST CT NE	FROM SR 1684 (33RD ST NE) TO SR 1657 (32ND ST NE)	5	2	2WU	NO	NO	0.11	20	0	0.11							75				5									
2024CPT.12.02.20181	Catawba	22	SR-1687 / 26TH ST NE	FROM SR 1684 (33RD ST NE) TO SR 1657 (32ND ST NE)	5	2	2WU	NO	NO	0.11	20	0	0.11							75				5	10			1					
2024CPT.12.02.20181	Catawba	23	SR-1688 / 27TH ST NE	FROM SR 1684 (33RD ST NE) TO SR 1657 (32ND ST NE)	5	2	2WU	NO	NO	0.11	20	0	0.11							75				5				3					
2024CPT.12.02.20181	Catawba	24	SR-1689 / 27TH ST PL NE	FROM SR 1684 (33RD ST NE) TO SR 1657 (32ND ST NE)	5	2	2WU	NO	NO	0.11	20	0	0.11							75				5				6					
2024CPT.12.02.20181	Catawba	25	SR-1815 / LITTLE MOUNTAIN RD	FROM SR 1810 (BALLS CREEK RD) TO SR 1003 (BUFFALLO SHOALS RD)	2, 6	2	2WU	NO	NO	1.72	22	0	1.72	60	3.44	210	1,300		300			1,969		121	100								
TOTAL FOR PROJ NO. 2024CPT.12.02.20181										**17.187**				**175**	**22.84**	**1,400**	**100,885**	**180**	**3,035**	**1,008**	**50**	**19,553**	**513**	**1,326**	**1,540**	**2**	**141**	**111**	**26**	*****		**2,566**	**300**
GRAND TOTAL										**19.747**				**175**	**27.04**	**1,652**	**122,510**	**180**	**4,535**	**1,008**	**50**	**27,760**	**513**	**1,815**	**1,640**	**2**	**143**	**112**	**26**	**1**	**1**	**3,966**	**400**