PROJECT REFERENCE NO.	SHEET NO.
HI-0015	SIGN-1

DocuSigned by:
CAF5DBCB928F4E2...
11/17/2023

NORTH CAROLINA PROFESSIONAL SEAL 047118 ENGINEER RICHARD D. LASHER, JR.

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
COLUMBUS COUNTY

LOCATION: US 74 (FUTURE I-74) FROM WEST OF NC 214 TO WEST OF WATER TANK ROAD (SR 1824)

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.50	ARROWS AND SHIELDS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.40	MILEPOST AND PLACEMENT
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL SUPPORTS

GENERAL NOTES

- SIGNS FURNISHED BY STATE
- CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'D', 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING, SEE TRAFFIC CONTROL PLANS. SEE PAVEMENT MARKING PLAN FOR PAVEMENT MARKING DESIGN.

PAY ITEM NOTES

1. DISPOSAL OF SIGN AND SIGN ERECTION, ALL SIGNS TYPE D, E AND F
2. SIGN ERECTION, TYPE E
3. SIGN ERECTION, TYPE F
4. DISPOSAL OF SIGN, ALL SIGNS TYPE D, E AND F
5. DISPOSAL OF SIGN AND SIGN ERECTION, MILE MARKERS

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4072000000-E	903	SUPPORTS, 3 LB STEEL U CHANNEL	1670	LF
4078000000-E	903	SUPPORTS, 2 LB STEEL U CHANNEL	16	EA
4096000000-N	904	SIGN ERECTION TYPE D	3	EA
4102000000-N	904	SIGN ERECTION TYPE E	57	EA
4108000000-N	904	SIGN ERECTION TYPE F	6	EA
4114000000-N	904	SIGN ERECTION MILE MARKERS	16	EA
4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	65	EA
4238500000-N	907	DISPOSAL OF SIGN, MILE MARKER	16	EA

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2	TYPE E AND F SIGNS
SIGN-3	TYPE D SIGNS
SIGN-4-12	SIGNING PLAN SHEETS

PLAN SUBMITTED TO: NCDOT SIGNING AND DELINEATION UNIT

MITCH EATON, PE — SIGNING & DELINEATION REGIONAL ENGINEER

STACEY JOHNS — SIGNING & DELINEATION PROJECT DESIGN ENGINEER

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

8/17/99
11/17/2023
G:\2019\1900765.002_HI-0016_US_74_From_E\CADD\HI-0015\Traffic\Signing\HI-0015_SIGN_01.dgn
User:Blankenship