PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.12.05.20491	15	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	1260000000-E AGGREGATE SHOULDER BORROW	1220000000-E INCIDENTAL STONE BASE	1245000000-E SHOULDER RECONSTRUCTION	1297000000-E 1" MILLING	1297000000-E 1½" MILLING	1308000000-E 0" TO 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1520000000-E LEVELING COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1524000000-E LEVELING COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT
										MI	FT			TON	TONS	SMI	SY	SY	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	TONS
2024CPT.12.05.20491	Iredell	1	SR-1446 / COOLEY RD	FROM SR 1445 (KEMP RD.) TO DEAD END	1	2		NO	NO	0.261	18	1.757	2.018	90	15	0.52						190	75			21	75
TOTAL FOR MAP NO. 1										**0.261**				**90**	**15**	**0.52**						**190**	**75**			**21**	**75**
2024CPT.12.05.20491	Iredell	2	SR-1445 / KEMP RD	FROM SR 1446 (COOLEY RD.) TO SR 1115 (MCKENDREE RD.)	1	2		NO	NO	0.721	20	0	0.721	240	40	1.44				165		530	100			46	100
TOTAL FOR MAP NO. 2										**0.721**				**240**	**40**	**1.44**				**165**		**530**	**100**			**46**	**100**
2024CPT.12.05.20491	Iredell	3	SR-2923 / CHATWORTH LN	FROM SR 1179 (CANVASBACK RD.) TO CUL-DE-SAC	1	2		NO	NO	0.069	20	0	0.069	30	5	0.16				40		80	50			11	50
TOTAL FOR MAP NO. 3										**0.069**				**30**	**5**	**0.16**				**40**		**80**	**50**			**11**	**50**
2024CPT.12.05.20491	Iredell	4	SR-2361 / MCNESS RD	FROM SR 2638 (SALISBURY HWY.) TO END OF MAINTANANCE	1	2		NO	NO	0.076	24	0	0.076	30	5	0.16				30		70	20			7	30
TOTAL FOR MAP NO. 4										**0.076**				**30**	**5**	**0.16**				**30**		**70**	**20**			**7**	**30**
2024CPT.12.05.20491	Iredell	5	SR-2141 / DUNLAP GATE RD	FROM US 21 TO SR 2158 (OLD MOCKSVILLE RD.)	1	2		NO	NO	1.504	20	0	1.504	500	75	3.00				180		1,100	225			95	175
TOTAL FOR MAP NO. 5										**1.504**				**500**	**75**	**3.00**				**180**		**1,100**	**225**			**95**	**175**
2024CPT.12.05.20491	Iredell	6	SR-2366 / PERRY RD./HOOVER RD./CREEKS EDGE LN	FROM US 21 TO CUL-DE-SAC	1	2		NO	NO	1.582	20	0	1.582	525	80	3.16	112			150		1,175	100			86	75
TOTAL FOR MAP NO. 6										**1.582**				**525**	**80**	**3.16**	**112**			**150**		**1,175**	**100**			**86**	**75**
2024CPT.12.05.20491	Iredell	7	SR-1916 / LENTZ RD	FROM SR 1890 (TOMLIN MILL RD.) TO SR 1892 (JENNINGS RD.)	1	2		NO	NO	1.956	20	0	1.956	655	100	3.95				100		1,440	220			113	100
TOTAL FOR MAP NO. 7										**1.956**				**655**	**100**	**3.95**				**100**		**1,440**	**220**			**113**	**100**
2024CPT.12.05.20491	Iredell	8	SR-1873 / N CHIPLEY FORD RD	FROM SR 1896 (FRIENDSHIP RD.) TO SR 1898 (DOBSON FARM RD)	1	2		NO	NO	2.031	20	0	2.031	670	105	4.06	223			60		1,450	125			107	100
TOTAL FOR MAP NO. 8										**2.031**				**670**	**105**	**4.06**	**223**			**60**		**1,450**	**125**			**107**	**100**
2024CPT.12.05.20491	Iredell	9	SR-1898 / N CHIPLEY FORD RD	FROM SR 1873 (NORTH CHIPLEY FORD RD.) TO SR 1903 (SNOW CREEK RD.)	1	2		NO	NO	1.743	20	2.39	4.133	575	90	3.48	112			120		1,235	150			94	75
TOTAL FOR MAP NO. 9										**1.743**				**575**	**90**	**3.48**	**112**			**120**		**1,235**	**150**			**94**	**75**
2024CPT.12.05.20491	Iredell	10	SR-1328 / EAST MONBO RD	FROM SR 1005 (OLD MOUNTAIN RD.) TO SR 2801 (HIGHLAND VIEW DR.)	2, 4	2		NO	NO	4.91	20	0	4.91	1,620	250	9.82		2,000		200				5,420	350	354	275
TOTAL FOR MAP NO. 10										**4.91**				**1,620**	**250**	**9.82**		**2,000**		**200**				**5,420**	**350**	**354**	**275**
2024CPT.12.05.20491	Iredell	11	SR-1903 / SNOW CREEK RD	FROM NC 115 TO SR 1892 (JENNINGS RD.)	3	2		NO	NO	4.555	20	0	4.555	1,505	230	9.12				210	2,500			5,035	275	433	150
TOTAL FOR MAP NO. 11										**4.555**				**1,505**	**230**	**9.12**				**210**	**2,500**			**5,035**	**275**	**433**	**150**
2024CPT.12.05.20491	Iredell	12	SR-1005 / OLD MOUNTAIN RD	FROM ALEXANDER COUNTY LINE TO BRIDGE #90 OVER I-40	2	2		NO	NO	5.732	20	0	5.732	1,900	300	11.46			245	690				6,325	300	400	200
TOTAL FOR MAP NO. 12										**5.732**				**1,900**	**300**	**11.46**			**245**	**690**				**6,325**	**300**	**400**	**200**
2024CPT.12.05.20491	Iredell	13	SR-2321 OI / E BROAD ST	FROM I-3819B PROJECT LIMITS TO SR 2320 (S.GREENBRIAR)	2, 4, 5	2		NO	NO	1.51	20	1.973	3.483	425	65	2.50		7,670	450	100				2,600	120	163	50
TOTAL FOR MAP NO. 13										**1.51**				**425**	**65**	**2.50**		**7,670**	**450**	**100**				**2,600**	**120**	**163**	**50**
2024CPT.12.05.20491	Iredell	14	SR-2333 / EASTSIDE DR	FROM I-3819B PROJECT LIMITS TO SR 2735 (SALISBURY RD.)	2, 5, 6, 7	2		NO	NO	1.04	22	0.124	1.164	350	55	2.08		5,000		180				1,740	120	113	75
TOTAL FOR MAP NO. 14										**1.04**				**350**	**55**	**2.08**		**5,000**		**180**				**1,740**	**120**	**113**	**75**
2024CPT.12.05.20491	Iredell	15	SR-1245 / MEDICAL PARK RD	FROM US 21 TO SR 1246 (FAIRVIEW RD)	4, 5, 6, 8	2		NO	NO	0.601	35	0	0.601	135	25	0.78		13,000		60				1,350		80	10
TOTAL FOR MAP NO. 15										**0.601**				**135**	**25**	**0.78**		**13,000**		**60**				**1,350**		**80**	**10**
2024CPT.12.05.20491	Iredell	16	SR-1421 / WILSON W LEE BLVD	FROM SR 1338 (WALLACE SPRINGS RD.) TO PAVEMENT CHANGE NORTH OF US 70	2, 9	2		NO	NO	0.701	30	0.251	0.952	25	5	0.14		12,000		100				1,200	20	73	25
TOTAL FOR MAP NO. 16										**0.701**				**25**	**5**	**0.14**		**12,000**		**100**				**1,200**	**20**	**73**	**25**
TOTAL FOR PROJ NO. 2024CPT.12.05.20491										**28.992**				**9,275**	**1,445**	**55.83**	**447**	**39,670**	**695**	**2,385**	**2,500**	**7,270**	**1,065**	**23,670**	**1,185**	**2,196**	**1,565**
GRAND TOTAL										**28.992**				**9,275**	**1,445**	**55.83**	**447**	**39,670**	**695**	**2,385**	**2,500**	**7,270**	**1,065**	**23,670**	**1,185**	**2,196**	**1,565**