PROJECT NO.	SHEET NO.
2024CPT.08.09.10621, 2024CPT.08.09.20621	16

THERMOPLASTIC AND PAINT QUANTITIES

												4820000000-E		4825000000-E	4830000000-E	4835000000-E	4840000000-N			4845000000-N						4850000000-E	4860000000-E	4870000000-E	4875000000-N	4891000000-E	4905100000-N	
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	8" YELLOW PAINT	8" WHITE PAINT	12" YELLOW PAINT	16" WHITE PAINT	24" WHITE PAINT	PAINT MSG RXR	PAINT MSG SCHOOL	PAINT MSG ONLY	PAINT YIELD LINE TRIANGLE	PAINT RT ARROW	PAINT LT ARROW	PAINT STR ARROW	PAINT STR & RT ARROW	PAINT STR & LT ARROW	4" LINE REMOVAL	8" LINE REMOVAL	24" LINE REMOVAL	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	GENERIC PAVEMENT MARKING ITEM REMOVAL OF 16" PAVEMENT MARKING LINES	NON-CAST IRON SNOW-PLOWABLE PAVEMENT MARKER C&R	NON-CAST IRON SNOW-PLOWABLE PAVEMENT MARKER Y&Y
								MI	FT			LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	EA	LF	EA	EA
2024CPT.08.09.10621	Montgomery	1	NC-134	FROM NC 24/27 TO END C&G 760LF N OF LESLIE ST (NON-SYSTEM)	1	2	2WU	1.04	36	0	1.04	80	1,215		150	333	6			6	2	18	3	4							30	70
TOTAL FOR MAP NO. 1								**1.04**				**80**	**1,215**		**150**	**333**	**6**			**6**	**2**	**18**	**3**	**4**							**30**	**70**
2024CPT.08.09.10621	Montgomery	2	NC-134	FROM END C&G 760LF N OF LESLIE ST (NON-SYSTEM)TO SR 1324 (GLEN RD)	2	2	2WU	0.64	24	1.04	1.68			68								1										45
TOTAL FOR MAP NO. 2								**0.64**						**68**								**1**										**45**
2024CPT.08.09.10621	Montgomery	3	NC-109 BUS	FROM NC 134 TO NC 109 BUS (ELDORADO ST) NON-SYSTEM	1	2	2WU	0.24	24	12.81	13.05				100	62	4															16
TOTAL FOR MAP NO. 3								**0.24**							**100**	**62**	**4**															**16**
2024CPT.08.09.10621	Montgomery	4	NC-109	FROM SR 1138 (DAIRY RD) TO 1.12 MILES NW OF SR 1147 (CORRELL RD)	3	2	2WU	4.4	24	18.5	22.9															94,688						295
TOTAL FOR MAP NO. 4								**4.4**																		**94,688**						**295**
2024CPT.08.09.10621	Montgomery	5	US-220 ALT	FROM SR 1608 (WHISKEY RD) TO NC 211	3,4	2	2WU	2.9	27	0.2	3.1		880		120	295	6	12	8			6	3	4	2	65,865	880	295	27	120	20	312
TOTAL FOR MAP NO. 5								**2.9**					**880**		**120**	**295**	**6**	**12**	**8**			**6**	**3**	**4**	**2**	**65,865**	**880**	**295**	**27**	**120**	**20**	**312**
TOTAL FOR PROJ NO. 2024CPT.08.09.10621								**9.22**				**80**	**2,095**	**68**	**370**	**690**	**16**	**12**	**8**	**6**	**2**	**25**	**6**	**8**	**2**	**160,553**	**880**	**295**	**27**	**120**	**50**	**738**
												2,175						**36**				**49**									**788**	
2024CPT.08.09.20621	Montgomery	6	SR-1563 / LOVIN HILL RD	FROM PVMT JOINT 2291' FROM NC-731 TO END PVMT	2	2	2WU	0.63	21	0.43	1.06																					
TOTAL FOR MAP NO. 6								**0.63**																								
2024CPT.08.09.20621	Montgomery	7	SR-1358 / GAP RD	FROM MOORE CO. LINE TO US 220 ALT	2	2	2WU	0.79	18	0	0.79																					
TOTAL FOR MAP NO. 7								**0.79**																								
2024CPT.08.09.20621	Montgomery	8	SR-1137 / LANDFILL RD	FROM 1.24 MILES NORTH OF NC 24/27 TO SR 1134 (MT CARMEL CH RD)	5	2	2WU	1.47	22	1.24	2.71																					
TOTAL FOR MAP NO. 8								**1.47**																								
2024CPT.08.09.20621	Montgomery	9	SR-1003 / WINDBLOW RD	FROM LONG LEAF LN TO SR 1524 (BELFORD CH RD)	5	2	2WU	1.36	22	4.72	6.08																					
TOTAL FOR MAP NO. 9								**1.36**																								
TOTAL FOR PROJ NO. 2024CPT.08.09.20621								**4.25**																								
GRAND TOTAL								**13.47**				**80**	**2,095**	**68**	**370**	**690**	**16**	**12**	**8**	**6**	**2**	**25**	**6**	**8**	**2**	**160,553**	**880**	**295**	**27**	**120**	**50**	**738**
												2,175						**36**				**49**									**788**	