PROJECT NO.	SHEET NO.	TOTAL NO.
2024CPT.08.13.20761	13	

THERMOPLASTIC AND PAINT QUANTITIES

												4413000000-E	4457000000-N	4451000000-N	4685000000-E		4700000000-E	4704000000-E	4709000000-E	4720000000-E		4725000000-E					4810000000-E		4825000000-E	4830000000-E	4835000000-E	4840000000-N		4845000000-N					4905100000-N
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	WORK ZONE ADVANCE/ GENERAL WARNING SIGNING	TEMPORARY TRAFFIC CONTROL	LAW ENFORCEMENT	4" X 90 M WHITE THERMO	4" X 90 M YELLOW THERMO	12" X 90 M YELLOW THERMO	16" X 90 M WHITE THERMO	24" X 90 M WHITE THERMO	THERMO RXR 90 M	THERMO MSG SCHOOL 90 M	THERMO RT ARROW 90 M	THERMO LT ARROW 90 M	THERMO STR ARROW 90 M	THERMO 24" YIELD TRIANGLE	THERMO STR & RT ARROW 90 M	4" WHITE PAINT	4" YELLOW PAINT	12" YELLOW PAINT	16" WHITE PAINT	24" WHITE PAINT	PAINT MSG RXR	PAINT MSG SCHOOL	PAINT RT ARROW	PAINT LT ARROW	PAINT STR ARROW	PAINT YIELD LINETRIANGLE	PAINT STR & RT ARROW	NON-CAST IRON SNOWPLOW-ABLE PAVEMENT MARKER Y&Y
								MI	FT			SF	LS	HR	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA
2024CPT.08.13.20761	Randolph	1	SR-3118 / LINDA LN	FROM SR 1408 (HOOVER HILL RD) TO SR 3119 (MOUNTAIN VIEW DR)	1	2	2WU	0.536	21	0	0.536	61															2,852	2,852											
TOTAL FOR MAP NO. 1								**0.536**				**61**															**2,852**	**2,852**											
2024CPT.08.13.20761	Randolph	2	SR-1408 / HOOVER HILL RD	(FROM SR 1406 (COVERED BRIDGE RD) TO US 64	2	2	2WU	3.09	22	5.01	8.1	350															16,316	16,316											
TOTAL FOR MAP NO. 2								**3.09**				**350**															**16,316**	**16,316**											
2024CPT.08.13.20761	Randolph	3	SR-1858 / OLD MARLBORO RD	FROM SR 1526 (EDGAR RD) TO SR 1004 (HILLSVILLE RD)	1	2	2WU	2.412	20	0	2.412	271															12,725	12,725											
TOTAL FOR MAP NO. 3								**2.412**				**271**															**12,725**	**12,725**											
2024CPT.08.13.20761	Randolph	4	SR-1916 / WEANT RD	FROM GUILFORD COUNTY LINE TO SR 1917 (SUITS RD)	1	2	2WU	1.888	20	0	1.888	212															9,980	9,980											
TOTAL FOR MAP NO. 4								**1.888**				**212**															**9,980**	**9,980**											
2024CPT.08.13.20761	Randolph	5	SR-1565 / RONNIEDALE RD	FROM SR 1564 (MEADOWBROOK DR) TO SR 1566 (FAIRVIEW CHURCH RD)	1	2	2WU	1.242	21	0	1.242	140	*														6,548	6,548											
TOTAL FOR MAP NO. 5								**1.242**				**140**															**6,548**	**6,548**											
2024CPT.08.13.20761	Randolph	6	SR-1413 / MT VIEW CHURCH RD	FROM SR 1416 (OLD LEXINGTON RD) TO SR 1004 (CARAWAY MOUNTAIN RD)	1	2	2WU	2.25	20	0	2.25	225															11,880	11,880											
TOTAL FOR MAP NO. 6								**2.25**				**225**															**11,880**	**11,880**											
2024CPT.08.13.20761	Randolph	7	SR-1004 / ARCHDALE RD / HILLSVILLE RD.	FROM SR 1004 (TRINITY RD) TO SR 1858 (OLD MARLBORO RD)	1	2	2WU	3.96	36	2.04	6	481		120	46,049	46,875	315	100	150	4	12	2	16	5	7	1	46,049	46,875	315	100	150	4	12	2	16	5	7	1	484
TOTAL FOR MAP NO. 7								**3.96**				**481**		**120**	**46,049**	**46,875**	**315**	**100**	**150**	**4**	**12**	**2**	**16**	**5**	**7**	**1**	**46,049**	**46,875**	**315**	**100**	**150**	**4**	**12**	**2**	**16**	**5**	**7**	**1**	**484**
2024CPT.08.13.20761	Randolph	8	SR-1798 / ROELEE ST	FROM SR 1577 (ARCHDALE RD) TO END OF MAINTENANCE	2,3	2	2WU	0.3	24	0	0.3	80															2,479	2,479											
TOTAL FOR MAP NO. 8								**0.3**				**80**															**2,479**	**2,479**											
TOTAL FOR PROJ NO. 2024CPT.08.13.20761								**15.678**				**1,820**	**1**	**120**	**46,049.000**	**46,875**	**315**	**100**	**150**	**4**	**12**	**2**	**16**	**5**	**7**	**1**	**108,829**	**109,655**	**315**	**100**	**150**	**4**	**12**	**2**	**16**	**5**	**7**	**1**	**484**
															92,924.000					**16**				**31**				**218,484**					**16**				**31**		
GRAND TOTAL								**15.678**				**1,820**	**1**	**120**	**46,049.000**	**46,875**	**315**	**100**	**150**	**4**	**12**	**2**	**16**	**5**	**7**	**1**	**108,829**	**109,655**	**315**	**100**	**150**	**4**	**12**	**2**	**16**	**5**	**7**	**1**	**484**
															92,924					**16**				**31**				**218,484**					**16**				**31**		