


**ZONE 4 VEGETATION REMOVAL LIMITS**  
-185SBL- STA. 423+50 TO STA. 430+00 (LT)



**ZONE 5 VEGETATION REMOVAL LIMITS**  
-185SBL- STA. 430+00 TO US 15/US 501 SB (LT)

**ZONE 4 NOTES**

1. REMOVE ALL EXISTING VEGETATION INCLUDING TREES, SHRUBS, AND OVERHANGING LIMBS BETWEEN THE I-85 SOUTHBOUND EDGE OF PAVEMENT AND THE CROASDAILE DRIVE EDGE OF PAVEMENT. FILL, COMPACT, AND GRADE SMOOTH ANY GROUND VOIDS WITH EXCESS EARTH MATERIAL FROM RAMP WIDENING AREAS SHOWN IN THE TYPICAL SECTIONS. THIS WORK WILL BE PAID FOR UNDER "CLEARING AND GRUBBING". ANY ADDITIONAL EARTH MATERIAL REQUIRED TO FILL GROUND VOIDS WILL BE PAID FOR UNDER "BORROW EXCAVATION".
2. REMOVE AND REPLACE EXISTING I-85 SOUTHBOUND GUARDRAIL PER DETAIL A. DO NOT DISTURB EXISTING GUARDRAIL ALONG CROASDAILE DRIVE.
3. RESTORE DISTURBED SIDE SLOPES AND DITCHES TO EXISTING GRADE. REPLACE ANY CONCRETE ITEM OR RIP RAP DITCH LINING THAT IS DAMAGED DURING CONSTRUCTION. NO PAYMENT WILL BE MADE FOR THIS WORK AND IS CONSIDERED INCIDENTAL TO "CLEARING AND GRUBBING".
4. INSTALL EROSION CONTROL DEVICES PER THE EROSION CONTROL PLANS.
5. WORK IN ZONE 4 IS INCLUDED IN MAP 2 PAY ITEMS.

**ZONE 5 NOTES**

1. REMOVE ALL EXISTING VEGETATION INCLUDING TREES, SHRUBS, AND OVERHANGING LIMBS BETWEEN THE I-85 SOUTHBOUND EDGE OF PAVEMENT AND THE EXISTING CHAIN LINK FENCE (CONTROLLED ACCESS FENCE). FILL, COMPACT, AND GRADE SMOOTH ANY GROUND VOIDS WITH EXCESS EARTH MATERIAL FROM RAMP WIDENING AREAS SHOWN IN THE TYPICAL SECTIONS. THIS WORK WILL BE PAID FOR UNDER "CLEARING AND GRUBBING". ANY ADDITIONAL EARTH MATERIAL REQUIRED TO FILL GROUND VOIDS WILL BE PAID FOR UNDER "BORROW EXCAVATION".
2. REMOVE AND REPLACE EXISTING I-85 SOUTHBOUND GUARDRAIL PER DETAIL A. DO NOT DISTURB EXISTING GUARDRAIL ALONG CROASDAILE DRIVE OR ALONG US 15/US 501.
3. RESTORE DISTURBED SIDE SLOPES AND DITCHES TO EXISTING GRADE. REPLACE ANY CONCRETE ITEM OR RIP RAP DITCH LINING THAT IS DAMAGED DURING CONSTRUCTION. NO PAYMENT WILL BE MADE FOR THIS WORK AND IS CONSIDERED INCIDENTAL TO "CLEARING AND GRUBBING".
4. INSTALL EROSION CONTROL DEVICES PER THE EROSION CONTROL PLANS.
5. WORK IN ZONE 5 IS INCLUDED IN MAP 2 PAY ITEMS.

8/17/99

495807-2003 1642  
J.A. Boardman, P.E. | 1-5943-RDY | Detroit, MI