
ASSEMBLED BY : D.D. LOWERY CHECKED BY : C.T. POOLE

DRAWN BY: TLA 8/05 CHECKED BY: GM 9/05

DATE: 03/2023 DATE: 03/2023

MAA/KMM MAA/GM



PP 24 X 0.50 GALVANIZED STEEL PILE

NOTES

PIPE PILES SHALL BE IN ACCORDANCE WITH SECTION 1084 OF THE STANDARD SPECIFICATIONS.

GALVANIZE STEEL PIPE PILES IN ACCORDANCE WITH SECTION 1076 OF THE STANDARD SPECIFICATIONS UNLESS METALLIZING IS REQUIRED. GALVANIZING OR METALLIZING PIPE PILE PLATES IS NOT REQUIRED.

REMOVE AND REPLACE OR REPAIR TO THE SATISFACTION OF THE ENGINEER PILES THAT ARE DAMAGED, DEFORMED OR COLLAPSED DURING INSTALLATION OR DRIVING.

PILE SPLICES SHALL BE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS AND AWS D1.1.

FOR OPEN END PIPE PILES, REMOVE ENOUGH SOIL AND WATER FROM INSIDE THE PILES TO CONSTRUCT THE CONCRETE PLUG WITHOUT FOULING THE CONCRETE.

FORM THE CONCRETE PLUG SUCH THAT THE REINFORCING STEEL OR CONCRETE DOES NOT MOVE AND THE CLEARANCE FROM THE REINFORCING STEEL TO THE INSIDE OF THE PILE IS MAINTAINED AFTER CONCRETE PLACEMENT. DO NOT PLACE CONCRETE IN THE BENT CAP UNTIL THE CONCRETE PLUG HAS ATTAINED A MINIMUM COMPRESSIVE STRENGTH OF 1500 PSI.

THE REINFORCING STEEL, CLASS A CONCRETE, AND GALVANIZING ARE CONSIDERED INCIDENTAL TO THE CONTRACT UNIT PRICE BID PER LINEAR FOOT FOR PP 24 X 0.50 GALVANIZED STEEL PILES.

BILL OF MATERIAL FOR ONE PP 24 X 0.50 GALVANIZED STEEL PILE NO. SIZE TYPE LENGTH WEIGHT #4 S1 6'-0'' 24 100 V1 10 #6 6′-8′′

CLASS A CONCRETE

5'-0'' MINIMUM PLUG 0.5 CY

REINFORCING STEEL =

BAR TYPES

____1'-3'' LAP 5′-10′′ 1'-6'' ALL BAR DIMENSIONS ARE OUT TO OUT.

124

lbs

PROJECT NO. B-5156 PENDER COUNTY STATION: 22+90.50 -L-

> STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

> > STANDARD

24" STEEL PIPE PILE

421 Fayetteville Street, Suite 600 Raleigh, NC 27601-1772 Phone (919) 677-2000 NC LICENSE #

REVISIONS SHEET N S-38 DATE: DATE: NO. BY: BY: TOTAL SHEETS

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED