

REFERENCE: B-5156

PROJECT: 42331

CONTENTS

<u>SHEET NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND (SOIL & ROCK)
3	SITE PLAN
4	PROFILE(S)
5-9	CROSS SECTION(S)
10-14	BORE LOG(S)
15	SOIL TEST RESULT(S)
16	SITE PHOTOGRAPHS)

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY PENDER
 SITE DESCRIPTION REPLACE BRIDGE NO. 28 OVER
LONG CREEK ON NC 210 AT -L- 22+90.50

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	B-5156	1	16

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

M. DURWAY

CAROLINA DRILLING:

G. EISTER

S. MAYNARD

INVESTIGATED BY F&R, Inc.

DRAWN BY T.T. WALKER

CHECKED BY D. RACEY

SUBMITTED BY P. ALTON, P.E.

DATE AUGUST 2019

SINCE **Prepared in the Office of:**
F&R FROEHLING & ROBERTSON, INC.
 Engineering Stability Since 1881
 310 Hubert Street
 Raleigh, North Carolina 27603-2302 | USA
 T 919.828.3441 | F 919.828.5751
 www.fandr.com



DocuSigned by:

Patrick Alton





10/26/2022

A270EF78A687649



DATE

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**


**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT
SUBSURFACE INVESTIGATION
SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**

SOIL DESCRIPTION										GRADATION										ROCK DESCRIPTION										TERMS AND DEFINITIONS									
SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6										WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.										HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED, AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 60 BLOWS PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:  NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED.  FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.  FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.  COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.										ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRODUCED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS IN OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.									
SOIL LEGEND AND AASHTO CLASSIFICATION										ANGULARITY OF GRAINS										WEATHERING																			
GENERAL CLASS. GRANULAR MATERIALS (<= 35% PASSING #200) SILT-CLAY MATERIALS (> 35% PASSING #200) ORGANIC MATERIALS										THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.										FRESH ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE.																			
GROUP CLASS. A-1, A-1-b, A-3, A-2-4, A-2-5, A-2-6, A-2-7, A-4, A-5, A-6, A-7, A-1, A-2, A-3, A-4, A-5, A-6, A-7										MINERALOGICAL COMPOSITION										VERY SLIGHT (V SLI.) ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.																			
SYMBOL										MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.										SLIGHT (SLI.) ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.																			
% PASSING #10, #40, #200										COMPRESSION										MODERATE (MOD.) SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.																			
MATERIAL PASSING #40 LL, PI										COMPRESSIBILITY										SEVERE (SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. IF TESTED, WOULD YIELD SPT REFUSAL																			
GROUP INDEX										PERCENTAGE OF MATERIAL										VERY SEVERE (V SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. IF TESTED, WOULD YIELD SPT N VALUES > 100 BPF																			
USUAL TYPES OF MAJOR MATERIALS										GROUND WATER										COMPLETE ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.																			
GEN. RATING AS SUBGRADE										MISCELLANEOUS SYMBOLS										ROCK HARDNESS																			
PI OF A-7-5 SUBGROUP IS <= LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30										ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION, SOIL SYMBOL, ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT, INFERRED SOIL BOUNDARY, INFERRED ROCK LINE, ALLUVIAL SOIL BOUNDARY										VERY HARD CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.																			
CONSISTENCY OR DENSENESS										RECOMMENDATION SYMBOLS										HARD CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.																			
PRIMARY SOIL TYPE, COMPACTNESS OR CONSISTENCY, RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE), RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)										UNCLASSIFIED EXCAVATION - UNSUITABLE WASTE, UNCLASSIFIED EXCAVATION - ACCEPTABLE DEGRADABLE ROCK										MODERATELY HARD CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.																			
TEXTURE OR GRAIN SIZE										ABBREVIATIONS										MEDIUM CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PEICES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.																			
U.S. STD. SIEVE SIZE OPENING (MM), BOULDER (BLDR.), COBBLE (COB.), GRAVEL (GR.), COARSE SAND (CSE. SD.), FINE SAND (F. SD.), SILT (SL.), CLAY (CL.)										AR - AUGER REFUSAL, BT - BORING TERMINATED, CL - CLAY, CPT - CONE PENETRATION TEST, CSE. - COARSE, DMT - DILATOMETER TEST, DPT - DYNAMIC PENETRATION TEST, e - VOID RATIO, F - FINE, FOSS. - FOSSILIFEROUS, FRAC. - FRACTURED, FRACTURES, FRAGS. - FRAGMENTS, HL. - HIGHLY, MED. - MEDIUM, MICA - MICACEOUS, MOD. - MODERATELY, NP - NON PLASTIC, ORG. - ORGANIC, PMT - PRESSUREMETER TEST, SAP. - SAPROLITIC, SD. - SAND, SANDY, SL. - SILT, SILTY, SLL. - SLIGHTLY, TCR - TRICONE REFUSAL, w - MOISTURE CONTENT, V - VERY, VST - VANE SHEAR TEST, WEA. - WEATHERED, % - UNIT WEIGHT, % - DRY UNIT WEIGHT										SOFT CAN BE GROOVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.																			
SOIL MOISTURE - CORRELATION OF TERMS										EQUIPMENT USED ON SUBJECT PROJECT										VERY SOFT CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGERNAIL.																			
SOIL MOISTURE SCALE (ATTERBERG LIMITS), FIELD MOISTURE DESCRIPTION, GUIDE FOR FIELD MOISTURE DESCRIPTION										DRILL UNITS: CME-45C, CME-55, CME-550, VANE SHEAR TEST, PORTABLE HOIST, ADVANCING TOOLS: CLAY BITS, 6" CONTINUOUS FLIGHT AUGER, 8" HOLLOW AUGERS, HARD FACED FINGER BITS, TUNG-CARBIDE INSERTS, CASING w/ ADVANCER, TRICONE * STEEL TEETH, TRICONE 2 1/8" TUNG-CARB., CORE BIT, DRAG BIT 2 7/8", HAMMER TYPE: AUTOMATIC, MANUAL, CORE SIZE: B, H, N, HAND TOOLS: POST HOLE DIGGER, HAND AUGER, SOUNDING ROD, VANE SHEAR TEST										FRACTURE SPACING										BEDDING									
PLASTICITY																				TERM SPACING, VERY WIDE MORE THAN 10 FEET, WIDE 3 TO 10 FEET, MODERATELY CLOSE 1 TO 3 FEET, CLOSE 0.15 TO 1 FOOT, VERY CLOSE LESS THAN 0.16 FEET										TERM THICKNESS, VERY THICKLY BEDDED 4 FEET, THICKLY BEDDED 1.5 - 4 FEET, THINLY BEDDED 0.16 - 1.5 FEET, VERY THINLY BEDDED 0.03 - 0.16 FEET, THICKLY LAMINATED 0.008 - 0.03 FEET, THINLY LAMINATED < 0.008 FEET									
PLASTICITY INDEX (PI), PLASTIC RANGE (PI), OPTIMUM MOISTURE (OM), SHRINKAGE LIMIT (SL)																				INDURATION																			
COLOR																				FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.																			
DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-BROWN). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.																				FRIABLE RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.																			
																				MODERATELY INDURATED GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.																			
																				INDURATED GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.																			
																				EXTREMELY INDURATED SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.																			
																				BENCH MARK: TBM-5																			
																				N: 252313.098, E: 2293801.746										ELEVATION: 15.30 FEET									
																				NOTES:																			

PROJECT REFERENCE NO.	SHEET NO.
B-5156	3
SITE PLAN	
SKEW = 90°	




LONG CREEK PROPERTIES LLC



PROJECT REFERENCE NO.	SHEET NO.
B-5156	4
PROFILE BORINGS PROJECTED ALONG -L-	


- (A) **Roadway Embankment:** Very Loose to Loose, Moist to Saturated, Tan-Orange-Gray, Silty Fine to Coarse SAND (A-2-4) with Trace Gravel
- (B) **Alluvial:** Very Soft to Medium Stiff, Saturated, Brown, MUCK with Trace Gravel
- (C) **Alluvial:** Loose, Gray-Brown, Silty Fine to Coarse SAND (A-2-4) with Trace Organics
- (D) **Coastal Plain:** Medium Stiff to Stiff, Saturated, Dark Gray, Clayey Fine Sandy SILT (A-4) with Trace Organics (PEEDEE FORMATION)
- (E) **Coastal Plain:** Medium Dense to Dense, Wet to Saturated, Dark Gray, Clayey Fine SAND (A-2-6) (PEEDEE FORMATION)




22+00

23+00

24+00




PROJECT REFERENCE NO.	SHEET NO.
B-5156	5
CROSS SECTION THROUGH END BENT 1	
AT -L- STATION 21+88	
SKEW = 90°	




GROUNDLINE TAKEN FROM B5156_LS_TIN_170919.tin FILE PROVIDED BY NCDOT DATED 5/28/2019. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE CROSS SECTION


80 60 40 20 0 20 40 60 80




PROJECT REFERENCE NO.	SHEET NO.
B-5156	6
CROSS SECTION THROUGH BENT 1	
AT -L- STATION 22+33	
SKEW = 90°	



GROUNDLINE TAKEN FROM B5156_LS_TIN_170919.tin FILE PROVIDED BY NCDOT DATED 5/28/2019. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE CROSS SECTION




PROJECT REFERENCE NO.	SHEET NO.
B-5156	7
CROSS SECTION THROUGH BENT 2	
AT -L- STATION 22+78	
SKEW=90°	




GROUNDLINE TAKEN FROM: B5156_LS_TIN_170919.tin FILE PROVIDED BY NCDOT DATED 5/28/2019. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE CROSS SECTION


80 60 40 20 0 20 40 60 80




PROJECT REFERENCE NO.	SHEET NO.
B-5156	8
CROSS SECTION THROUGH BENT 3	
AT -L- STATION 23+43	
SKEW = 90°	



GROUNDLINE TAKEN FROM B5156_LS_TIN_170919.in FILE PROVIDED BY NCDOT DATED
5/28/2019. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH
BOTH PROJECTED ONTO THE CROSS SECTION



PROJECT REFERENCE NO.	SHEET NO.
B-5156	9
CROSS SECTION THROUGH END BENT 2	
AT -L- STATION 23+93	
SKEW = 90°	



(A) **Alluvial:** Loose, Gray-Brown, Silty Fine to Coarse SAND (A-2-4) with Trace Organics

EB2-C
23+93

SS-2

Roadway Embankment:
Very Loose to Loose, Moist to Saturated, Tan-Orange-Gray, Silty Fine to Coarse SAND (A-2-4) with Trace Gravel

Water Surface 02/06/2019
Ground Surface 07/19

Alluvial: Very Loose, Saturated, Brown, MUCK with Trace Gravel

Loose to Medium Dense, Saturated, Gray-Brown, Silty Fine to Coarse SAND (A-2-4) with Trace Gravel and Little Organics

Coastal Plain:

Loose to Medium Dense, Saturated to Wet, Gray-Dark Gray, Silty Fine SAND (A-2-4) and Clayey Fine SAND (A-2-6) (PEEDEE FORMATION)

Stiff to Hard, Wet, Gray-Dark Gray, Fine Sandy CLAY (A-6) (PEEDEE FORMATION)

Coastal Plain Sedimentary Rock: Hard, Friable, Dark Gray, MUDSTONE (PEEDEE FORMATION)

GROUNDLINE TAKEN FROM B5156_LS_TIN_170919.tin FILE PROVIDED BY NCDOT DATED 5/28/2019. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE CROSS SECTION

80 60 40 20 0 20 40 60 80

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 42331.1.2		TIP B-5156		COUNTY PENDER		GEOLOGIST M. Durway										
SITE DESCRIPTION Replace Bridge 28 over Long Creek on NC 210 at -L- 22+90.50							GROUND WTR (ft)									
BORING NO. EB1-B		STATION 21+84		OFFSET 43 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 16.6 ft		TOTAL DEPTH 133.1 ft		NORTHING 252,303		EASTING 2,293,587										
DRILL RIG/HAMMER EFF./DATE BRI0674 CME-45C 95% 06/12/2019			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER G. Eister		START DATE 07/10/19		COMP. DATE 07/11/19		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
20																
	16.6	0.0	3	3	3											16.6
15	13.6	3.0	1	1	1											
10	8.6	8.0	1	0	2											
5	3.6	13.0	1	0	1											
0	-1.5	18.0	1	2	3											
-5	-6.5	23.0	3	3	2											
-10	-11.5	28.0	7	6	8											
-15	-16.5	33.0	4	4	4											
-20	-21.5	38.0	5	5	7											
-25	-26.5	43.0	7	5	7											
-30	-31.5	48.0	7	8	10											
-35	-36.5	53.0	6	5	6											
-40	-41.5	58.0	6	5	6											
-45	-46.5	63.0	5	5	5											
-50	-51.5	68.0	4	5	5											
-55	-56.5	73.0	4	6	7											
-60																

WBS 42331.1.2		TIP B-5156		COUNTY PENDER		GEOLOGIST M. Durway										
SITE DESCRIPTION Replace Bridge 28 over Long Creek on NC 210 at -L- 22+90.50							GROUND WTR (ft)									
BORING NO. EB1-B		STATION 21+84		OFFSET 43 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 16.6 ft		TOTAL DEPTH 133.1 ft		NORTHING 252,303		EASTING 2,293,587										
DRILL RIG/HAMMER EFF./DATE BRI0674 CME-45C 95% 06/12/2019			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER G. Eister		START DATE 07/10/19		COMP. DATE 07/11/19		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
-60																
	-61.5	78.0	5	5	6											
-65	-66.5	83.0	6	5	8											
-70	-71.5	88.0	6	8	9											
-75	-76.5	93.0	6	9	9											
-80	-81.5	98.0	7	7	8											
-85	-86.5	103.0	9	10	14											
-90	-91.5	108.0	8	7	9											
-95	-96.5	113.0	14	16	18											
-100	-101.5	118.0	11	13	14											
-105	-106.5	123.0	6	5	6											
-110	-111.5	128.0	100/0.2													
-115	-116.5	133.0	60/0.1													

NCDOT BORE DOUBLE B-5156_GEO_BH_BRD0028.GPJ NC_DOT_GDT_8/27/19

SS-29 207%

Match Line

Gray-Dark Gray, Fine Sandy CLAY (A-6)
(PEEDEE FORMATION) (continued)

COASTAL PLAIN SEDIMENTARY ROCK
Dark Gray, MUDSTONE (PEEDEE FORMATION)

Boring Terminated at Elevation -116.6 ft in
SEDIMENTARY ROCK (COASTAL PLAIN)

Note:
Surficial Organic Soil: 0.0-0.3'

GEOTECHNICAL BORING REPORT

BORE LOG



WBS 42331.1.2		TIP B-5156		COUNTY PENDER		GEOLOGIST M. Durway	
SITE DESCRIPTION Replace Bridge 28 over Long Creek on NC 210 at -L- 22+90.50							GROUND WTR (ft)
BORING NO. B1-B		STATION 22+30		OFFSET 51 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 0.5 ft		TOTAL DEPTH 117.1 ft		NORTHING 252,297		EASTING 2,293,633	
DRILL RIG/HAMMER EFF./DATE BRI0674 CME-45C 95% 06/12/2019			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER G. Eister		START DATE 07/11/19		COMP. DATE 07/12/19		SURFACE WATER DEPTH 0.3ft	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
5															
0	0.5	0.0	WOH	WOH	WOH										
-5	-7.5	8.0	3	2	3										
-10	-10.5	11.0	4	2	2										
-15	-15.5	16.0	3	4	3										
-20	-20.5	21.0	5	5	10										
-25	-25.5	26.0	9	6	8										
-30	-30.5	31.0	6	10	12										
-35	-35.5	36.0	5	5	6										
-40	-40.5	41.0	5	6	7										
-45	-45.5	46.0	6	6	5										
-50	-51.5	52.0	5	5	5										
-55	-56.5	57.0	5	5	7										
-60	-61.5	62.0	5	5	6										
-65	-66.5	67.0	5	5	7										
-70	-71.5	72.0	6	6	9										
-75															

WBS 42331.1.2		TIP B-5156		COUNTY PENDER		GEOLOGIST M. Durway	
SITE DESCRIPTION Replace Bridge 28 over Long Creek on NC 210 at -L- 22+90.50							GROUND WTR (ft)
BORING NO. B1-B		STATION 22+30		OFFSET 51 ft RT		ALIGNMENT -L-	
COLLAR ELEV. 0.5 ft		TOTAL DEPTH 117.1 ft		NORTHING 252,297		EASTING 2,293,633	
DRILL RIG/HAMMER EFF./DATE BRI0674 CME-45C 95% 06/12/2019			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER G. Eister		START DATE 07/11/19		COMP. DATE 07/12/19		SURFACE WATER DEPTH 0.3ft	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-75															
-76.5	77.0	77.0	7	8	13										
-80	-81.5	82.0	5	8	8										
-85	-86.5	87.0	9	12	12										
-90	-91.5	92.0	8	7	8										
-95	-96.5	97.0	16	18	20										
-100	-101.5	102.0	15	15	15										
-105	-106.5	107.0	6	6	7										
-110	-111.5	112.0													
-115	-116.5	117.0	60/0.1												

NCDOT BORE DOUBLE B-5156_GEO_BH_BRD0028.GPJ NC_DOT_GDT_8/27/19



Note:
Driller indicates harder drilling from 112.0'-117.0'

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 42331.1.2		TIP B-5156		COUNTY PENDER		GEOLOGIST M. Durway										
SITE DESCRIPTION Replace Bridge 28 over Long Creek on NC 210 at -L- 22+90.50							GROUND WTR (ft)									
BORING NO. B2-B		STATION 22+78		OFFSET 50 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 0.0 ft		TOTAL DEPTH 122.5 ft		NORTHING 252,300		EASTING 2,293,681										
DRILL RIG/HAMMER EFF./DATE BRI0674 CME-45C 95% 06/12/2019			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER G. Eister		START DATE 07/15/19		COMP. DATE 07/16/19		SURFACE WATER DEPTH 1.8ft										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	ELEV. (ft)	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
0	0.0	0.0	1	1	1										0.0	0.0
-5																
-10	-8.0	8.0	6	4	4											
-15	-11.0	11.0	4	2	2											
-20	-16.0	16.0	2	2	2											
-25	-21.0	21.0	4	6	9											
-30	-26.0	26.0	5	6	8											
-35	-31.0	31.0	7	7	6											
-40	-36.0	36.0	6	6	6											
-45	-41.0	41.0	5	6	6											
-50	-46.0	46.0	4	4	4											
-55	-51.0	51.0	4	4	5											
-60	-56.0	56.0	5	5	9											
-65	-61.0	61.0	5	4	6											
-70	-66.0	66.0	5	7	7											
-75	-71.0	71.0	6	8	8											
-80	-76.0	76.0	6	7	7											



WBS 42331.1.2		TIP B-5156		COUNTY PENDER		GEOLOGIST M. Durway										
SITE DESCRIPTION Replace Bridge 28 over Long Creek on NC 210 at -L- 22+90.50							GROUND WTR (ft)									
BORING NO. B2-B		STATION 22+78		OFFSET 50 ft RT		ALIGNMENT -L-										
COLLAR ELEV. 0.0 ft		TOTAL DEPTH 122.5 ft		NORTHING 252,300		EASTING 2,293,681										
DRILL RIG/HAMMER EFF./DATE BRI0674 CME-45C 95% 06/12/2019			DRILL METHOD Mud Rotary			HAMMER TYPE Automatic										
DRILLER G. Eister		START DATE 07/15/19		COMP. DATE 07/16/19		SURFACE WATER DEPTH 1.8ft										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	ELEV. (ft)	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
-80	-81.0	81.0	7	8	13											
-85	-86.0	86.0	9	12	11											
-90	-91.0	91.0	7	7	8											
-95	-96.0	96.0	19	17	21											
-100	-101.0	101.0	11	12	12											
-105	-106.0	106.0	5	5	5											
-110	-111.0	111.0	100/0.2													
-115	-116.0	116.0	60/0.1													
-120	-121.0	121.0	6	6	10											

NCDOT BORE DOUBLE B-5156_GEO_BH_BRDG0028.GPJ NC_DOT_GDT_8/29/19

Boring Terminated at Elevation -122.5 ft in SAND (COASTAL PLAIN)
 Note:
 Driller indicates harder drilling from 111.0'-117.0'

GEOTECHNICAL BORING REPORT

BORE LOG



NCDOT BORE DOUBLE B-5156_GEO_BH_BRDG0028.GPJ NC_DOT_GDT_8/29/19

Note:
Driller indicates harder drilling from 108.0'-115.0'

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 42331.1.2		TIP B-5156		COUNTY PENDER		GEOLOGIST M. Durway	
SITE DESCRIPTION Replace Bridge 28 over Long Creek on NC 210 at -L- 22+90.50							GROUND WTR (ft)
BORING NO. EB2-C		STATION 23+93		OFFSET CL		ALIGNMENT -L-	
COLLAR ELEV. 2.7 ft		TOTAL DEPTH 118.7 ft		NORTHING 252,355		EASTING 2,293,794	
DRILL RIG/HAMMER EFF./DATE BRI0674 CME-45C 95% 06/12/2019			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER G. Eister		START DATE 07/09/19		COMP. DATE 07/09/19		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
5															
	2.7	0.0		4	4	5								2.7	GROUND SURFACE
0	-0.8	3.5	WOH	WOH	1								SS-2	96%	ALLUVIAL Gray-Brown, Silty Fine to Coarse SAND (A-2-4) with Trace Organics Brown, MUCK, with Trace Gravel
-5	-5.8	8.5		7	5	5							Sat.		Gray-Brown, Silty Fine to Coarse SAND (A-2-4) with Trace Gravel and Little Organics
-10	-10.8	13.5		3	2	4							Sat.		
-15	-15.8	18.5		3	4	4							Sat.		COASTAL PLAIN Gray-Dark Gray, Silty Fine SAND (A-2-4) (PEEDEE FORMATION)
-20	-20.8	23.5		6	8	10							Sat.		
-25	-25.8	28.5		7	9	12							Sat.		
-30	-30.8	33.5		7	7	8							Sat.		
-35	-35.8	38.5		7	8	7							Sat.		Gray-Dark Gray, Clayey Fine SAND (A-2-6) (PEEDEE FORMATION)
-40	-40.8	43.5		5	7	7							W		
-45	-45.8	48.5		5	5	7							W		
-50	-50.8	53.5		4	6	5							W		
-55	-55.8	58.5		5	7	8							W		
-60	-60.8	63.5		6	6	7							W		
-65	-65.8	68.5		6	8	8							W		
-70	-70.8	73.5		7	9	9							W		
-75													W		

WBS 42331.1.2		TIP B-5156		COUNTY PENDER		GEOLOGIST M. Durway	
SITE DESCRIPTION Replace Bridge 28 over Long Creek on NC 210 at -L- 22+90.50							GROUND WTR (ft)
BORING NO. EB2-C		STATION 23+93		OFFSET CL		ALIGNMENT -L-	
COLLAR ELEV. 2.7 ft		TOTAL DEPTH 118.7 ft		NORTHING 252,355		EASTING 2,293,794	
DRILL RIG/HAMMER EFF./DATE BRI0674 CME-45C 95% 06/12/2019			DRILL METHOD Mud Rotary		HAMMER TYPE Automatic		
DRILLER G. Eister		START DATE 07/09/19		COMP. DATE 07/09/19		SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
-75	-75.8	78.5		9	11	15									
-80	-80.8	83.5		7	7	10									
-85	-85.8	88.5		11	12	14									
-90	-90.8	93.5		7	7	10									
-95	-95.8	98.5		19	21	27									
-100	-100.8	103.5		14	14	12									
-105	-105.8	108.5		7	6	9									
-110	-110.8	113.5		100/0.3											
-115	-115.8	118.5		100/0.2											

Match Line

Gray-Dark Gray, Fine Sandy CLAY (A-6)
(PEEDEE FORMATION) (continued)

-109.3 COASTAL PLAIN SEDIMENTARY ROCK
Dark Gray-Gray, MUDSTONE (PEEDEE FORMATION)

-116.0 Boring Terminated at Elevation -116.0 ft in
SEDIMENTARY ROCK (COASTAL PLAIN)

Notes:
1. Surficial Organic Soil: 0.0-0.3'

Shelby tubes obtained in offset boring
23+91 (-L-) CL:
ST-1: 3.0'-5.0' (Not tested)
ST-2: 5.0'-7.0' (Tested)

NCDOT BORE DOUBLE B-5156_GEO_BH_BRDG0028.GPJ NC_DOT.GDT 8/28/19

**North Carolina Department of Transportation
Division of Highways
Materials and Test Unit
Soils Laboratory**

T.I.P. ID NO.: B-5156
DESCRIPTION: Replace Bridge 28 on NC 210 over Long Creek at -L- 22+90.50

REPORT ON SAMPLES OF: SOIL FOR QUALITY

F&R PROJECT #: 66X-0151
DATE SAMPLED: 7/19
SAMPLED FROM: -L-
SUBMITTED BY: P Alton

COUNTY: Pender
RECEIVED: 7/19
REPORTED: 8/19
BY: D. Council
Certification No.: 101-02-0603

TEST RESULTS

PROJ. SAMPLE NO.	SS-29	SS-67	SS-74	SS-2	ST-2								
BORING NO.	EB1-B	B2-B	B2-B	EB2-C	EB2-C								
Retained #4 Sieve %	NT	NT	0.0	NT	0.0								
Passing #10 Sieve %	NT	NT	100.0	NT	99.1								
Passing #40 Sieve %	NT	NT	100.0	NT	77.8								
Passing #200 Sieve %	NT	NT	62.5	NT	14.7								

SOIL MORTAR - 100%													
Coarse Sand Ret - #60 %	NT	NT	0.1	NT	32.0								
Fine Sand Ret - #270 %	NT	NT	65.5	NT	56.5								
Silt 0.053 - 0.010 mm %	NT	NT	17.5	NT	8.9								
Clay < 0.010 mm %	NT	NT	16.9	NT	2.6								
L.L.	ND	ND	27	ND	NP								
P.L.	ND	ND	23	ND	NP								
P.I.	ND	ND	4	ND	NP								
AASHTO Classification	ND	ND	A-4(1)	ND	A-2-4(0)								
Approximate Station	21+84	22+78	22+78	23+93	23+91								
Offset	43' RT	50' RT	50' RT	CL	CL								
Depth (ft)	18.0	0.0	46.0	3.5	5.0								
to	19.5	1.5	47.5	5.0	7.0								
Alignment	-L-	-L-	-L-	-L-	-L-								
Moisture Content (%)	206.5	82.7	24.8	95.6	66.2								
Organic Content (%)	43.4	19.3	1.9	10.3	30.4								

NP = Not plastic
NT = Not tested
ND = Not Determined
CL = Centerline

W.P. Alton, P.E.
Soils Engineer



Bridge No. 28 over Long Creek at -L- Station 22+90.50
SITE PHOTOGRAPHS



Photograph No. 1: View at existing Bent 3 looking northwest, drilling B2-B



Photograph No. 3: View looking west toward proposed End Bent 1



Photograph No. 2: View from existing End Bent 1 looking east at proposed End Bent 2



Photograph No. 4: View from existing End Bent 2 slope looking west toward proposed End Bent 1