

DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA

# **SOIL STABILIZATION TIMEFRAMES**

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

3/5/2024  
 X:\Raleigh\114-783\050 - B-5527 CE Update\05-CAD\B5527\Hydro\114-783\050.dgn  
 3/5/2024 8:17 AM  
 A. MORTON THOMAS AND ASSOCIATES, INC.