PROJECT REFERENCE NO.	SHEET NO.
B-4654	RW02D-1
Location and Surveys	

PROPOSED ALIGNMENT CONTROL SHEET

L

TYPE	STATION	NORTH	EAST
POT	10+00.00	711041.6865	2114998.9499
PC	15+40.67	711575.3957	2114912.4766
PRC	18+23.64	711848.2671	2114839.3933
PT	21+06.61	712121.1386	2114766.3101
PC	24+41.47	712451.6843	2114712.7540
PRC	27+24.44	712733.6722	2114695.9370
PT	30+07.41	713015.6601	2114679.1200
POT	36+26.95	713627.2298	2114580.0314

Y1

TYPE	STATION	NORTH	EAST
POT	10+00.00	713021.5154	2113186.6547
PC	10+13.16	713014.9790	2113198.0729
CS	16+74.59	712711.6138	2113785.6007
ST	18+74.59	712629.2192	2113967.8382
POT	38+17.44	711836.5435	2115741.6255

Y2

TYPE	STATION	NORTH	EAST
POT	10+00.00	711907.7882	2114551.7168
PC	12+13.65	711843.2558	2114755.3877
PT	12+87.20	711845.2384	2114827.5460
POT	12+99.35	711849.5393	2114838.9112

Y3

TYPE	STATION	NORTH	EAST
POT	10+00.00	712706.1975	2114299.8078
POT	12+21.82	712926.5966	2114274.7232

LPB

TYPE	STATION	NORTH	EAST
TS	10+00.00	712394.7041	2114588.2066
SC	11+44.00	712471.7141	2114468.0605
PT	14+97.75	712734.5626	2114580.7176
POT	16+13.48	712741.5518	2114696.2419

RPB

TYPE	STATION	NORTH	EAST
POT	10+00.00	712703.1770	2114175.0566
PC	10+31.70	712702.8429	2114206.7540
PRC	12+65.93	712727.7014	2114439.1207
PT	14+29.19	712750.7904	2114600.5592
POT	15+25.51	712756.6070	2114696.7009

RPC

TYPE	STATION	NORTH	EAST
POT	10+00.00	712275.9078	2114452.6536
PC	12+96.48	712073.9910	2114669.7477
PT	14+26.54	712021.4163	2114786.2086

RPD

TYPE	STATION	NORTH	EAST
PC	9+00.00	711984.8256	2115233.0796
PT	10+00.00	711999.3406	2115134.1753
PC	11+31.16	712011.8741	2115003.6085
PRC	13+48.87	712021.4163	2114786.2086
PT	15+66.58	712011.8741	2115003.6085

NOTES:

1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.

2. THE PROPOSED ALIGNMENT CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATINO REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

REVISIONS

6/2/99