PROJECT REFERENCE NO.	SHEET NO.
B-4654	EC-03A
R/W SHEET NO.	

Prepared in the Office of: AECOM NC FIRM LICENSE No: F-0342 5438 Wade Park Boulevard, Suite 200 Raleigh, NC 27607 +1-919-461-100

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	13+30	14+86	LT	330
5	-RPD-	12+00	12+50	RT	70
5	-LPB-	12+00	14+00	LT	280
5	-RPB-	12+00	14+50	LT	350
5	-RPB-	12+00	12+50	RT	275
5	-RPD-	11+20	12+00	LT	115
5	-DWR3-	10+50	11+00	LT	70
5	-DWR3-	10+50	11+00	RT	70
7	-RPB-	11+00	12+00	LT	140
			SUBTOTAL		1,700
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					9,975
			TOTAL		11,675
			SAY		11,700

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)

5/14/99

11:12:57 AM
R:\Environmental\Design\R4654_EC_EC03a.dgn