PROJECT: BR-0069

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SIGNING PLAN CASWELL COUNTY

LOCATION: BRIDGE NO.160001 OVER COUNTRY LINE CREEK ON US 158 /NC 86

APPROVED:

2/5/2024

DATE:

SEAL

SEAL

O23912

MONTH CAROLINA

4700 FALLS OF NEUSE ROAD, SUITE 300
RALEIGH, NORTH CAROLINA 27609
(9 19) 781-4626 VOICE (9 19) 78 1-4869 FAX (F-0 105)

UNLESS ALL SIGNATURES COMPLETED

SIGN-1

PROJECT REFERENCE NO.

BR-0069

PROJECT NOTES

1 DISPOSAL OF SIGN SYSTEM, U-CHANNEL

		SUMMARY OF QUANTITIES		
ITEM NO.		ITEM DESCRIPTION	QUANTITY	UNIT
DESC. NO.	SECT. NO.			
4025000000 4072000000 4096000000 4155000000	903 904	CONTRACTOR FURNISHED, TYPE D SIGN SUPPORTS, 3LB STEEL U-CHANNEL SIGN ERECTION, TYPE D DISPOSAL OF SIGN SYSTEM, U-CHANNEL	28.00 80.00 4 2	S.F. L.F. EA.

INDEX

SHEET NO.	DESCRIPTION
SIGN-1 SIGN-2	TITLE SHEET PROPOSED SIGN DESIGN
SIGN-3	SIGNING PLAN SHEETS

PLAN PREPARED BY: MOFFATT & NICHOL

TRENT HUFFMAN, PE PROJECT ENGINEER

ZITONG LIU, EI PROJECT DESIGN

PLAN REVIEWED BY: NCDOT SIGNING AND DELINEATION UNIT

GENERAL NOTES

- ·SIGNS FURNISHED BY CONTRACTOR.
- .ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- ·IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- ·ALL EXISTING SIGNS ON 'U' CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSTED OF UNLESS OTHERWISE NOTED ON PLANS.
- ·SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO. TITLE

904.10 ORIENTATION OF GROUND MOUNTED SIGNS 904.50 MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS