PROJECT REFERENCE NO.	SHEET NO.
R-2577A	RW29

Location and Surveys

PROJECT SURVEYOR

NORTH CAROLINA PROFESSIONAL SEAL L-3877 LAND SURVEYOR MICHAEL L. MOTSINGER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS

6/2/99

-Y5-
PI Sta 18+25.56
△ = 59° 56' 31.1" (LT)
D = 6° 01' 52.1"
L = 993.88'
T = 547.84'
R = 950.00'
SE= 0.03
DS= 35 MPH

-Y5A-
PI Sta 14+03.88
△ = 44° 22' 01.8" (RT)
D = 11° 27' 33.0"
L = 387.18'
T = 203.88'
R = 500.00'
SE= 0.04
DS= 35 MPH

NC GRID NAD 83 NA 2011

BOBBY BREWER
PAMELA P BREWER
DB 1908 PG 3481

BOBBIE H MILLER
DB 3133 PG 728
PB 8 PG 216

56
EDNA B HOWARD
DB 2740 PG 3508
PB 8 PG 216

ALLISON L. WESTMORELAND
DB 2798 PG 3559

LOUISE BEESON
DB 2530 PG 2460
PB 8 PG 216

SHERI RANDAZZO
DB 3335 PG 1825

JOSE A HERNANDEZ
ERIKA R HERNANDEZ
DB 3155 PG 589

58
EARL WATKINS
DB 3340 PG 1649

59
THELMA E ESQUIVEL
DB 2993 PG 3402

60
BRAYAN ELIACIT ALBERTO ALVAREZ
& JESSICA ALBERTO
DB 3650 PG 1073

TIE TO EXISTING
BEGIN CONSTRUCTION
-Y5A- POT Sta. 10+00.00

TIE TO EXISTING
BEGIN CONSTRUCTION
-Y5- POT Sta. 10+15.00

-Y5A-
N 24° 30' 02.4" E

SR 2396/OLD BELEWS CREEK RD 22' BST

EXISTING R/W

TO US HWY 158

S 9° 45' 51.4" E

-Y5A- PT Sta. 15+87.18

-Y5A- PC Sta. 12+00.00

-Y5- PC Sta. 12+77.72

N 68° 52' 04.2" E

-Y5A- POT Sta. 16+44.00=
-Y5- POC Sta. 17+90.00

COURTNEY R LILLY
DB 3245 PG 4202
PB 10 PG 117

52
EUGENE P HUDSON
JUANITA L HUDSON
DB 2447 PG 2737
PB 10 PG 117

61
WILLIAM RONALD VAUGHN
DB 1840 PG 708
PB 10 PG 117

WILLIAM RONALD VAUGHN
DB 1840 PG 708
PB 10 PG 117

62
BOBBY A WOLFINGTON
ROBIN V WOLFINGTON
DB 2084 PG 449
PB 8 PG 216

63
TIMOTHY O CREWS
KIMBERLY CREWS
DB 2995 PG 1713

MATCHLINE -Y5- STA. 19+75 SEE SHEET 10

I, Michael L. Motsinger, certify that the right of way and permanent easement monumentation for this project shown herein was completed under my direct and responsible charge from an actual survey made under my supervision: that all horizontal closures had a minimum ratio of precision of 1:10,000 (Class A). Field work was performed from March 2021 to November 2021, and all coordinates are based on NAD83/2011; That this survey was performed to meet the requirements of 21NCAC 56.1600 as applicable.

This 19th day of December, 2023.

DocuSigned by:
Michael L. Motsinger
FDB6FE70E23C40E...

Professional Land Surveyor L-3877

NORTH CAROLINA PROFESSIONAL SEAL L-3877 LAND SURVEYOR MICHAEL L. MOTSINGER

NOTES:

1. IF FURTHER INFORMATION REGARDING PROJECT CONTROL IS NEEDED PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.
2. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.
3. RIGHT OF WAY MONUMENTATION ESTABLISHED _____ TO _____ .

19-DEC-2023 14:50
S:\Winston\Ruth Computer\Rural\R2577A\Right of Way\Control Sheets_231214\Files Pulled 2023-12-13\R-2577A_rdy_psh29.dgn
bevington AT\S-328698