PROJECT REFERENCE NO.	SHEET NO.
R-2577A	SCP 41

FIBER OPTIC CABLE

MODIFIED SPLICE ENCLOSURE
FOR EXISTING CCTV
SHEET SCP 26

NEW PROPOSED SIGNAL TRUNKLINE TO 09–0912

24 FIBERS IN 2 BUFFER TUBES

BLUE

ORANGE

1 2 3 4 5 6 7 8 9 10 11 12

C C C C C C C C C C C C

C

EXISTING

EXISTING TRUNKLINE TO WEST

72 FIBERS IN 6 BUFFER TUBES

BLUE
ORANGE
GREEN
BROWN
SLATE
WHITE

EXISTING

EXISTING TRUNKLINE TO R–2577A TO EAST

72 FIBERS IN 6 BUFFER TUBES

BLUE
ORANGE
GREEN
BROWN
SLATE
WHITE

BUFFER TUBE
BUFFER TUBE
BUFFER TUBE
BUFFER TUBE

SPLICE TRAY

LEGEND

COLOR CODE TIA/EIA 598–A

(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA

C = CAP AND SEAL
X = FUSION SPLICE INDIVIDUAL FIBER
O = EXISTING SPLICE

BUFFER TUBE = EXPRESS ENTIRE BUFFER TUBE

SPLICE = SPLICE ENTIRE BUFFER TUBE COLOR TO COLOR

NOTES:

1. FIBER INTERCONNECT CENTER RACKS ARE SCHEMATIC ONLY, ACTUAL EQUIPMENT FORM MAY VARY.
2. UNUSED FIBERS LEFT COILED AND STORED IN SPLICE TRAY.
3. UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPLICE TRAY.
4. ETHERNET SWITCH TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING /ENSURING PROPER TERMINATION.
5. INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING:
   (1) SPLICE
   (2) DATE
   (3) COMPANY NAME
   (4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

   PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY, TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1–4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS TO THE ENGINEER.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

RK&K
P: (919) 878-9560
8601 Six Forks Road, Forum 1,Suite 700
Raleigh, North Carolina 27615-5960
NC License No. F-0112
Engineers | Construction Managers | Planners | Scientists
www.rkk.com
Responsive People | Creative Solutions

Prepared for the Offices of:
Traffic Engineering, Mobility and Safety Division
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
Intelligent Transportation Systems Section
750 N. Greenfield Pkwy., Garner, NC 27529

SCALE
N/A

SPLICE DETAILS

Division 09 Forsyth County Winston-Salem/ Walkertown

PLAN DATE: February 2024 REVIEWED BY: Porter Erickson-Jones

PREPARED BY: Haylee Townsend REVIEWED BY:

REVISIONS	INIT.	DATE

SEAL
NORTH CAROLINA PROFESSIONAL SEAL 056142 ENGINEER PORTER W. JONES

DocuSigned by: Porter Jones 2/12/2024
SIGNATURE DATE

CADD Filename:

2/12/2024
R-2577A_SCP_Splice Details.dgn
wjones