STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PAVEMENT MARKING PLAN HAYWOOD COUNTY

LOCATION: BRIDGE NO. 430174 OVER BIG CREEK ON SR 1332 (WATERVILLE ROAD)

14SP.20441.2 PMP_1 11/30/2023

PROJECT REFERENCE NO.

DOCUMENT NOT CONSIDERED FINAL

UNLESS ALL SIGNATURES COMPLETED

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C. DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.01	PAVEMENT MARKINGS - TWO LANE & MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES & MOUNTING
1262.01	GUARDRAIL END DELINEATION

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE

ROAD NAME: MARKER MARKING SR 1332 (WATERVILLE ROAD) THERMOPLASTIC

- B) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.
- C) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.
- D) REMOVE ALL RESIDUE AND SURFACE LAITANCE BY ACCEPTABLE METHODS AND TREAT WITH APPROVED PRIMER ON CONCRETE BRIDGE DECKS PRIOR TO PLACING THERMOPLASTIC PAVEMENT MARKING MATERIAL.

SCHEDULE

PAVEMENT MARKING

FINAL PAVEMENT MARKINGS

SYMBOL

DESCRIPTION

THERMOPLASTIC (4", 90 MIL)

WHITE EDGELINE

YELLOW DOUBLE CENTER

INDEX

SHEET NO.

DESCRIPTION

PMP - 1

PAVEMENT MARKING PLAN TITLE SHEET AND SCHEDULE

PMP-2

PAVEMENT MARKING DETAIL AND QUANTITIES

Prepared in the Office of: JOHNSON, MIRMIRAN, & THOMPSON, INC. 1318-F Patton Avenue Asheville NC, 28806

TRANSPORTATION ENGINEER LLOYD D. BROWN, P.E.

TRANSPORTATION ALEX FITZPATRICK **ENGINEER**

PROJ. REFERENCE NO. 14SP.20441.2 TIE TO PROJ. 14SP.20441.1 PAVEMENT MARKINGS BEGIN PROJECT 14SP.20441.2 -L- STA 10+45.00 T13 END PROJECT 14SP.20441.2 -L- STA 14+40.00 TIE TO EXIST. PAVEMENT MARKINGS -L- SR 1332 (WATERVILLE RD.) FINAL PAVEMENT MARKING SCHEDULE SCALE 1'' = 30'SYMBOL DESCRIPTION QUANTITY BREAKDOWN PAY ITEM TOTAL QUANTITY T1 1,190 FT 1,190 FT WHITE EDGELINE (4", 90 MIL) - THERMO T13 1,190 FT 1,190 FT YELLOW DOUBLE CENTER (4", 90 MIL) - THERMO 4685000000 - E APPROVED: Usyd D. Brown PAVEMENT MARKING DETAIL AND QUANTITIES

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED