STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
B-4926	X-1A

Approximate quantities only. Unclassified excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station TEMP. PVMT. L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
	PHASE IA (SUMMARY NO. 1)		
14+78.00	0	0	0
15+00.00	1	0	0
15+50.00	6	9	0
16+00.00	6	25	0
16+50.00	6	34	0
17+00.00	7	26	0
17+50.00	12	32	0
18+00.00	15	23	0
18+50.00	15	2	0
19+00.00	16	2	0
19+50.00	14	1	0
20+00.00	10	3	0
20+50.00	9	3	0
21+00.00	7	5	0
21+50.00	6	5	0
22+00.00	7	1	0
22+46.00	3	0	0

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
	PHASE IB (SUMMARY NO. 2)		
15+00.00	0	0	0
15+50.00	36	1	0
16+00.00	40	1	0
16+50.00	6	25	22
17+00.00	3	47	35
17+50.00	0	79	31
18+00.00	0	142	50
18+50.00	7	212	77
19+00.00	21	312	94
19+50.00	28	431	115
20+00.00	27	542	66
20+50.00	26	682	0
21+00.00	21	952	0
21+50.00	22	1302	0
22+00.00	28	1608	43
22+50.00	31	1901	188
22+75.00	17	1030	269

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
	PHASE IB (SUMMARY NO. 3)		
28+15.00	0	0	40
28+50.00	23	1672	56
29+00.00	33	1117	61
29+50.00	31	2170	94
30+00.00	27	1959	53
30+50.00	21	1820	176
31+00.00	22	1796	269
31+50.00	21	1693	230
32+00.00	20	1553	255
32+50.00	30	1390	177
33+00.00	35	1215	185

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
	PHASE IB (SUMMARY NO. 3) CONT.		
33+50.00	38	1178	282
33+92.00	33	1027	322

Station L RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
	PHASE IB (SUMMARY NO. 4)		
36+07.50	0	0	35
36+50.00	24	874	243
37+00.00	28	985	126
37+50.00	28	848	171
38+00.00	28	676	228
38+50.00	28	562	222
39+00.00	29	463	195
39+50.00	30	302	137
40+00.00	30	139	71
40+50.00	40	44	37
41+00.00	77	10	22
41+50.00	54	6	13
42+00.00	4	5	0
42+50.00	2	3	0
43+00.00	0	1	0

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
	PHASE II (SUMMARY NO. 5)		
15+00.00	0	0	0
15+50.00	4	1	0
16+00.00	6	2	0
16+50.00	3	6	0
17+00.00	1	41	0
17+50.00	183	56	0
18+00.00	426	58	0
18+50.00	489	87	0
19+00.00	630	108	0
19+50.00	839	117	0
20+00.00	923	113	0
20+50.00	469	55	0
21+00.00	174	86	0
21+50.00	554	120	0
22+00.00	894	45	0
22+50.00	1224	11	0
23+00.00	1417	0	0

Station DRV	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
11+58.04	0	0	0
12+00.00	452	169	0
12+29.88	436	138	0

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
	PHASE II (SUMMARY NO. 6)		
28+00.00	0	0	0
28+50.00	1358	0	0
29+00.00	1372	0	0
29+50.00	1164	0	0
30+00.00	1067	0	0
30+50.00	954	1	0
31+00.00	858	2	0
31+50.00	819	1	0
32+00.00	838	0	0
32+50.00	845	0	0
33+00.00	852	0	0
33+50.00	887	0	0
34+00.00	1027	0	0

Station L LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	UnderCut (cu. yd.)
	PHASE II (SUMMARY NO. 7)		
36+00.00	0	0	0
36+50.00	985	0	0
37+00.00	919	0	0
37+50.00	895	0	0
38+00.00	844	0	0
38+50.00	759	0	0
39+00.00	635	0	0
39+50.00	444	0	0
40+00.00	274	0	0
40+50.00	159	4	0
41+00.00	67	19	0
41+50.00	40	19	0
42+00.00	26	7	0
42+50.00	3	0	0
43+00.00	0	0	0