icrutcher Wr. V:NC/Structures/03/747-01 - B-4926 Lenoir 20 &34\Structures\Lenoir 20\Plans\40_009_B4926_SMU_F

SUMMARY OF PILE INFORMATION/INSTALLATION

(Blank entries indicate item is not applicable to structure)

End Don4/						Driven Piles			Predrilling for Piles*		ı	Drilled-In Piles	
End Bent/ Bent No, Pile(s) #-# (e.g., "Bent 1, Piles 1-5")	Factored Resistance per Pile TONS	Pile Cut-Off (Top of Pile) Elevation FT	Estimated Pile Lenth per Pile FT	Scour Critical Elevation FT	Min Pile Tip (Tip No Higher Than) Elev FT	Required Driving Resistance (RDR)** per Pile TONS	Total Pile Redrives Quantity EACH	Predrilling Length per Pile Lin FT	Predrilling Elevation (Elev Not To Predrill Below) FT	Maximum Predrilling Dia INCHES	Pile Excavation (Bottom of Hole) Elev FT	Pile Exc Not In Soil per Pile Lin FT	Pile Exc In Soil per Pile Lin FT
End Bent 1, Piles 1-8	110	32.04	40			150	4						
End Bent 2, Piles 1-8	110	32.94	50			150	4						

+ Nominal Downdrag Resistance +

Nominal Scour Resistance

Scour Resistance Factor

Factored Resistance + Factored Downdrag Load + Factored Dead Load

Dynamic Resistance Factor

PILE DESIGN INFORMATION

(Blank entries indicate item is not applicable to structure)

End Bent/ Bent No, Pile(s) #-# (e.g., "Bent 1, Piles 1-5")	Factored Axial Load per Pile TONS	Factored Downdrag Load per Pile TONS	Factored Dead Load* per Pile TONS	Dynamic Resistance Factor	Nominal Downdrag Resistance per Pile TONS	Nominal Scour Resistance per Pile TONS	Scour Resistance Factor (Default = 1.00)
End Bent 1, Piles 1-8	110			0.75			
End Bent 2, Piles 1-8	110			0.75			

*Factored Dead Load is factored weight of pile above the ground line.

SUMMARY OF DRILLED PIER INFORMATION/INSTALLATION

(Blank entries indicate item is not applicable to structure)

End Bent/ Bent No, Pier(s) #-# (e.g., "Bent 1, Piers 1-3")	Factored Resistance per Pier TONS	Minimum Pier Tip (Tip No Higher Than) Elevation FT	Required Tip Resistance per Pier TSF	Scour Critical Elevation FT	Minimum Drilled Pier Penetration Into Rock per Pier Lin FT	Drilled Pier Length per Pier Lin FT	Drilled Pier Length Not In Soil per Pier Lin FT	Drilled Pier Length In Soil per Pier Lin FT	Permanent Steel Casing Required? YES or MAYBE	Permanent Steel Casing Tip Elevation (Elev Not To Extend Casing Below) FT	Permanent Steel Casing Length* per Pier Lin FT
Bent 1, Piers 1-3	465	-63.0	5	-16.0		78.5			YES	-20.0	35.5
Bent 2, Piers 1-3	460	-59.0	5	-17.5		74.5			YES	-20.0	35.5
Bent 3, Piers 1-3	465	-61.0	5	-17.5		76.5			YES	-21.0	36.5
Bent 4, Piers 1-3	460	-61.5	5	-14.5		77.0			YES	-22.0	37.5
Bent 5, Piers 1-3	470	-62.5	5	-14.5		78.0			YES	-26.0	41.5

*Permanent Steel Casing Length equals the difference between the ground line or top of drilled pier elevation, whichever is higher, and the permanent casing tip elevation.

NOTES:

- 1. The Pile and Drilled Pier Foundation Tables are based on the bridge substructure design and foundation recommendations sealed by a North Carolina Professional Engineer (Chien-Ting Tang, 047389) on 4-26-2022.
- 2. Total Pile Driving Equipment Setup quantity (not shown in Pile Foundation Tables) equals the number of driven piles, i.e., the number of piles with a Required Driving Resistance.
- 3. The Engineer will determine the need for DPT Testing, Permanent Steel Casing, SPTs, CSL Testing, SID Inspections and PITs when these items may be required.

SUMMARY OF DPT/PILE ORDER LENGTHS

(Blank entries indicate item is not applicable to structure)

Dy	namic Pile Testi	Pile Order Lengths			
End Bent/ Bent No	DPT Testing Required? YES or MAYBE	DPT Test Pile Length FT	Total DPT Testing Quantity EACH	End Bent/ Bent No(s)	Pile Order Length Basis* EST or DPT
End Bent 1, Piles 1-8	YES	45			
End Bent 2, Piles 1-8	YES	55			
			2		

*EST = Pile order lengths from estimated pile lengths; DPT = Pile order lengths based on DPT testing. For groups of end bents/bents with pile order lengths based on DPT testing, the first end bent/bent no. listed for each group is the representative end bent/bent with the DPT.

SUMMARY OF PILE ACCESSORIES

(Blank entries indicate item is not applicable to structure)

Dina Dila	S			
Pipe Pile Plates Required? YES or MAYBE	Pipe Pile Cutting Shoes Required? YES	Pipe Pile Conical Points Required? YES	H-Pile Points Required? YES	Steel Pile Tips Required? YES
	Required? YES or	Pipe Pile Plates Pipe Pile Cutting YES or MAYBE Required?	Plates Pipe Pile Pipe Pile Cutting YES or MAYBE Pipe Pile Cutting Conical Points Required? Required?	Pipe Pile Plates Required? YES or MAYBE Pipe Pile Cutting Shoes Required? Pipe Pile Conical Points Points Required? Required? YES

SUMMARY OF DRILLED PIER TESTING

(Blank entries indicate item is not applicable to structure)

End Bent/ Bent No, Pier(s) #-# (e.g., "Bent 1, Piers 1-3")	Standard Penetration Test (SPT) Required? YES or MAYBE	Crosshole Sonic Logging (CSL) Required?* YES or MAYBE	Total CSL Tube Length (For All Tubes) per Pier Lin FT	Shaft Inspection Device (SID) Required? YES or MAYBE	Pile Integrity Test (PIT) Required′ MAYBE
Bent 1, Piers 1-3		Yes	320	Yes	
Bent 2, Piers 1-3		Yes	304	Yes	
Bent 3, Piers 1-3		Yes	312	Yes	
Bent 4, Piers 1-3		Yes	314	Yes	
Bent 5, Piers 1-3		Yes	318	Yes	
TOTAL QTY:		5	4704	5	

*CSL Tubes are required if CSL Testing is or may be required. The number of CSL Tubes per drilled pier is equal to one tube per foot of design pier diameter with at least 4 tubes per pier. The length of each CSL Tube is equal to the drilled pier length plus 1.5 ft.

PROJECT NO. B-4926

LENOIR COUNTY

STATION: 25+45.00 -L-

SHEET 5 OF 6


STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

RALEIGH

PILE AND DRILLED PIER FOUNDATION TABLES

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



		SHEET NO.				
0.	BY:	DATE:	NO.	BY:	DATE:	S1-5
			(F)			TOTAL SHEETS
2			₩			4.9

DWN. BY: WDC DATE: 03/2023 CHKD. BY: PRG DATE: 03/2023 DES. EGR. OF RECORD: PRG DATE: 03/2023