PROJECT NO.	SHEET NO.
HI-0017	3B-2

SUMMARY OF QUANTITIES - ROADWAY

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0000100000-N MOBILIZATION	0000400000-N CONSTRUCTION SURVEYING	0106000000-E BORROW EXCAVATION	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 2" MILLING	1308000000-E 1" TO 3" MILLING	1330000000-E INCIDENTAL MILLING
										MI	FT	LS	LS	CY	SMI	TON	SY	SY	SY
49988.3.1	Robeson	1	US 74 WB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24							52,715	
		2	US 74 EB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24							52,072	
TOTAL FOR MAP NO. 1										2.98								52,715	
TOTAL FOR MAP NO. 2										2.98								52,072	
GRAND TOTAL										5.96		1	1	10,450	12.35	11,395	375	104,787	7,475
												1	1	10,450	12.35	11,395	375	104,790	7,475
													TOTAL FOR DRAINAGE	5					
													PROJECT TOTAL	10,455					

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1491000000-E ASPHALT CONC BASE COURSE, TYPE B25.0C	1503000000-E ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1840000000-E MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	1880000000-E GENERIC PAVING ITEM - ASPHALT CONC SURFACE COURSE, TYPE S9.5C (WEDGING COURSE)	3030000000-E STEEL BEAM GUARDRAIL	3150000000-N ADDITIONAL GUARDRAIL POSTS
										MI	FT	TONS	TONS	TONS	TONS	LF	TONS	LF	EA
49988.3.1	Robeson	1	US 74 WB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24	6,440	65	6,395	682	32,600	240		
		2	US 74 EB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24	6,421	65	6,320	677	32,600	240		
TOTAL FOR MAP NO. 1										2.98		6,440	65	6,395	682	32,600	240		
TOTAL FOR MAP NO. 2										2.98		6,421	65	6,320	681	32,600	240		
GRAND TOTAL										5.96		12,861	130	12,715	1,363	65,200	480	6,787.5	15
												12,870	130	12,720	1,365	65,200	480	6,787.5	15

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	3210000000-N GUARDRAIL END UNITS, TYPE CAT-1	3287000000-N GUARDRAIL END UNITS, TYPE TL-3	3317000000-N GUARDRAIL ANCHOR UNITS, TYPE B-77	3360000000-E REMOVE EXISTING GUARDRAIL	3503000000-E WOVEN WIRE FENCE, 47" FABRIC	3509000000-E 4" TIMBER FENCE POSTS, 7'-6" LONG	3515000000-E 5" TIMBER FENCE POSTS, 8'-0" LONG
										MI	FT	EA	EA	EA	LF	LF	EA	EA
49988.3.1	Robeson	1	US 74 WB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24							
		2	US 74 EB 2" MILL	FROM THE SCOTLAND COUNTY LINE TO US 74 BUSINESS	1	2	2WD	NO	NO	2.98	24							
TOTAL FOR MAP NO. 1										2.98								
TOTAL FOR MAP NO. 2										2.98								
GRAND TOTAL										5.96		4	14	22	7,989	470	21	24
												4	14	22	7,989	470	21	24