| PROJECT NO. | SHEET NO. | TOTAL NO. |
|---|---|---|
| 45565.3.2 | 4 | |

# SUMMARY OF QUANTITIES

| | | | | | | | | | | | | | | 0000100000-N | 0106000000-E | 0318000000-E | 03210000000-E | 0335300000-E | 0995000000-E | 1220000000-E | 1245000000-E | 1260000000-E | 1330000000-E | 1519000000-E | 1575000000-E |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | BEGIN MP | END MP | MOBILIZATION | BORROW EXCAVATION | FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES | FOUNDATION CONDITIONING GEOTEXTILE | 18" DRAINAGE PIPE | PIPE REMOVAL | INCIDENTAL STONE BASE | SHOULDER RECONSTRUCTION | AGGREGATE SHOULDER BORROW | INCIDENTAL MILLING | ASPHALT CONC SURFACE COURSE, S9.5B | ASPHALT BINDER FOR PLANT MIX |
| | | | | | | | | | | MI | FT | | | LS | CY | TON | SY | LF | LF | TONS | SMI | TON | SY | TONS | TONS |
| 45565.3.2 | Dare | 1 | SR-1241 / EAGLE PASS RD | NC 12 TO NC 12 | 1 | 2 | 2WU | NO | NO | 0.767 | 20 | 0 | 0.767 | 1 | 160 | 100 | 180 | 80.00 | 40.00 | 400 | 1.52 | 5 | 450 | 1,675 | 110 |
| **TOTAL FOR PROJECT 45565.3.2 DETOUR RESURFACING** | | | | | | | | | | **0.767** | | | | | **160** | **100** | **180** | **80.00** | **40.00** | **400** | **1.52** | **5** | **450** | **1,675** | **110** |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| **GRAND TOTAL** | | | | | | | | | | **0.767** | | | | **1** | **160** | **100** | **180** | **80.00** | **40.00** | **400** | **1.52** | **5** | **450** | **1,675** | **110** |

# SUMMARY OF QUANTITIES

| | | | | | | | | | | | | | | 1693000000-E | 1880000000-E | 2286000000-N | 2364000000-N | 2591000000-E | 2845000000-N | 3649000000-E | 6000000000-E | 6037000000-E | 6071012000-E | 6084000000-E | 6117000000-N |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | BEGIN MP | END MP | ASPHALT PLANT MIX, PAVEMENT REPAIR | GENERIC PAVING ITEM, PATCHING EXISTING PAVEMENT (FULL DEPTH, 0-5") | MASONRY DRAINAGE STRUCTURES | FRAME WITH TWO GRATES, STD 840.16 | 4" CONCRETE SIDEWALK | ADJUSTMENT OF METER OR VALVE BOXES | RIP RAP, CLASS B | TEMPORARY SILT FENCE | COIR FIBER MAT | COIR FIBER WATTLE | SEEDING & MULCHING | RESPONSE FOR EROSION CONTROL |
| | | | | | | | | | | MI | FT | | | TON | TON | EA | EA | SY | EA | TON | LF | SY | LF | ACR | EA |
| 45565.3.2 | Dare | 1 | SR-1241 / EAGLE PASS RD | NC 12 TO NC 12 | 1 | 2 | 2WU | NO | NO | 0.767 | 20 | 0 | 0.767 | 130 | 19 | 1 | 1 | 45 | 1 | 15 | 4,210 | 200 | 20 | 0.8 | 1 |
| **TOTAL FOR PROJECT 45565.3.2 DETOUR RESURFACING** | | | | | | | | | | **0.767** | | | | **130** | **19** | **1** | **1** | **45** | **1** | **15** | **4,210** | **200** | **20** | **0.8** | **1** |
| | | | | | | | | | | | | | | | | | | | | | | | | | |
| **GRAND TOTAL** | | | | | | | | | | **0.767** | | | | **130** | **19** | **1** | **1** | **45** | **1** | **15** | **4,210** | **200** | **20** | **0.8** | **1** |

# THERMOPLASTIC AND PAINT QUANTITIES

| | | | | | | | | | | | | | | 4413000000-E | 4457000000-N | 4695000000-E | 4709000000-E | 4810000000-E | | 4820000000-E | 4835000000-E | 4890000000-E | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| PROJECT NO | COUNTY | MAP NO | ROUTE | DESCRIPTION | TYP NO | LANES | LANE TYPE | FINAL SURFACE TESTING REQUIRED | WARM MIX ASPHALT REQUIRED | LENGTH | WIDTH | BEGIN MP | END MP | WORK ZONE ADVANCE / GENERAL WARNING SIGNING | TEMPORARY TRAFFIC CONTROL | THERMO PAVEMENT MARKING LINES (8" 90 MILS) | THERMO PAVEMENT MARKING LINES (24" 90 MILS) WHITE | PAINT PAVEMENT MARKING LINES (4") WHITE | PAINT PAVEMENT MARKING LINES (4") YELLOW | PAINT PAVEMENT MARKING LINES (8") | PAINT PAVEMENT MARKING LINES (24") | GEN PAVEMENT MARKING ITEM, THERMO HOT SPRAY LINES (4" 55 MILS) WHITE | GEN PAVEMENT MARKING ITEM, THERMO HOT SPRAY LINES (4" 55 MILS) YELLOW |
| | | | | | | | | | | MI | FT | | | SF | LS | LF | LF | LF | LF | LF | LF | LF | LFT |
| 45565.3.2 | Dare | 1 | SR-1241 / EAGLE PASS RD | FROM NC 12 TO NC 12 | 1 | 2 | 2WU | NO | NO | 0.767 | 20 | 0 | 0.767 | 264 | 1 | 160 | 200 | 8,100 | 8,100 | 160 | 200 | 8,100 | 8,100 |
| **TOTAL FOR PROJECT 45565.3.2 DETOUR RESURFACING** | | | | | | | | | | **0.767** | | | | **264** | **1** | **160** | **200** | **8,100** | **8,100** | **160** | **200** | **8,100** | **8,100** |
| | | | | | | | | | | | | | | | | | | **16,200** | | | | **16,200** | |
| | | | | | | | | | | | | | | | | | | | | | | | |
| **GRAND TOTAL** | | | | | | | | | | **0.767** | | | | **264** | **1** | **160** | **200** | **8,100** | **8,100** | **160** | **200** | **8,100** | **8,100** |
| | | | | | | | | | | | | | | | | | | **16,200** | | | | **16,200** | |