

PROJECT NO.	SHEET NO.	TOTAL NO.
49218.16, 49218.17 49218.18, ETC.	20	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	BEGIN MP	END MP	1704000000-E	1814500000-E	1838000000-E	1838500000-N	1840000000-E	3030000000-E	3045000000-E	3150000000-N	3195000000-N	3287000000-N	3360000000-E	3628000000-E	3656000000-E	6000000000-E	6009000000-E	6012000000-E			
														PATCHING EXISTING PAVEMENT	ASPHALT SURFACE TREATMENT, SINGLE SEAL	EMULSION FOR ASPHALT SURFACE TREATMENT	VACUUM TRUCK	MILLED RUMBLE STRIPS	STEEL BEAM GUARDRAIL	STEEL BEAM GUARDRAIL, SHOP CURVED	ADDITIONAL GUARDRAIL POSTS	GUARDRAIL END UNITS, TYPE AT-1	GUARDRAIL END UNITS, TYPE TL-3	REMOVE EXISTING GUARDRAIL	RIP RAP, CLASS I	GEOTEXTILE FOR DRAINAGE	TEMPORARY SILT FENCE	STONE FOR EROSION CONTROL, CLASS B	SEDIMENT CONTROL STONE			
														MI	FT	TONS	SY	GAL	WK	LF	LF	LF	EA	EA	EA	LF	TON	SY	LF	TON	TON	
49218.16	Hoke	1	KING ROAD	FDR - FROM MORGANTON RD TO INTERSECTION REALIGNMENT LIMITS (STA. 13+73.24)	1,2	2	2WU	NO	NO	7.17	28	0.07	7.24	75	108,767.00	38,068	5.00	113,752														
49218.16	Hoke	1	KING ROAD	INTERSECTION REALIGNMENT (KING RD AT PLANK RD)	3	2	2WU	NO	NO	0.07	28	0	0.07					930						90.00			500	65.00	25			
TOTAL FOR MAP NO. 1										7.24				75	108,767.00	38,068	5.00	114,682					90.00	880	1,800.00	1,000	130.00	50				
TOTAL FOR PROJ NO. 49218.16										7.24				75	108,767.00	38,068	5.00	114,682					90.00	880	1,800.00	1,000	130.00	50				
49218.17	Hoke	2	MORGANTON ROAD	RESURFACING - FROM CJ EAST OF INTERSECTION OF SR 2074 (FORT BRAGG RD) TO CJ AT INTERSECTION WITH MANCHESTER RD.	5	2	2WU	NO	NO	0.58	24	0	0.58	25																		
TOTAL FOR MAP NO. 2										0.58				25																		
TOTAL FOR PROJ NO. 49218.17										0.58				25																		
49218.18	Hoke	3	MORRISON BRIDGE ROAD	RESURFACING - FROM END OF STATE MAINTENANCE TO MANCHESTER RD	7	2	2WU	NO	NO	0.58	24	0	0.58																			
TOTAL FOR MAP NO. 3										0.58																						
TOTAL FOR PROJ NO. 49218.18										0.58																						
49218.23	Hoke	4	PLANK ROAD	RESURFACING AND WIDENING - FROM 800' EAST OF CL OF NC HWY 211 TO CJ EAST OF KING ROAD	4	2	2WU	NO	NO	0.42	32	3.74	4.16	60																		
TOTAL FOR MAP NO. 4										0.42				60																		
TOTAL FOR PROJ NO. 49218.23										0.42				60																		
49218.24	Cumberland, Hoke	5	MANCHESTER ROAD	RESURFACING - FROM LAMONT RD TO C.J. WEST OF BLUES RD	8	2	2WU	NO	NO	5.03	32	0	5.03	110				79,675														
TOTAL FOR MAP NO. 5										5.03				110				79,675														
49218.24	Hoke	6	MANCHESTER ROAD	FDR - FROM CJ WEST OF BLUES RD TO CJ EAST OF MORGANTON RD	6	2	2WU	NO	NO	10.61	24	0	10.61		186,883.00	65,409	10.00	168,062	2,275.00	50.00	5.00	1.00	7.00	2,625.00		500	75.00	30				
TOTAL FOR MAP NO. 6										10.61					186,883.00	65,409	10.00	168,062	2,275.00	50.00	5.00	1.00	7.00	2,625.00		500	75.00	30				
TOTAL FOR PROJ NO. 49218.24										15.64					110	186,883.00	65,409	10.00	247,737	2,275.00	50.00	5.00	1.00	7.00	2,625.00		500	75.00	30			
49218.25	Hoke	7	ATF ROAD	PAVEMENT MARKINGS - FROM KING RD TO C.J.		2	2WU	NO	NO	0.9	24	0	0.9																			
TOTAL FOR MAP NO. 7										0.9																						
TOTAL FOR PROJ NO. 49218.25										0.9																						
GRAND TOTAL										25.36				270	295,650.00	103,477	15.00	362,419	2,275.00	50.00	5.00	1.00	7.00	2,781.00	880	1,800.00	1,500	205.00	80			