
ASSEMBLED BY : J.I.KIMBLE CHECKED BY : T.H.ORR


DRAWN BY: TLA 10/05 REV. 12/17 REV. 06/19 REV. 07/23

DATE : 10/2023 DATE : 10/2023

MAA/THC

BNB/THC





SECTION THRU SLAB

## NOTES

FOR BRIDGE APPROACH FILL, SEE ROADWAY PLANS.

APPROACH SLAB SHALL NOT BE CONSTRUCTED PRIOR TO COMPLETION OF THE BRIDGE DECK.

AREA BETWEEN THE WINGWALL AND APPROACH SLAB SHALL BE GRADED TO DRAIN THE WATER AWAY FROM THE FILL FACE OF THE BRIDGE AND SHALL BE PAVED. SEE ROADWAY PLANS.

THE JOINT OPENING AT THE APPROACH SLAB/DECK INTERFACE SHALL BE SAWED NO MORE THAN 12 HOURS AFTER THE APPROACH SLAB IS CAST. THE JOINT SHALL BE CLEANED OF ALL DEBRIS BEFORE THE SEALANT IS APPLIED. THE JOINT SEALER MATERIAL SHALL CONFORM TO THE REQUIREMENTS OF SECTION 1028-3 OF THE STANDARD SPECIFICATIONS.


AT THE CONTRACTORS OPTION "TYPE 1A - ALTERNATE APPROACH FILL" (ROADWAY STD. 423.02) MAY BE CONSTRUCTED AT NO ADDITIONAL COST TO THE DEPARTMENT IN LIEU OF "TYPE 1 - APPROACH FILL".


FOR ONE APPROACH SLAB (2 REQ'D)								
3AR	NO.	SIZE	TYPE	LENGTH	WEIGHT			
÷ A1	52	4	STR	22′-3″	773			
Α2	52	4	STR	22'-1"	767			
÷ B1	85	5	STR	24'-2"	2,142			
B2	85	6	STR	24'-8"	3,149			

BILL OF MATERIAL

REINFORCING STEEL	3,916 LBS.
* EPOXY COATED REINFORCING STEEL	2,915 LBS.
CLASS AA CONCRETE	46.5 C.Y.

SPLICE LENGTHS							
BAR SIZE	EPOXY COATED	UNCOATED					
#4	1'-11"	1'-7"					
#5	2'-5"	2'-0"					
#6	3'-7"	2'-5"					





**DOCUMENT NOT CONSIDERED FINAL** 

**UNLESS ALL SIGNATURES COMPLETED** 

PROJECT NO. U-5108 MECKLENBURG \_ COUNTY STATION: 74+01.00 -L-

SHEET 1 OF 2

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

STANDARD

BRIDGE APPROACH SLAB FOR INTEGRAL ABUTMENT WITH FLEXIBLE PAVEMENT

	SHEET NO.				
BY:	DATE:	NO.	BY:	DATE:	S-32
		(R)			TOTAL SHEETS
		셯			33

