

AS-BUILT REPAIR QUANTITY TABLE

TOP OF DECK REPAIRS

UNDERSIDE OF DECK REPAIRS


QUANTITIES IN TABLE REPRESENT ESTIMATED VALUES OF CLASS II SURFACE PREPARATION AND CONCRETE DECK REPAIR FOR POLYMER OVERLAY AFTER REMOVAL OF UNSOUND CONCRETE (MIN. 2" CLEAR TO SAW CUT). SEE OVERLAY SURFACE PREPARATION FOR POLYMER CONCRETE SPECIAL PROVISION.

CLASS II SURFACE PREPARATION

UNDERSIDE REPAIR

TEST LOCATION

SPAN L			APPROACH SLAB AT END BENT 2			SHOTCRETE REPAIRS			
	ESTIMATE	ACTUAL		ESTIMATE	ACTUAL	ESTIMATE		ACTUAL	
	AREA SF	VOLUME CF		AREA SF	VOLUME CF	AREA SF	VOLUME CF	AREA SF	VOLUME CF
SCARIFYING BRIDGE DECK	199.1	SY	SCARIFYING BRIDGE DECK	61.3	SY				
SHOTBLASTING OF BRIDGE DECK	199.1	SY	SHOTBLASTING OF BRIDGE DECK	61.3	SY				
CLASS II SURFACE PREPARATION	5.1	SY	CLASS II SURFACE PREPARATION	2.6	SY				
EPOXY RESIN INJECTION	0.0	LF	EPOXY RESIN INJECTION	0.0	LF				
GROOVING BRIDGE FLOORS	1660.9	SF	GROOVING BRIDGE FLOORS	508.8	SF				
CONCRETE DECK REPAIR FOR PC OVERLAY	5.1	SY	CONCRETE DECK REPAIR FOR PC OVERLAY	2.6	SY				
POLYMER CONCRETE MATERIALS	5.5	CY	POLYMER CONCRETE MATERIALS	1.7	CY				
PLACING AND FINISHING POLYMER CONCRETE OVERLAY	199.1	SY	PLACING AND FINISHING POLYMER CONCRETE OVERLAY	61.3	SY				
SURFACE PREPARATION FOR SILANE BARRIER RAIL TREATMENT	272.7	SF	SURFACE PREPARATION FOR SILANE BARRIER RAIL TREATMENT	0.0	SF				
SILANE BARRIER RAIL TREATMENT	272.7	SF	SILANE BARRIER RAIL TREATMENT	0.0	SF				
						ESTIMATE		ACTUAL	
						0.0	LF		



PLAN OF SPAN L


NOTES

REPAIR LOCATIONS AND ESTIMATED QUANTITIES ARE GIVEN WITH THE BEST INFORMATION AVAILABLE. IF ADDITIONAL REPAIRS NOT SHOWN ON THE DRAWINGS ARE DEEMED NECESSARY BY THE ENGINEER, THE ENGINEER WILL NOTE ON THE DRAWINGS THE APPROXIMATE LOCATIONS AND DESCRIPTION OF THE REPAIRS AND ADJUST THE ACTUAL QUANTITIES ENTERED INTO THE AS-BUILT REPAIR QUANTITY TABLE.

FOR SECTIONS E-E AND F-F, SEE "JOINT REPAIR DETAILS" SHEET.

TEST LOCATION	* CONCRETE COVER (INCH)	CONCRETE STRENGTH (PSI)
#10	2 5/8"	6940

INFORMATION IN CHART TAKEN FROM DECK EVALUATION DATED 6/01/2022.



4/24/2024

PROJECT NO. 15BPR.130
CHATHAM COUNTY
 BRIDGE NO. 180477

SHEET 6 OF 6

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

SUPERSTRUCTURE PLAN OF SPAN L

RIGHT LANE (NBL)

DRAWN BY : T. MAZARURA DATE : 8/2022
 CHECKED BY : D. GLADDEN DATE : 9/2022

22-APR-2024 16:23
 *****DCN*****
 brent.bornhill AT C-1001568

VOLKERT

5430 Wade Park Blvd., Suite 410
 Raleigh, NC 27607
 Tel: 919-854-0344 Fax: 919-854-0355
 NC License No. F-0762

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-54
1			3			TOTAL SHEETS
2			4			156

DOCUMENT NOT CONSIDERED
 FINAL UNLESS ALL
 SIGNATURES COMPLETED