DocuSign Envelope ID: 53439949-7A8E-4C6E-A80B-0CB5A7242039

PROJECT REFERENCE NO.	SHEET NO.
U-5809	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

SLOPE MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	L	10+50	11+00	RT	106
4	L	19+50	20+00	RT	123
5	L	32+00	32+15	LT	28
5	L	33+79	34+00	LT	45
6	Y5	11+50	12+00	LT	138

DITCHLINE STRAW MATTING FOR EROSION CONTROL

4	L	16+25	16+85	LT	70
4	L	16+85	17+30	LT	55
4	RPB	11+00	12+50	RT	445
4	RPC	11+00	11+96	RT	285
5	Y3	11+35	12+50	LT	135
6	Y4	11+00	12+50	RT	200
6	Y4	12+50	13+60	RT	150
6	Y5	14+00	14+50	RT	70
6	Y5	15+50	16+85	LT	105

DITCHLINE EXCELSIOR MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	RPA	11+50	13+50	LT	590
4	RPA	11+50	14+50	RT	745
4	RPC	11+00	11+96	LT	285
5	Y2	11+64	11+64	RT	50
6	Y5	14+50	14+89	RT	55
			SLOPE MATTING SUBTOTAL		440
			DITCHLINE STRAW MATTING SUBTOTAL		1,515
			DITCHLINE EXCELSIOR MATTING SUBTOTAL		1,725
	MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER				9,935
				TOTAL	13,615
				SAY	13,615

DITCHLINE PSRM FOR EROSION CONTROL

	NONE				