I–2513AA

PIPE REHABILITATION CIPP LINER

SURVEY LINE	STATION	LOC. LT/RT	STRUCTURE NUMBER	
			FROM	TO
Y	86+85	RT	0810	e804
Y	86+85	RT	e805	0812
*Y	39+33 to 42+36	MED	e518	e602
*Y	42+36 to 43+00	MED	e602	e604

*May require CIPP Liner, to be determined after pipe cleanout.

PIPE CLEANOUTS

SURVEY LINE	STATION	LOC. LT/RT	STRUCTURE NUMBER	
			FROM	TO
Y	39+33 to 42+36	MED	e518	e602
Y	42+36 to 43+00	MED	e602	e604
Y	43+00 to 43+09	LT	e604	e605
Y	43+09 to 41+22	LT	e605	e606
Y	86+85		0810	e804
Y	86+85	LT	e805	0812

I–2513AB

SUMMARY OF BASIN COMPONENT ITEMS
(for Stormwater BMP's)

ITEM DESCRIPTION	UNIT	QUANTITY		
		BASIN 2A	BASIN 2B	PROJECT TOTALS
MASONRY DRAINAGE STRUCTURE	EA	0	1	1
RISER TRASH RACK	EA	0	1	1
POLYPROPYLENE NONWOVEN GEOTEXTILE FABRIC	SY	211	198	409
WASHED NO. 57 STONE	TON	72	71	143
UNDERDRAIN PIPE – 6" HDPE PERFORATED	LF	106	104	210
UNDERDRAIN PIPE – 6" HDPE NONPERFORATED	LF	15	18	33
6" HDPE CROSS	EA	1	1	2
6" x 6" x 6" HDPE TEE	EA	2	2	4
6" HDPE 45–DEGREE BEND	EA	0	1	1
6" CLEANOUT	EA	5	6	11
ENGINEERED SOIL MEDIA	CY	130	125	255
6" CLEANOUT CAP (THREADED)	EA	5	6	11
ZOYSIA SOD	SY	400	350	750
RIPRAP FOR SPILLWAY CL. I	TON	11	11	22
RIPRAP FOR FOREBAY CL. I	TON	14	14	28
6" HDPE	LF	30	0	30
8" HDPE	LF	0	190	190
18" SIDE DRAIN PIPE	LF	0	48	48
PVC/HDPE DRAINAGE STRUCTURE	EA	1	1	2
RIP RAP OUTLET PAD CL. B	TON	0	2	2
GEOTEXTILE FOR DRAINAGE	SY	30	37	67

PIPE REHABILITATION CIPP LINER

SURVEY LINE	STATION	LOC. LT/RT	STRUCTURE NUMBER	
			FROM	TO
RPDB	16+80	LT	e1202	e1203

12/06/07
2/26/2024
12:06:42 PM
Barr, Smith
2D_02_Qty.psh, 02D_08.dgn